Ontario Provincial Standards for Roads and Public Works



- Volume 3 -

MUNICIPAL AND PROVINCIAL COMMON

DRAWINGS FOR ROADS, BARRIERS, DRAINAGE,
SANITARY SEWERS, WATERMAINS,
AND STRUCTURES

Ontario

OPS is co-owned by the
Ministry of Transportation, Ontario
and the
Municipal Engineers Association

Municipal
Engineers
Association

MANUAL REVISION RECORD

Volume 3 – Drawings for Roads, Barriers, Drainage, Sanitary Sewers, Watermains, and Structures

This record should remain in the manual at all times. Revisions are numbered sequentially. This sheet should be filled in after each revision has been placed into the manual. It will quickly indicate to users whether the contents of the manual are up-to-date.

REVISION NUMBER	REVISION DATE	ENTERED BY	REVISION NUMBER	DATE	ENTERED BY
51	April 2005	Included in new manuals	75	April 2019	Included in new manuals
52	Nov 2005	Included in new manuals	76	Nov 2019	Included in new manuals
53	Nov 2006	Included in new manuals	77	Nov 2020	Included in new manuals
54	April 2007	Included in new manuals	78	Apr 2021	Included in new manuals
55	Nov 2007	Included in new manuals	79	Nov 2021	Included in new manuals
56	April 2008	Included in new manuals	80	Apr 2022	Included in new manuals
57	Nov 2008	Included in new manuals	81	Nov 2022	Included in new manuals
58	Nov 2009	Included in new manuals	82		
59	April 2010	Included in new manuals	83		
60	Nov 2010	Included in new manuals	84		
61	April 2011	Included in new manuals	85		
62	Nov 2011	Included in new manuals	86		
63	Nov 2012	Included in new manuals	87		
64	April 2013	Included in new manuals	88		
65	Nov 2013	Included in new manuals	89		
66	Nov 2014	Included in new manuals	90		
67	April 2015	Included in new manuals	91		
68	Nov 2015	Included in new manuals	92		
69	April 2016	Included in new manuals	93		
70	Nov 2016	Included in new manuals	94		
71	April 2017	Included in new manuals	95		
72	Nov 2017	Included in new manuals	96		
73	April 2018	Included in new manuals	97		
74	Nov 2018	Included in new manuals	98		

DATE	OPSD	REV.	TITLE
DIVISION 100 - ABBREVIATIONS			
2010 11	100.010	4	Abbreviations, General A-C
2006 11	100.011	1	Abbreviations, General D-J
2009 11	100.012	2	Abbreviations, General L-R
2009 11	100.013	4	Abbreviations, General S-W
2006 11	100.050	1	Abbreviations, Building Descriptions
2006 11	100.060	1	Abbreviations, Geotechnical
2006 11	101.010	1	Topography Plan Features, Monument Features
2006 11	101.011	1	Topography Plan Features, Ground Features
2006 11	101.012	1	Topography Plan Features, Road Features
2006 11	101.013	1	Topography Plan Features, Barrier and Vegetation Features
2006 11	101.014	1	Topography Plan Features, Utility Features
2006 11	101.015	1	Topography Plan Features, Drainage Features
2006 11	101.016	1	Topography Plan Features, Miscellaneous Features
2008 11	101.017	3	Topography Plan Features, Right-of-Way Features
2006 11	102.010	1	Removals, Legend
2006 11	103.010	1	New Construction, Legend 1
2008 04	103.011	2	New Construction, Legend 2
2007 11	104.010	0	Miscellaneous Symbols
DIVISION 200 - GRADING			
2009 11	200.010	2	Earth/Shale Grading, Undivided Rural
2009 11	200.020	2	Earth/Shale Grading, Divided Rural
2009 11	201.010	2	Rock Grading, Undivided Rural
2009 11	201.020	2	Rock Grading, Divided Rural
2016 11 (R2021)	202.010	3	Slope Flattening Using Surplus Excavated Material on Earth or Rock Embankment
2013 11	202.020	3	Drainage Gap for Slope Flattening on Rock or Granular Embankment
2016 11 (R2021)	202.031	1	Roadway Widening for Steel Beam Energy Attenuating Terminal Approach End
2016 11	202.032	1	Roadway Widening for Steel Beam Energy Attenuating Terminal Leaving End and Constrained Approach End

DATE	OPSD	REV.	TITLE
2016 11	202.033	1	Roadway Widening, Single Sided Energy Attenuating Terminals, Approach End
2017 11	202.037	0	Roadway Widening for Steel Beam Terminal on Inside of Curve
2017 11	202.038	0	Roadway Widening for Steel Beam Terminal on Outside of Curve
2018 04	202.040	0	Roadway Widening for High Tension Cable Terminals, Slope Installation
2018 04	202.041	0	Roadway Widening for High Tension Cable Terminals, Shoulder Installation
2017 11 (R2022)	203.010	4	Embankments Over Swamp, New Construction
2017 11 (R2022)	203.020	4	Embankments Over Swamp, Existing Slope Excavated
2017 11 (R2022)	203.030	4	Embankments Over Swamp, Existing Slopes Maintained
2022 11	203.040	5	Embankments Over Swamp at Culverts ≤ 1500 mm
2015 11 (R2019)	204.010	3	Boulder Treatment, Cut Sections - Subgrade
2016 11 (R2022)	205.010	3	Transition Treatment, Earth Cut to Earth Fill
2016 11 (R2022)	205.020	3	Transition Treatment, Rock Cut to Rock Fill
2016 11 (R2022)	205.030	3	Transition Treatment, Rock Cut to Earth Fill
2016 11 (R2022)	205.040	3	Transition Treatment, Earth Fill to Rock Fill and Earth Fill to Granular Fill
2016 11 (R2022)	205.050	3	Transition Treatment, Rock Cut to Earth Cut
2019 11	205.060	4	Frost Heave Treatment
2018 11	206.010	2	Granular Courses, Undivided Rural
2018 11	206.020	2	Granular Courses, Divided Rural
2018 11	206.050	2	Subdrain Pipe, Connection and Outlet, Rural
2016 11 (R2021)	207.010	3	Concrete Pavement on Open Graded Drainage Layer, Divided Highway
2016 11 (R2021)	207.020	3	Composite Pavement on Open Graded Drainage Layer, Divided Highway
2016 11 (R2021)	207.030	2	Concrete and Composite Pavement on Open Graded Drainage Layer, Urban Section
2016 11 (R2021)	207.041	4	Subdrain Pipe, Open Graded Drainage Layer, Hot Mix Asphalt, Concrete, or Composite Pavement
2016 11 (R2021)	207.044	5	Subdrain Pipe, Connection and Outlet, Open Graded Drainage Layer
2019 04	208.010	4	Benching of Earth Slopes
2018 11	209.010	2	Rural Pavement Widening
2018 11	209.011	3	Rural Pavement Widening, Curb with Gutter

DATE	OPSD	REV.	TITLE
2016 11 (R2022)	209.020	3	Widening Existing Rock Cut with Grade Rise
2018 11	210.010	2	Tangent Shoulders, Rural
2018 11	210.020	2	Superelevated Shoulders, Rural
2016 11	210.070	4	Granular Sealing
2018 11	211.010	3	Partially Paved Shoulders, Existing Pavement Maintained
2018 11	211.020	3	Partially Paved Shoulders, Existing Pavement Resurfaced
2018 11	212.010	2	Resurfacing with Crossfall Correction with Hot Mix Asphalt, Tangent Section
2018 11	212.020	2	Resurfacing with Crossfall Correction with Hot Mix Asphalt, Superelevated Section
2018 11	212.030	2	Resurfacing, Existing Crossfall Maintained
2022 04	213.010	1	Pavement Widening on Curves, Widening On Both Sides of Curve With or Without Spirals
2022 04	213.020	1	Pavement Widening on Curves, Widening on Inside of Curves with or Without Spirals
2016 11 (R2021)	214.010	2	Single-Lane Ramp Grading for Asphalt Pavement with Granular Base and Shoulder
2016 11 (R2021)	214.020	2	Single-Lane Ramp Grading for Asphalt Pavement with Granular Base and Asphalt Shoulder
2016 11 (R2021)	214.030	3	Single-Lane Ramp Grading for Asphalt Pavement with Granular Base, Asphalt Shoulder, and Curb with Gutter
2016 11 (R2021)	215.010	2	Two-Lane Ramp Grading for Asphalt Pavement with Granular Base and Asphalt Shoulder
2016 11 (R2021)	215.020	2	Two-Lane Ramp Grading for Asphalt Pavement with Granular Base, Asphalt Shoulder, and Curb with Gutter for Tangent Section
2016 11 (R2021)	215.030	3	Two-Lane Ramp Grading for Asphalt Pavement with Granular Base, Asphalt Shoulder, and Curb with Gutter for Superelevated Section
2017 11	216.010	2	Boulevard Treatments, Urban Section
2017 11	216.020	2	Hot Mix, Concrete, and Composite Pavement On Granular Base, Urban Section
2017 11	216.021	3	Subdrain Pipe, Connection and Outlet, Urban Section
2011 11	217.050	2	Access to Hydrant Across Ditch
2011 11	217.060	2	Utility Pole Setting Depth at Ditch Locations
2021 11	219.100	3	Light-Duty Straw Bale Barrier
2021 11	219.110	3	Light-Duty Silt Fence Barrier

DATE	OPSD	REV.	TITLE
2021 11	219.120	1	Light-Duty Fibre Roll Barrier
2021 11	219.130	3	Heavy-Duty Silt Fence Barrier
2021 11	219.131	1	Heavy-Duty Wire-Backed Silt Fence Barrier
2015 11 (R2021)	219.150	2	Sandbag Barrier
2021 11	219.160	1	Fibre Roll Grade Breaks
2021 11	219.180	3	Straw Bale Flow Check Dam
2021 11	219.191	1	Fibre Roll Flow Check Dams
2022 11	219.200	3	Sandbag Flow Check Dam
2022 11	219.210	3	Temporary Rock Flow Check Dam, V-Ditch
2021 11	219.211	3	Temporary Rock Flow Check Dam, Flat Bottom Ditch
2015 11 (R2021)	219.220	2	Sediment Trap in Ditch
2015 11 (R2021)	219.230	4	Temporary Slope Drain for Sediment Trap
2022 11	219.231	2	Temporary Berm Barrier for Slope Drain
2015 11	219.240	2	Sediment Trap for Dewatering
2022 11	219.260	3	Turbidity Curtain
2022 11	219.261	3	Turbidity Curtain, Seam Detail
2019 11	220.010	1	Barrier for Tree Protection
2021 11	221.010	1	Temporary Water Passage System, Culvert in Watercourse
2021 11	221.020	1	Temporary Water Passage System, Pumping and Piping
2021 11	221.030	1	Temporary Flow Passage System, Temporary Channel or Culvert Outside Watercourse
2021 11	221.040	1	Temporary Waterbody Crossing, Fill and Culvert
2022 04	222.010	2	Rootwad Structures
2022 11	222.020	1	Large Woody Debris
2022 11	222.030	1	Stone LUNKERS
2022 11	222.040	1	Wood LUNKERS
2014 11	222.050	0	Riffles on Streambeds
2017 11	222.060	1	Pools in Streambeds
2014 11	222.070	0	Rocky Ramps on Streambeds
2014 11	222.080	0	Low Flow Channel
2017 11	222.100	0	Local Vegetation Blocks
2018 11	222.110	0	Live Fascines
2018 11	222.120	0	Live Stakes

DATE	OPSD	REV.	TITLE
2018 11	222.130	0	Brush Mattress
2018 11	222.140	0	Brush Layers
DIVISION 300 - ENTRANCES			
2018 11	300.010	3	Side Road Intersection, Fill
2018 11	300.020	3	Side Road Intersection, Cut
2010 11	301.010	2	Rural Entrances to Roads on Fill
2010 11	301.020	2	Rural Entrances to Roads in Earth Cut
2010 11	301.030	2	Rural Entrance, Rock Cut
2015 11 (R2022)	302.010	2	Median Crossovers for Service and Emergency Vehicles
2018 11	304.010	2	Shoulder Treatment, Sideroad Intersections
2019 11	310.010	3	Concrete Sidewalk
2019 11	310.020	3	Concrete Sidewalk Adjacent to Curb with Gutter
2015 11 (R2019)	310.030	1	Concrete Sidewalk Ramps at Signalized Intersections
2015 11 (R2019)	310.031	0	Concrete Sidewalk Ramps at Signalized Intersections with Intersecting Crosswalks
2019 11	310.033	0	Concrete Sidewalk Ramps at Unsignalized Intersections
2019 11	310.039	1	Concrete Sidewalk Ramps Tactile Walking Surface Indicators Component
2019 11	310.040	3	Utility Isolation in Concrete Sidewalks
2019 11	310.050	3	Concrete Sidewalk Driveway Entrance Details
2015 11 (R2019)	310.060	2	Joint Detail for Concrete Pedestrian Crosswalk at Signalized and All-Way Stop Controlled Intersections
2018 11	350.010	2	Urban Industrial, Commercial, and Apartment Entrances
2018 11	351.010	2	Urban Residential Entrance
DIVISION 400 - FRAMES AND GRATES			
2018 11	400.001	2	Hoisting Hook Rib for Cast Iron Frames for Catch Basins, Maintenance Holes, and Valve Chambers
2018 11	400.010	3	Cast Iron, Square Frame with Square Overflow Type Dished Grate for Catch Basins, Herring Bone Openings
2018 11	400.020	3	Cast Iron, Square Frame with Square Flat Grate for Catch Basins, Herring Bone Openings
2018 11	400.021	1	Cast Iron, Square Frame for Curb Inlet Overflow
2018 11	400.030	3	Cast Iron, Square Frame with Square V Grate for Catch Basins, Herring Bone Openings

DATE	OPSD	REV.	TITLE
2018 11	400.040	3	Cast Iron, One-Piece Frame and Flat Square Grate for Temporary Installation, Herring Bone Openings
2019 11	400.050	0	Cast Iron, Square Frame, Fish Type Cover
2018 11	400.070	6	Cast Iron, Raised Square Frame with Circular Flat Grate for Catch Basins, Herring Bone Openings
2018 11	400.080	4	Cast Iron, Side Inlet for Catch Basins
2018 11	400.081	3	Cast Iron, Curb Inlet Frame with Two-Piece Raised Cover for Catch Basins Out of Roadway
2019 11	400.082	5	Cast Iron, Raised Curb Inlet Frame with Cover for Catch Basins Out of Roadway
2018 11	400.090	3	Cast Iron, Curb Inlet Overflow for Catch Basins
2018 11	400.100	3	Cast Iron, Square Frame with Square Flat Grate for Catch Basins, Perforated Openings
2018 11	400.110	3	Cast Iron, Square Frame with Square Overflow Type Flat Grate for Catch Basins, Perforated Openings
2018 11	400.120	3	Cast Iron, Square Frame with Birdcage Grate for Catch Basins
2018 11	401.010	4	Cast Iron, Square Frame with Circular Closed or Open Cover for Maintenance Holes
2018 11	401.020	4	Cast Iron, Circular Frame with Circular 745 mm Cover for Maintenance Holes
2018 11	401.030	4	Cast Iron, Square Frame with Circular Watertight Cover for Maintenance Holes
2018 11	401.040	5	Cast Iron, Raised Square Frame with Circular Closed or Open Cover for Maintenance Holes
2018 11	401.050	5	Cast Iron, Raised Square Frame with Circular Watertight Cover for Maintenance Holes
2018 11	401.060	4	Cast Iron, Circular Locking Cover for Maintenance Holes
2019 11	401.080	1	Cast Iron, Curb Inlet, Fish Type Cover for Catch Basins Out of Roadway
2019 11	402.010	4	Cast Iron, Square Frame with Circular Cover and Plug for Valve Chambers
2019 11	402.011	4	Cast Iron, Square Frame with Vented Circular Cover and Plug for Valve Chambers
2019 11	402.020	5	Cast Iron, Raised Square Frame with Circular Cover and Plug for Valve Chambers
2019 11	402.021	4	Cast Iron, Raised Square Frame with Vented Circular Cover and Plug for Valve Chambers

DATE	OPSD	REV.	TITLE
2019 11	402.030	5	Cast Iron, Rectangular Frame with Two Piece Cover for Meter and Valve Chambers
2017 11 (R2022)	403.010	3	Galvanized Steel, Honey Comb Grating for Ditch Inlets
2017 11	403.011	1	Raised Bar Grate for Ditch Inlet, 600 x 600 mm
2018 11	404.010	2	Aluminum Safety Platform and Ladder for Rectangular Precast Concrete Valve Chambers
2018 11	404.020	4	Aluminum Safety Platform for Circular Maintenance Holes
2018 11	404.021	3	Aluminum Safety Platform for 1500 mm Diameter Circular Maintenance Holes with Drop Pipe
2018 11	404.022	3	Aluminum Safety Platform for 1800 mm Diameter Circular Maintenance Holes with Drop Pipe
2018 11	405.010	4	Maintenance Hole Steps, Hollow
2018 11	405.020	4	Maintenance Hole Steps, Solid
2018 11	406.010	3	Aluminum Ladder for Maintenance Holes
DIVISION 500 - PAVING			
2018 11	500.010	1	Turning Basins for Terminated Rural Roadways
2018 11	500.020	1	Turning Basins for Terminated Urban Roadways, Residential
2018 11	500.030	1	Turning Basins for Terminated Urban Roadways, Industrial and Commercial
2018 11	501.010	2	Bus Bays
2018 11	502.010	2	Access Lanes for Rear Lots
2011 11 (R2019)	503.010	1	Concrete Ripple Strip
2012 11 (R2019)	504.010	1	Raised Traffic Island
2018 11	506.010	2	Hot Mix Resurfacing Treatment at Structure Approaches
2015 11 (R2021)	508.010	2	Routing and Sealing Cracks Up to 20 mm Width in Asphalt Pavement
2018 11	508.020	3	Sealing or Resealing of Joints and Cracks in Concrete Pavement and Concrete Base
2020 11	509.010	3	Pavement Reinstatement for Utility Cuts
2018 11	514.010	2	Extruded Expanded Polystyrene Frost Heave Treatment, 25 mm Thickness
2018 11	514.020	2	Extruded Expanded Polystyrene Frost Heave Treatment, 40 mm Thickness
2017 11	551.010	2	Concrete and Composite Pavement Joint Spacing
2017 11	551.020	2	Concrete and Composite Pavement Joint Layout at Converging or Diverging Lanes

DATE	OPSD	REV.	TITLE
2017 11	551.030	3	Concrete and Composite Pavement Skewed Joint Layout at Intersections
2017 11	551.031	3	Concrete and Composite Pavement Right Angle Joint Layout at Intersections
2017 11	551.032	3	Concrete and Composite Pavement Utility Isolation
2017 11	552.010	2	Concrete Pavement Joint Details
2017 11	552.020	2	Composite Pavement Joint Details
2017 11	552.050	3	Load Transfer Device, Skewed Contraction Joint, Concrete or Composite Pavement
2017 11	552.051	3	Load Transfer Device, Right Angle Contraction Joint, Concrete or Composite Pavement
2017 11	552.060	3	Load Transfer Device, Skewed Expansion Joint, Concrete or Composite Pavement
2017 11	552.061	3	Load Transfer Device, Right Angle Expansion Joint, Concrete or Composite Pavement
2017 11	553.010	2	Concrete Pavement in Gore Areas
2017 11	553.020	2	Composite Pavement in Gore Areas
2017 11	554.010	2	Concrete Pavement Shoulder Terminal
2017 11	554.020	2	Composite Pavement Shoulder Terminal
2017 11	555.010	2	Concrete Pavement Approach Treatment to Hot Mix and Composite Pavements and Structure Approaches
2017 11	555.020	2	Composite Pavement Approach Treatment to Hot Mix and Concrete Pavements and Structure Approaches
2018 11	560.010	6	Composite or Exposed Concrete Pavements, Full Depth Concrete Slab Repair Layout
2018 11	560.020	3	Exposed Concrete Pavement, Full Depth Concrete Slab Repair, Joint Details
2017 11	560.025	1	Concrete Pavement and Concrete Base, Cross-Stitching Longitudinal Cracks
2018 11	560.030	2	Composite Pavement, Full Depth Concrete Slab Repair, Joint Details
2018 11	560.040	2	Partial Depth Repairs in Concrete Pavement
2016 11 (R2020)	561.010	2	Interlocking Concrete Pavers on Granular Base
2016 11 (R2020)	561.020	2	Interlocking Concrete Pavers on Concrete or Asphalt Base
2016 11 (R2020)	561.030	2	Interlocking Concrete Pavers for Retrofit Crosswalk Installation

DATE	OPSD	REV.	TITLE
DIVISION 600 - CURBS AND GUTTERS			
2012 11 (R2019)	600.010	2	Concrete Barrier Curb with Wide Gutter
2019 11	600.011	0	Concrete Barrier Curb with Wide Gutter and Wide Back
2019 11	600.061	0	Concrete Semi-Mountable Curb with Wide Gutter and Narrow Back
2012 11 (R2019)	600.020	2	Concrete Semi-Mountable Curb with Wide Gutter
2012 11 (R2019)	600.030	2	Concrete Mountable Curb with Wide Gutter
2012 11 (R2019)	600.040	2	Concrete Barrier Curb with Standard Gutter
2012 11 (R2019)	600.060	2	Concrete Semi-Mountable Curb with Standard Gutter
2012 11 (R2019)	600.070	2	Concrete Barrier Curb with Standard Gutter, Two Stage Construction
2012 11 (R2019)	600.080	2	Concrete Barrier Curb with Narrow Gutter
2012 11 (R2019)	600.090	2	Concrete Semi-Mountable Curb with Narrow Gutter
2012 11 (R2019)	600.100	2	Concrete Mountable Curb with Narrow Gutter
2012 11 (R2019)	600.110	2	Concrete Barrier Curb
2013 11 (R2020)	601.010	2	Asphalt Curb and Asphalt Curb with Gutter
2012 11 (R2019)	603.020	2	Precast Concrete Curb
2012 11 (R2019)	604.010	2	90° Concrete Outlet for Concrete Curb with Gutter
2013 11 (R2019)	604.020	2	90° Asphalt Outlet for Asphalt Curb with Gutter
2012 11 (R2020)	605.010	2	45° Concrete Outlet for Concrete Curb with Gutter
2013 11 (R2020)	605.020	2	30° and 45° Asphalt Outlets for Asphalt Curb with Gutter
2012 11 (R2020)	605.030	2	45° Concrete Outlet for Concrete Curb with Gutter at End of Run
2013 11 (R2020)	605.040	2	Asphalt Spillways
2012 11 (R2019)	606.010	2	600 mm Radius Barrier Bullnose
2012 11 (R2019)	606.020	2	600 mm Radius Mountable Bullnose
2012 11 (R2019)	606.030	2	800 mm Radius Bullnose, Curb with Gutter Twin Inlet
2012 11 (R2019)	607.010	2	Over 600 mm Radius Mountable Bullnose
2012 11 (R2019)	607.020	2	Over 600 mm Radius Barrier Bullnose
2012 11 (R2019)	608.010	2	Method of Termination for Concrete Curb with Gutter
2018 11	610.010	2	Catch Basin Frame with Grate Installation at Curb with Gutter
2018 11	610.020	3	Catch Basin Frame with Grate Shoulder Installation at Concrete Barrier
2018 11	610.030	2	Frame with Grate Installation for Inlet Type Catch Basins

DATE	OPSD	REV.	TITLE
DIVISION 700 - CATCH BASINS AND MAINTENANCE HOLES			
2014 11 (R2019)	701.010	5	Precast Concrete Maintenance Hole, 1200 mm Diameter
2014 11 (R2019)	701.011	5	Precast Concrete Maintenance Hole, 1500 mm Diameter
2014 11 (R2019)	701.012	5	Precast Concrete Maintenance Hole, 1800 mm Diameter
2014 11 (R2019)	701.013	5	Precast Concrete Maintenance Hole, 2400 mm Diameter
2014 11 (R2019)	701.014	4	Precast Concrete Maintenance Hole, 3000 mm Diameter
2014 11 (R2019)	701.015	4	Precast Concrete Maintenance Hole, 3600 mm Diameter
2014 11 (R2019)	701.021	4	Maintenance Hole Benching and Pipe Opening Alternatives
2014 11 (R2019)	701.030	4	Precast Concrete Maintenance Hole Components, 1200 mm Diameter, Tapered Top and Flat Cap
2014 11 (R2019)	701.031	2	Precast Concrete Maintenance Hole Components, 1200 mm Diameter, Riser and Monolithic Base
2014 11 (R2019)	701.032	2	Precast Concrete Maintenance Hole Components, 1200 mm Diameter, Base Slab
2014 11 (R2019)	701.040	4	Precast Concrete Maintenance Hole Components, 1500 mm Diameter, Transition Cone and Slabs
2014 11 (R2019)	701.041	2	Precast Concrete Maintenance Hole Components, 1500 mm Diameter, Riser and Bases
2014 11 (R2019)	701.050	4	Precast Concrete Maintenance Hole Components, 1800 mm Diameter, Transition Slabs
2014 11 (R2019)	701.051	2	Precast Concrete Maintenance Hole Components, 1800 mm Diameter, Riser and Base Slab
2014 11 (R2019)	701.060	4	Precast Concrete Maintenance Hole Components, 2400 mm Diameter, Transition Slab
2014 11 (R2019)	701.061	2	Precast Concrete Maintenance Hole Components, 2400 mm Diameter, Riser and Base Slab
2014 11 (R2019)	701.070	3	Precast Concrete Maintenance Hole Components, 3000 mm Diameter, Transition Slab
2014 11 (R2019)	701.071	2	Precast Concrete Maintenance Hole Components, 3000 mm Diameter, Riser and Base Slab
2014 11 (R2019)	701.080	3	Precast Concrete Maintenance Hole Components, 3600 mm Diameter, Transition Slab
2014 11 (R2019)	701.081	2	Precast Concrete Maintenance Hole Components, 3600 mm Diameter, Riser and Base Slab
2018 11	701.100	3	Frost Strap Installation
2014 11 (R2019)	702.040	3	Precast Concrete Ditch Inlet Maintenance Hole - Type A, 1200 x 1200 mm

DATE	OPSD	REV.	TITLE
2014 11 (R2019)	702.050	3	Precast Concrete Ditch Inlet Maintenance Hole - Type B, 1200 x 1200 mm
2014 11 (R2019)	703.011	2	Precast Concrete Single Inlet Flat Cap, 1500 mm Diameter
2014 11 (R2019)	703.012	2	Precast Concrete Single Inlet Flat Cap, 1800 mm Diameter
2014 11 (R2019)	703.013	2	Precast Concrete Single Inlet Flat Cap, 2400 mm Diameter
2014 11 (R2019)	703.014	2	Precast Concrete Single Inlet Flat Cap, 3000 mm Diameter
2014 11 (R2019)	703.015	2	Precast Concrete Single Inlet Flat Cap, 3600 mm Diameter
2014 11 (R2019)	703.021	2	Precast Concrete Twin Inlet Flat Cap, 1500 mm Diameter
2014 11 (R2019)	703.022	2	Precast Concrete Twin Inlet Flat Cap, 1800 mm Diameter
2014 11 (R2019)	703.023	2	Precast Concrete Twin Inlet Flat Cap, 2400 mm Diameter
2014 11 (R2019)	703.024	2	Precast Concrete Twin Inlet Flat Cap, 3000 mm Diameter
2014 11 (R2019)	704.010	3	Precast Concrete Adjustment Units for Maintenance Holes, Catch Basins, and Valve Chambers
2018 11 (R2019)	704.011	2	High Density Polyethylene Adjustment Units for Maintenance Holes, Catch Basins, and Valve Chambers
2018 11 (R2019)	704.012	1	Expanded Polystyrene (EPS) Adjustment Units for maintenance Holes, Catch Basins, and Valve Chambers
2018 11 (R2019)	704.013	0	Rubber Adjustment Units for Maintenance Holes, Catch Basins, And Valve Chambers
2018 11	705.001	1	Concrete Catch Basin Apron, Mountable Curb with Wide Gutter
2018 11	705.002	1	Concrete Catch Basin Apron, Barrier Curb with Standard Gutter
2019 11	705.010	4	Precast Concrete Catch Basin, 600 x 600 mm
2019 11	705.020	4	Precast Concrete Twin Inlet Catch Basin, 600 x 1450 mm
2019 11	705.030	4	Precast Concrete Ditch Inlet, 600 x 600 mm
2019 11	705.040	4	Precast Concrete Ditch Inlets, 600 x 1200 mm
2014 11 (R2019)	706.010	3	Precast Concrete Ditch Inlets, 600 x 1200 mm with 1500 mm Diameter Flat Cap
2014 11 (R2019)	706.020	3	Precast Concrete Ditch Inlets, 600 x 1200 mm with 1800 mm Diameter Flat Cap
2014 11 (R2019)	706.030	3	Precast Concrete Ditch Inlet - Type A, 600 x 1200 mm with 2400 mm Diameter Flat Cap
2014 11 (R2019)	706.031	2	Precast Concrete Ditch Inlet - Type B, 600 x 1200 mm with 2400 mm Diameter Flat Cap
2014 11 (R2019)	706.040	3	Precast Concrete Ditch Inlet - Type A, 600 x 1200 mm with 3000 mm Diameter Flat Cap

DATE	OPSD	REV.	TITLE
2014 11 (R2019)	706.041	2	Precast Concrete Ditch Inlet - Type B, 600 x 1200 mm with 3000 mm Diameter Flat Cap
2019 11	707.010	4	Precast Concrete Maintenance Hole Manufactured Tee
2016 11 (R2021)	708.010	3	Catch Basin Connection for Rigid Main Pipe Sewer
2016 11 (R2021)	708.020	4	Support for Pipe at Catch Basin or Maintenance Hole
2016 11 (R2021)	708.030	3	Catch Basin Connection for Flexible Main Pipe Sewer
2019 04	710.010	4	Capping Existing Structures, Maximum 4.0 m Cover
DIVISION 800 - CULVERTS AND DRAINS			
2017 11 (R2022)	800.010	3	Concrete Pipe Culvert and Sewer Extensions Using Corrugated Steel Pipe, Temporary Conditions
2017 11 (R2022)	800.011	3	Concrete Rigid Frame Box and Open Culvert Extensions Using Corrugated Steel Pipe, Temporary Conditions
2017 11	801.010	3	Cut End Finish Circular Pipe and Pipe-Arch, Corrugated Steel Pipe
2017 11	801.020	2	End Section Details, Corrugated Steel Pipe
2017 11	801.030	3	Bevel Details, Circular and Pipe-Arch Structural Plate, Corrugated Steel Pipe
2017 11	801.040	3	Culvert and Sewer Safety Slope End Treatment Notes and Tables
2017 11	801.041	3	Culvert and Sewer Safety Slope End Treatment, Assembly Details
2017 11	801.042	3	Culvert and Sewer Safety Slope End Treatment, Connection Details
2017 11	801.043	3	Culvert and Sewer Safety Slope End Treatment, Installation Details
2014 11 (R2019)	802.010	3	Flexible Pipe Embedment and Backfill, Earth Excavation
2014 11 (R2019)	802.013	3	Flexible Pipe Embedment and Backfill, Rock Excavation
2014 11 (R2019)	802.014	3	Flexible Pipe Embedment in Embankment, Original Ground: Earth or Rock
2015 11 (R2020)	802.020	3	Flexible Pipe Arch Embedment and Backfill, Earth Excavation
2015 11 (R2020)	802.023	3	Flexible Pipe Arch Embedment and Backfill, Rock Excavation
2015 11 (R2020)	802.024	3	Flexible Pipe Arch Embedment in Embankment, Original Ground: Earth or Rock
2015 11 (R2020)	802.030	3	Rigid Pipe Bedding, Cover, and Backfill, Type 1 or 2 Soil - Earth Excavation
2015 11 (R2020)	802.031	3	Rigid Pipe Bedding, Cover, and Backfill, Type 3 Soil - Earth Excavation

DATE	OPSD	REV.	TITLE
2015 11 (R2020)	802.032	3	Rigid Pipe Bedding, Cover, and Backfill, Type 4 Soil - Earth Excavation
2015 11 (R2020)	802.033	3	Rigid Pipe Bedding, Cover, and Backfill, Rock Excavation
2015 11 (R2020)	802.034	3	Rigid Pipe Bedding and Cover in Embankment, Original Ground: Earth or Rock
2015 11 (R2020)	802.050	3	Horizontal Elliptical Rigid Pipe Bedding, Cover, and Backfill, Type 1 or 2 Soil - Earth Excavation
2015 11 (R2020)	802.051	3	Horizontal Elliptical Rigid Pipe Bedding, Cover, and Backfill, Type 3 Soil - Earth Excavation
2015 11 (R2020)	802.052	3	Horizontal Elliptical Rigid Pipe Bedding, Cover, and Backfill, Type 4 Soil - Earth Excavation
2015 11 (R2020)	802.053	3	Horizontal Elliptical Rigid Pipe Bedding, Cover, and Backfill, Rock Excavation
2015 11 (R2020)	802.054	3	Horizontal Elliptical Rigid Pipe Bedding and Cover in Embankment, Original Ground: Earth or Rock
2021 11	802.095	3	Trench Plug
2015 11 (R2020)	803.010	3	Backfill and Cover for Concrete Culverts with Spans Less Than or Equal to 3.0 m
2015 11 (R2020)	803.030	3	Frost Treatment - Pipe Culverts, Frost Penetration Line Below Bedding Grade
2015 11 (R2020)	803.031	4	Frost Treatment - Pipe Culverts, Frost Penetration Line Between Top of Pipe and Bedding Grade
2017 11	804.030	2	Concrete Headwall for Pipe Less Than 900 mm Diameter
2017 11	804.040	1	Concrete Headwall for Sewer or Culvert Pipe Outlet
2021 11	804.050	3	Grating for Concrete Endwall
2018 11	805.010	3	Height of Fill Table, Round Corrugated Steel Pipe and Structural Plate Corrugated Steel Pipe
2018 11	805.020	3	Height of Fill Table, Corrugated Steel Pipe-Arch and Structural Plate Corrugated Steel Pipe-Arch
2018 11	805.030	3	Height of Fill Table, Spiral Rib Round Pipe
2018 11	805.040	3	Height of Fill Table, Spiral Rib Pipe-Arch
2018 11	806.020	3	Height of Fill Table, Dual Wall Corrugated Polyethylene Gravity Sewer Pipe, 320 kPa and RSC 160
2018 11	806.021	3	Height of Fill Table, Closed Profile Wall Polyethylene Pipe, RSC 160 and RSC 250
2018 11	806.022	3	Height of Fill Table, Dual Wall Corrugated Polyethylene Gravity Sewer Pipe, RSC 100 and RSC 160

DATE	OPSD	REV.	TITLE
2018 11	806.030	1	Height of Fill Table, Dual and Triple Wall Corrugated Polypropylene Gravity Sewer Pipe, 320 kPa
2018 11	806.040	4	Height of Fill Table, Polyvinyl Chloride Gravity Sewer Pipe, 210, 320, and 625 kPa
2019 11	806.060	2	Height of Fill Table, Polyvinyl Chloride Pressure Pipe for Different Dimension Ratios
2018 11	807.010	4	Height of Fill Table, Reinforced Concrete Pipe - Confined Trench, Class 50-D, 65-D, 100-D, and 140-D
2018 11	807.030	4	Height of Fill Table, Reinforced Concrete Pipe - Embankment, Class 50-D, 65-D, 100-D, and 140-D
2018 11	807.050	4	Height of Fill Table, Horizontal Elliptical Concrete Pipe, Class HE-A, HE-I, HE-II, HE-III, and HE-IV
2018 11	809.010	4	Perforated Pipe Subdrain in Granular Trench Main Storm Sewer Connection to Drainage Structure
2018 11	810.010	3	General Rip-Rap Layout for Sewer and Culvert Outlets
2018 11	810.020	3	General Rip-Rap Layout for Ditch Inlets
2017 11	812.010	1	Cut Off Wall for Structural Plate Pipe Arch and Circular CSP
DIVISION 900 - FENCING, GUIDE RAILS			
2021 04	911.130	2	Guide Rail System, Concrete Barrier, Cast-In-Place, Type A, Installation
2021 04	911.131	2	Guide Rail System, Concrete Barrier, Cast-In-Place, Type C, Installation
2021 04	911.132	2	Guide Rail System, Concrete Barrier, Cast-In-Place, Tall Wall, Installation
2021 04	911.134	2	Guide Rail System, Concrete Barrier, Installation - Median Concrete Barrier to Structure
2015 11 (R2021)	911.135	0	Guide Rail System, Concrete Roadside Barrier, Cast-In-Place or Slipformed, Installation
2021 04	911.136	0	Guide Rail System, Concrete Barrier, Cast-In-Place, Type M, Installation
2021 11	911.143	2	Guide Rail System, Concrete Barrier, Precast I-Lock Connection, Type TW, Installation - Permanent
2021 11	911.150	1	Guide Rail System, Concrete Barrier, Type J Connection, 4m Length, Installation - Temporary
2021 11	911.151	1	Guide Rail System, Concrete Barrier, Type J Connection, 6m Length, Installation - Temporary
2021 11	911.160	1	Guide Rail System, Concrete Barrier, Type M Connection, Installation - Temporary 1

DATE	OPSD	REV.	TITLE
2013 11 (R2020)	911.161	0	Guide Rail System, Concrete Barrier, Type M Connection, Installation - Temporary 2
2021 11	911.162	1	Guide Rail System, Concrete Barrier, Type M Connection, Installation - Temporary Restraint System, Pinned to Asphalt Pavement
2021 11	911.163	1	Guide Rail System, Concrete Barrier, Type M Connection, Installation - Temporary Restraint System, Strapped to Concrete
2021 11	911.164	1	Guide Rail System, Concrete Barrier, Type M Connection, Installation - Temporary Restraint System, Strapped to Concrete with Asphalt Surface
2021 11	911.167	1	Guide Rail System, Concrete Barrier, Type M Connection, Installation - Temporary Restraint System, Bolted Through Concrete
2021 11	911.168	1	Guide Rail System, Concrete Barrier, Type M Connection, Installation - Temporary Restraint System, Bolted Through Concrete with Asphalt Surface
2021 11	911.170	2	Guide Rail System, Concrete Barrier, Type M Connection, Installation - Temporary Restraint System, Transition to Pinned TCB
2021 11	911.171	2	Guide Rail System, Concrete Barrier, Type M Connection, Installation - Temporary Restraint System, Transition to Strapped TCB
2021 11	911.172	2	Guide Rail system, Concrete Barrier, Type M Connection, Installation - Temporary Restraint System, Transition to Bolted TCB
2021 11	911.173	2	Guide Rail System, Concrete Barrier, Type M Connection, Installation - Temporary Restraint System, Transition to Permanent Concrete Barrier
2021 11	911.174	2	Guide Rail System, Concrete Barrier, Type M Connection, Component - Thrie Beam Transition
2021 11	911.180	1	Guide Rail System, Concrete Barrier, Type T Connection, 4.0m Length, Installation - Temporary
2021 11	911.181	1	Guide Rail System, Concrete Barrier, Type T Connection, 6.0m Length, Installation - Temporary
2021 11	911.190	0	Guide Rail System, Concrete Barrier, Type X Connection, 9.1m Length, Installation - Temporary
2021 11	911.191	0	Guide Rail System, Concrete Barrier, Type X Connection, Components
2021 11	911.192	0	Guide Rail System, Concrete Barrier, Type X Connection - Reinforcement, Components

DATE	OPSD	REV.	TITLE
2021 11	911.193	0	Guide Rail System, Concrete Barrier, Type X Connection, 3.048m Length, Installation - Temporary
2021 11	911.194	0	Guide Rail System, Concrete Barrier, Type X Connection, 4.0m Length, Installation - Temporary
2021 11	911.195	0	Guide Rail System, Concrete Barrier, Type X Connection, Installation - Temporary
2021 11	911.196	0	Guide Rail System, Concrete Barrier, Type X Connection, Installation - Temporary, Reduced Deflection Transition to TCB
2021 11	911.197	0	Guide Rail System, Concrete Barrier, Type X Connection, 4.0m Length, Reinforcing Steel
2021 11	911.198	0	Guide Rail System, Concrete Barrier, Type X Connection, 6.1m Length, Installation - Temporary
2021 11	911.199	0	Guide Rail System, Concrete Barrier, Type X Connection, 4.0m Length, Clipped, Installation - Temporary
2021 11	911.200	0	Guide Rail System, Concrete Barrier, Type X Connection, Installation - Temporary - Low Speed
2021 04	911.230	2	Guide Rail System, Concrete Barrier, Median End Treatment Installation
2021 11	911.232	2	Guide Rail System, Temporary Concrete Barrier and Energy Attenuator - Temporary, Reduced Exposure, Installation - Temporary
2021 11	911.236	0	Guide Rail System, Temporary Concrete Barrier and Energy Attenuator - Temporary, Reduced Exposure, Anchored Barrier, Installation - Temporary
2020 11	911.331	0	Guide Rail System, Concrete Barrier, Temporary Transition Barrier, Installation
2020 11	911.335	0	Guide Rail System, Concrete Barrier, Temporary Transition Barrier, Ribs and Stiffener Posts - Components
2020 11	911.336	0	Guide Rail System, Concrete Barrier, Temporary Transition Barrier, Stiffener Post Details - Components
2020 11	911.337	0	Guide Rail System, Concrete Barrier, Temporary Transition Barrier, Tail Piece Details - Components
2020 11	911.338	0	Guide Rail System, Concrete Barrier, Temporary Transition Barrier, End Cap Details - Components
2020 11	911.339	0	Guide Rail System, Concrete Barrier, Temporary Transition Barrier, Cup Washer 1 - Component
2020 11	911.340	1	Guide Rail System, Concrete Barrier, Temporary Concrete Barrier Transition, Installation - Temporary
2020 11	911.341	0	Guide Rail System, Concrete Barrier, Temporary Transition Barrier, Connection to Permanent Barrier - Component

DATE	OPSD	REV.	TITLE
2020 11	911.342	0	Guide Rail System, Concrete Barrier, Temporary Transition Barrier, Cup Washer 2 - Component
2020 11	911.350	0	Guide Rail System, Concrete Barrier, Steel Beam Guide Rail to Temporary Concrete Barrier, Installation - Temporary
2020 11	911.351	0	Guide Rail System, Concrete Barrier, Steel Beam Guide Rail to Temporary Concrete Barrier, Connector Plate - Component
2020 11	911.352	0	Guide Rail System, Concrete Barrier, Steel Beam Guide Rail to Temporary Concrete Barrier, Connector Gussets - Components
2020 11	911.353	0	Guide Rail System, Concrete Barrier, Steel Beam Guide Rail to Temporary Concrete Barrier, Connector Plate Face Plate - Component
2020 11	911.354	0	Guide Rail System, Concrete Barrier, Steel Beam Guide Rail to Temporary Concrete Barrier, Steel Brackets - Components
2020 11	911.355	0	Guide Rail System, Concrete Barrier, Steel Beam Guide Rail to Temporary Concrete Barrier, Wooden Offset Blocks - Components
2020 11	911.357	0	Guide Rail System, Concrete Barrier, Steel Beam Guide Rail to Temporary Concrete Barrier, Temporary Transition Connection
2021 04	911.380	2	Guide Rail System, Concrete Barrier, Permanent Transition, Installation at Piers and Poles
2021 04	911.381	3	Guide Rail System, Concrete Barrier, Permanent Transition Installation, Roadside Concrete Barrier to Structure
2015 11 (R2021)	911.382	1	Guide Rail System, Concrete Barrier, Dowel Connection Detail
2021 04	911.383	1	Guide Rail System, Concrete Barrier, Permanent Transition Installation at Lighting Pole and Sign Support Footings
2015 11 (R2020)	911.430	1	Guide Rail System, Concrete Barrier, Temporary - Leaving End Treatment, Installation - Divided Highway
2021 11	911.610	0	Guide Rail System, Concrete Barrier, QuickChange Moveable Barrier, Installation - Temporary
2016 11	912.101	3	Guide Rail System, Steel Beam, Rail, Component
2016 11	912.102	2	Guide Rail System, Steel Beam, Channel, Component
2021 11	912.103	4	Guide Rail System, Steel Beam, Plastic Offset Blocks, Component
2016 11	912.104	3	Guide Rail System, Steel Beam, Steel Post with Wooden Offset Block, Component
2016 11	912.105	2	Guide Rail System, Steel Beam, Base Plate, Component
2019 11	912.109	0	Guide Rail System, Steel Beam, Type M20 Steel Post with Offset Block and Base Plate, Component

DATE	OPSD	REV.	TITLE
2016 11	912.123	0	Guide Rail System, Steel Beam, Type M Rail - 476mm Hole Spacing, Component
2016 04	912.124	0	Guide Rail System, Steel Beam, Type M Transition Rail, Component
2016 04	912.125	0	Guide Rail System, Steel Beam, Type M Rail, Component
2019 11	912.126	0	Guide Rail System, Steel Beam, Steel Post for Thrie Beam Rail with 30cm Offset Block, Component
2016 04	912.127	0	Guide Rail System, Steel Beam, M20 Steel Post with Offset Block, Component
2016 11	912.128	0	Guide Rail System, Steel Beam, Type M30 Steel Post with Offset Block, Component
2016 11	912.129	0	Guide Rail System, Steel Beam, 30cm Polymer Offset Block - P-Block, Component
2016 11	912.130	3	Guide Rail System, Steel Beam, Steel Post with Wooden Offset Block Assembly, Installation - Single Rail
2016 11	912.135	1	Guide Rail System, Steel Beam, Steel Post with Steel Offset Block Assembly, Adjustment - Single Rail
2016 11	912.145	1	Guide Rail System, Steel Beam, Wooden Post Assembly, Adjustment - Single Rail
2016 11	912.185	0	Guide Rail System, Steel Beam, Type M20, Installation
2016 11	912.186	0	Guide Rail System, Steel Beam, Type M20 - Adjacent To 2H:1V Slope Installation - Rail at Shoulder
2019 11	912.188	0	Guide Rail System, Steel Beam, Type M20 - Adjacent to Concrete Curb, Installation
2016 11	912.189	0	Guide Rail System, Steel Beam, Type M30 - Adjacent to Sidewalk, Installation
2010 11	912.235	1	Guide Rail System, Steel Beam, Leaving End Treatment, Installation
2016 11	912.245	0	Guide Rail System, Steel Beam, Type M - 7.62m Long Span Treatment, Installation
2016 11	912.246	0	Guide Rail System, Steel Beam, Type M - 5.71m Long Span Treatment, Installation
2019 11	912.249	0	Guide Rail System, Steel Beam, Type M - Base Plated for Shallow Box Culverts, Installation
2018 11	912.255	1	Guide Rail System, Steel Beam, Type M20 and M30 Leaving End Treatment, Installation
2018 11	912.256	1	Guide Rail System, Steel Beam, Type M Leaving End Treatment, Component - Rail, Terminal Section and Post Anchor Detail

DATE	OPSD	REV.	TITLE
2018 11	912.257	0	Guide Rail System, Steel Beam, Type M20 and M30 Leaving End Treatment Post Components
2020 11	912.313	0	Guide Rail System, Steel Beam, Transition from Type M to Existing Steel Beam Guide Rail - Installation
2017 04	912.314	0	Guide Rail System, Steel Beam, Transition from Type M to Existing Steel Beam Guide Rail, Installation
2016 11	912.315	0	Guide Rail System, Steel Beam, Transition from Type M to Steel Beam Guide Rail with Channel For Structure Connection, Installation
2016 11	912.316	0	Guide Rail System, Steel Beam, Type M Reduced Deflection Treatment, Installation
2002 11	912.330	1	Guide Rail System, Steel Beam, Temporary Transition Installation - Rail Method, Single Steel Beam to Temporary Concrete Barrier
2002 11	912.331	1	Guide Rail System, Steel Beam, Temporary Transition Installation, Single Steel Beam to Temporary Concrete Barrier
2008 11	912.380	1	Guide Rail System, Steel Beam, Permanent Transition Installation, Channel Termination, Median
2010 11	912.401	1	Guide Rail System, Steel Beam, Structure Connection, Component - Rail and Channel
2020 11	912.402	0	Guide Rail System, Steel Beam, Terminal Connector, Component
2010 11	912.430	3	Guide Rail System, Steel Beam, Structure Connection
2019 11	912.450	0	Guide Rail System, Steel Beam, Structure Connection - 3 Tube Railing, Installation
2019 11	912.451	0	Guide Rail System, Steel Beam, Structure Connection - 4 Tube Railing, Installation
2019 11	912.452	0	Guide Rail System, Steel Beam, Structure Connection - 4 Tube Railing with Sidewalk, Installation
2008 11	912.480	2	Guide Rail System, Steel Beam, Permanent Connection Installation, Single Steel Beam to Concrete Barrier
2008 11	912.481	2	Guide Rail System, Steel Beam, Permanent Connection Installation, Double Steel Beam to Concrete Barrier
2016 11	912.530	2	Guide Rail System, Steel Beam, Structure Approach Treatment, Installation - Rural Highway
2019 11	912.625	0	Guide Rail System, Steel Beam, Thrie Beam Rail - 476mm Hole Spacing, Component
2019 11	912.630	0	Guide Rail System, Steel Beam, Asymmetric Transition Rail, Component
2008 11	913.101	1	Guide Rail System, Cable, Component - Cable Fittings
2013 11	913.135	0	Guide Rail System, Cable, Adjustment - Shoulder

DATE	OPSD	REV.	TITLE
2018 04	913.220	0	Guide Rail System, High Tension Cable, Safence Terminal, 3-Cable, Slope Installation
2018 04	913.221	0	Guide Rail System, High Tension Cable, Safence Terminal, 3-Cable, Shoulder Installation
2018 04	913.222	0	Guide Rail System, High Tension Cable, Safence Terminal, 3-Cable, Terminal Posts - Component
2018 04	913.226	0	Guide Rail System, High Tension Cable, Safence Terminal, Steel Anchor Assembly - Component
2018 04	913.250	0	Guide Rail System, High Tension Cable, Safence, 3-Cable Shoulder Installation
2018 04	913.251	0	Guide Rail System, High Tension Cable, Safence, 3-Cable Slope Installation
2018 04	913.252	0	Guide Rail System, High Tension Cable, Safence, 3-Cable, Slope Installation Line Post, Component
2018 04	913.253	0	Guide Rail System, High Tension Cable, Safence, 3-Cable Shoulder Installation Line Post, Component
2018 04	913.255	0	Guide Rail System, High Tension Cable, Safence, 3-Cable Buried Obstacle Treatment Installation
2016 11	921.101	2	Energy Attenuator, General, Installation - Granular Approach Pad, Median
2011 11	922.131	2	Energy Attenuator, Crash Cushion, QuadTrend System, Installation - Concrete Barrier
2011 11	922.133	2	Energy Attenuator, Crash Cushion, QuadTrend System, Installation - Concrete Pad and Rear Cable Anchor Block
2018 04	922.150	1	Energy Attenuator, End Terminal, Steel Beam Terminal, MASH Slotted Rail Terminal System, Installation
2022 11	922.165	2	Energy Attenuator, End Treatment, Steel Beam Energy Attenuating Terminal, MASH SoftStop Terminal System, Installation
2018 11	922.171	0	Energy Attenuator, End Treatment, Steel Beam Energy Attenuating Terminal, MASH Max-Tension Terminal System, Installation
2018 11	922.186	1	Energy Attenuator, End Treatment, Steel Beam Energy Attenuating Terminal, MASH Sequential Kinking Terminal System, Installation
2011 11 (R2022)	923.001	3	Energy Attenuator, Crash Cushion, Narrow Systems, Component - Reinforced Concrete Pad
2021 11	923.002	2	Energy Attenuator, Crash Cushion, Component - Anchor Assembly

DATE	OPSD	REV.	TITLE
2021 11	923.004	1	Energy Attenuator, Crash Cushion, Wide Systems, Component - Reinforced Concrete Pad
2021 11	923.005	1	Energy Attenuator, Crash Cushion, Extra Wide Systems, Component - Reinforced Concrete Pad
2021 11	923.006	1	Energy Attenuator, Crash Cushion, Quadguard Super Wide System, Component - Reinforced Concrete Pad
2021 11	923.007	0	Energy Attenuator, Crash Cushion, Quadguard M10 Wide System, Component, Reinforced Concrete Pad
2021 11	923.008	0	Energy Attenuator, Crash Cushion, Hercules System, Component, Reinforced Concrete Pad
2022 04	923.010	1	Energy Attenuator, Crash Cushion, Narrow Systems, Component - Reinforced Precast Concrete Pad for Permanent Installation
2022 04	923.011	1	Energy Attenuator, Crash Cushion, Component - Reinforced Precast Concrete Pad for Modified Temporary Concrete Barrier
2021 11	923.141	0	Energy Attenuator, Crash Cushion, Quadguard M10 Wide System, Installation – Permanent, Unidirectional
2011 11 (R2021)	923.187	0	Energy Attenuator, Crash Cushion, QuadGuard Wide System, Installation - Permanent, Bidirectional
2011 11 (R2021)	923.188	0	Energy Attenuator, Crash Cushion, QuadGuard Extra Wide System, Installation - Temporary, Unidirectional
2011 11 (R2021)	923.189	0	Energy Attenuator, Crash Cushion, QuadGuard Extra Wide System, Installation - Temporary, Bidirectional
2011 11 (R2021)	923.190	0	Energy Attenuator, Crash Cushion, QuadGuard Extra Wide System, Installation - Permanent, Unidirectional
2011 11 (R2021)	923.191	0	Energy Attenuator, Crash Cushion, QuadGuard Extra Wide System, Installation - Permanent, Bidirectional
2015 11 (R2021)	923.192	0	Energy Attenuator, Crash Cushion, Quadguard Super Wide System, Installation - Temporary, Undirectional
2015 11 (R2021)	923.193	0	Energy Attenuator, Crash Cushion, Quadguard Super Wide System, Installation - Temporary, Bidirectional
2015 11 (R2021)	923.194	0	Energy Attenuator, Crash Cushion, Quadguard Super Wide System, Installation - Permanent Undirectional
2015 11 (R2021)	923.195	0	Energy Attenuator, Crash Cushion, Quadguard Super Wide System, Installation - Permanent Bidirectional
2021 11	923.196	0	Energy Attenuator, Crash Cushion, Quadguard M10 System, Installation – Temporary, Unidirectional
2021 11	923.197	0	Energy Attenuator, Crash Cushion, Quadguard M10 System, Installation – Temporary, Bidirectional

DATE	OPSD	REV.	TITLE
2021 11	923.198	0	Energy Attenuator, Crash Cushion, Quadguard M10 System, Installation – Permanent, Unidirectional
2021 11	923.199	0	Energy Attenuator, Crash Cushion, Quadguard M10 System, Installation – Permanent, Bidirectional
2013 11 (R2021)	923.201	2	Energy Attenuator, Crash Cushion, Connecticut Impact Attenuation System, Component - Steel Cylinder
2013 11 (R2021)	923.202	2	Energy Attenuator, Crash Cushion, Connecticut Impact Attenuation System, Component - Polyethylene Lid
2013 11 (R2021)	923.204	2	Energy Attenuator, Crash Cushion, Connecticut Impact Attenuation System, Component - Concrete Backwall
2013 11 (R2021)	923.242	2	Energy Attenuator, Crash Cushion, Connecticut Impact Attenuation System, Installation
2021 11	923.244	2	Energy Attenuator, Crash Cushion, Connecticut Impact Attenuation System, Installation - Long Median Hazard
2021 11	923.245	3	Energy Attenuator, Crash Cushion, Connecticut Impact Attenuation System, Installation - Short Median Hazard
2011 11 (R2021)	923.384	0	Energy Attenuator, Crash Cushion, TAU II Wide System, Installation - Temporary, Unidirectional
2011 11 (R2021)	923.385	0	Energy Attenuator, Crash Cushion, TAU II Wide System, Installation - Temporary, Bidirectional
2011 11 (R2021)	923.386	0	Energy Attenuator, Crash Cushion, TAU II Wide System, Installation - Permanent, Unidirectional
2011 11 (R2021)	923.387	0	Energy Attenuator, Crash Cushion, TAU II Wide System, Installation - Permanent, Bidirectional
2011 11 (R2021)	923.388	0	Energy Attenuator, Crash Cushion, TAU II Extra Wide System - TL-2, Installation - Temporary, Unidirectional
2011 11 (R2021)	923.389	0	Energy Attenuator, Crash Cushion, TAU II Extra Wide System - TL-2, Installation - Temporary, Bidirectional
2011 11 (R2021)	923.390	0	Energy Attenuator, Crash Cushion, TAU II Extra Wide System - TL-3, Installation - Temporary, Unidirectional
2011 11 (R2021)	923.391	0	Energy Attenuator, Crash Cushion, TAU II Extra Wide System - TL-3, Installation - Temporary, Bidirectional
2011 11 (R2021)	923.392	0	Energy Attenuator, Crash Cushion, TAU II Extra Wide System - TL-2, Installation - Permanent, Unidirectional
2011 11 (R2021)	923.393	0	Energy Attenuator, Crash Cushion, TAU II Extra Wide System - TL-2, Installation - Permanent, Bidirectional
2011 11 (R2021)	923.394	0	Energy Attenuator, Crash Cushion, TAU II Extra Wide System - TL-3, Installation - Permanent, Unidirectional

DATE	OPSD	REV.	TITLE
2011 11 (R2021)	923.395	0	Energy Attenuator, Crash Cushion, TAU II Extra Wide System - TL-3, Installation - Permanent, Bidirectional
2021 11	923.396	0	Energy Attenuator, Crash Cushion, TAU-M System, Installation - Temporary, Unidirectional
2021 11	923.397	0	Energy Attenuator, Crash Cushion, TAU-M System, Installation - Temporary, Bidirectional
2021 11	923.398	0	Energy Attenuator, Crash Cushion, TAU-M System, Installation - Permanent, Unidirectional
2021 11	923.399	0	Energy Attenuator, Crash Cushion, TAU-M System, Installation - Permanent, Bidirectional
2017 11 (R2022)	923.480	1	Energy Attenuator, Crash Cushion, Smart System, Installation - Temporary, Unidirectional
2017 11 (R2022)	923.481	1	Energy Attenuator, Crash Cushion, Smart System, Installation - Temporary, Bidirectional
2017 11 (R2022)	923.482	1	Energy Attenuator, Crash Cushion, Smart System, Installation - Permanent, Unidirectional
2017 11 (R2022)	923.483	1	Energy Attenuator, Crash Cushion, Smart System, Installation - Permanent, Bidirectional
2021 11	923.501	0	Energy Attenuator, Crash Cushion, Hercules System, Installation - Temporary, Unidirectional and Bidirectional
2021 11	923.502	0	Energy Attenuator, Crash Cushion, Hercules System, Installation - Permanent, Unidirectional and Bidirectional
2011 11 (R2021)	923.530	1	Energy Attenuator, Crash Cushion, Box Beam Bursting Energy Absorbing Terminal, Installation - Layout
2011 11 (R2021)	923.531	1	Energy Attenuator, Crash Cushion, Box Beam Bursting Energy Absorbing Terminal, Installation - Impact Head and Post
2021 11	924.130	0	Energy Attenuator, Crash Cushion, ABSORB 350 System, Movable Temporary Concrete Barrier, Installation
2016 11 (R2022)	924.131	1	Energy Attenuator, Crash Cushion, ABSORB 350 System, Installation - Temporary Concrete Barrier
2021 11	924.132	0	Energy Attenuator, Crash Cushion, ABSORB-M System TL-2, Installation – Temporary Concrete Barrier
2021 11	924.133	0	Energy Attenuator, Crash Cushion, ABSORB-M System TL-3, Installation – Temporary Concrete Barrier
2016 11 (R2022)	924.135	2	Energy Attenuator, Crash Cushion, ACZ-350 System, Installation - Temporary Concrete Barrier
2017 11 (R2022)	924.141	1	Energy Attenuator, Crash Cushion, Sled System, Installation - Temporary Concrete Barrier
2013 11	925.010	0	Guide Rail System, Thrie Beam, Component - Rail

DATE	OPSD	REV.	TITLE
2013 11	925.030	0	Guide Rail System, Thrie Beam, Component - Terminal Connector
2022 04	971.101	5	Fence, Highway, In Earth, Shale, Loose Rock, Or Friable Rock, Installation
2022 04	971.102	3	Fence, Highway, In Solid Rock, Installation
2016 11 (R2022)	971.103	0	Fence, Highway, Installation Details
2012 11 (R2019)	972.101	2	Fence, Chain-Link, Component - Barbed Wire
2012 11 (R2019)	972.102	2	Fence, Chain-Link, Component - Gate
2012 11 (R2019)	972.130	2	Fence, Chain-Link, Installation - Roadway
2012 11 (R2019)	972.131	2	Fence, Chain-Link, Installation - Concrete Barrier
2012 11 (R2019)	972.132	0	Fence, Chain-Link, Details and Table
2022 11	973.130	1	Fence, Steel Beam, Barricade, installation
2022 11	973.131	0	Wildlife Fence, Type A, With Apron of Type B Fence Fabric
2022 11	973.132	0	Wildlife Fence, Type A, Access Gate
2022 11	973.133	0	Wildlife Fence, Type B, on Steel Posts, Installation
2022 11	973.134	0	Wildlife Fence, Type B, on Wooden Posts, Installation
2022 11	973.135	0	Wildlife Fence, Type A, Installation
2022 11	973.140	0	Wildlife Fence, Steel Post Footing Details
2022 11	973.141	0	Wildlife Fence, Wooden Post Installation Details
2022 11	973.142	0	Wildlife Fence, Miscellaneous Details
2022 11	973.143	0	Wildlife Fence, Tie-In at Culverts or Wildlife Crossing Structures
2022 11	973.144	0	Wildlife Escape
2022 11	973.145	0	Wildlife Fence, Type B, Fence End Turnaround
2017 11	980.101	3	Pedestrian Barricade, Installation
2017 11	982.101	2	Splash Guard, Pedestrian, Installation
2014 11 (R2021)	984.101	1	Post Mounted Delineator, Installation
2016 11 (R2021)	984.105	0	Flexible Delineator Post, Installation - temporary and Permanent
2017 11	984.201	1	Energy Attenuator, End Treatment, Delineation, Installation - Approach End
2017 11	984.202	1	Energy Attenuator, End Treatment, Delineation, Installation - Leaving End
2017 11	984.203	1	Energy Attenuator, Crash Cushion, Delineation, Installation - Temporary
2017 11	984.204	1	Energy Attenuator, Crash Cushion, Delineation, Installation - Permanent

DATE	OPSD	REV.	TITLE
2013 11 (R2021)	984.205	0	Energy Attenuator, Crash Cushion, Connecticut Impact Attenuation System, Delineation, Installation - Permanent
2018 04	984.206	0	Guide Rail System, High Tension Cable, Delineation, Installation - Leaving End
2018 04	984.207	0	Guide Rail System, High Tension Cable, Delineation, Installation - Approach End
2019 04	985.110	1	Small Sign Support System, Single Breakaway Wooden Post, 89x89mm, 89x140mm, 140x140mm, and 140x148mm, Installation - Single Post Assembly
2019 04	985.210	1	Small Sign Support System, Double Breakaway Wooden Post, 89x89mm and 89x140mm, Installation - Double Post Assembly
2019 04	985.220	1	Small Sign Support System, Double Breakaway Wooden Post, 140x140mm and 140x184mm, Installation - Double Post Assembly
2019 04	987.101	1	Small Sign Support System, Lap Splice Rib-Bak Breakaway System, Components
2019 04	987.110	1	Small Sign Support, Lap Splice Rib-Bak Breakaway System, Installation - Single Post Assembly
2019 04	987.210	1	Small Sign Support System, Lap Splice Rib-Bak Breakaway System, Installation - Double Post Assembly
2019 04	987.310	1	Small Sign Support System, Lap Splice Rib-Bak Breakaway System, Installation - Triple Post Assembly
2019 04	989.110	1	Small Sign Support System, Sqr-Loc Perforated Steel Square Sign Post System, Installation - Single Post Assembly
2019 04	989.210	1	Small Sign Support System, Sqr-Loc Perforated Steel Square Post System, Installation - Double Post
2014 11	990.110	1	Small Sign Support System, Non-Breakaway U-Flange Post, Installation - Single Post Assembly
2012 11 (R2021)	991.132	2	Expanded Metal Anti-Glare Screen, Installation - Chain-Link Fence
2022 04	992.101	1	Intermediate Sign Support System, Slip-Safe Supreme Rib-Bak Breakaway System, Components
2018 11	992.210	0	Intermediate Sign Support System, Slip-Safe Supreme Rib-Bak Breakaway System, Installation-Double Post Assembly

DIVISION 1000 - SANITARY SEWERS

2016 11 (R2021)	1003.010	3	Cast-in-Place Maintenance Hole Drop Structure Tee
2016 11 (R2021)	1003.020	3	Cast-in-Place Maintenance Hole Drop Structure Wye
2021 11	1003.030	5	Internal Drop Structure for Existing Maintenance Holes with Optional Side Cleanout

DATE	OPSD	REV.	TITLE
2021 11	1003.031	4	Internal Drop Structure for New Maintenance Holes with Optional Side Cleanout
2021 11	1003.032	0	Internal Drop Structure for Existing Maintenance Holes with Top Cleanout
2021 11	1003.033	0	Internal Drop Structure for New Maintenance Holes with Top Cleanout
2021 11	1006.010	4	Sewer Service Connections for Main Pipe Sewer
DIVISION 1100 - WATERMAINS			
2014 11	1100.010	3	Cast-in-Place Chamber for Valves Up to 350 mm Diameter
2014 11	1100.011	2	Piping Layout for Butterfly and Gate Valves Up to 350 mm Diameter in Cast-in-Place Chambers
2015 11	1101.010	4	Precast Valve Chamber, 1200 mm and 1500 mm Diameter
2018 11	1101.012	3	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 1800 x 2400 mm Components
2018 11	1101.013	3	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 1800 x 2400 mm, Riser and Base
2018 11	1101.014	3	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 1800 x 2400 mm, Thrust Blocks
2018 11	1101.015	3	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 1800 x 2400 mm, Chimney and Cap
2018 11	1101.016	3	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 2400 x 3000 mm Components
2018 11	1101.017	3	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 2400 x 3000 mm Riser and Base
2018 11	1101.018	4	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 2400 x 3000 mm Thrust Blocks
2018 11	1101.019	3	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 2400 x 3000 mm Chimney and Cap
2018 11	1101.020	4	Valve Operator
2018 11	1101.030	1	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 3000 x 3000 mm Components
2018 11	1101.031	1	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 3000 x 3000 mm Riser and Base
2018 11	1101.032	1	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 3000 x 3000 mm Thrust Blocks
2018 11	1101.033	1	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 3000 x 3000 mm Chimney and Cap

DATE	OPSD	REV.	TITLE
2018 11	1101.040	1	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 3600 x 3000 mm Components
2018 11	1101.041	1	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 3600 x 3000 mm Riser and Base
2018 11	1101.042	1	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 3600 x 3000 mm Thrust Blocks
2018 11	1101.043	1	Precast Concrete Valve Chamber with Poured-in-Place Thrust Blocks, 3600 x 3000 mm Chimney and Cap
2018 11	1103.010	3	Concrete Thrust Blocks for Tees, Plugs, and Horizontal Bends
2018 11	1103.020	4	Concrete Thrust Blocks for Vertical Bends
2018 11	1103.021	1	Dimension Tables for Concrete Thrust Blocks for Vertical ends
2018 11	1104.010	4	Water Service Connection, 19 and 25 mm Diameter Sizes
2018 11	1104.020	3	Water Service Connection, 32, 38, and 50 mm Diameter Sizes
2018 11	1104.030	3	Blow Off Installation
2018 11	1105.010	3	Hydrant Installation
2019 11	1107.010	3	Piping Layout for Water Meters 50 mm and Smaller in Chambers
2019 11	1107.020	3	Piping Layout for Water Meters 75 to 250 mm in Chambers with By-Pass
2019 11	1107.030	3	Piping Layout for Water Meters in Building with By-Pass
2018 11	1108.010	3	Cast-in-Place Water Meter Chamber for 75 to 250 mm Meters
2020 11	1109.010	3	Cathodic Protection for Metallic Watermain Systems
2020 11	1109.011	3	Cathodic Protection for PVC Watermain Systems
2020 11	1109.012	2	Cathodic Protection of Existing Metallic Watermains, Exposed Service or Pipe Method
2020 11	1109.013	2	Anode Installation Over Pipe Method for Existing Metallic Watermains
2020 11	1109.014	2	Horizontal Anode Bank at Service
2020 11	1109.015	2	Vertical Anode Bank at Service
2015 11 (R2020)	1109.025	1	Waterproofing of Splices
2020 11	1109.030	1	Insulation for Sewers and Watermains in Shallow Trenches
DIVISION 3000 - STRUCTURES			
2010 11 (R2019)	3000.100	2	Foundation, Piles, Steel H-Pile Driving Shoe
2019 11	3000.150	2	Foundation, Piles, Steel H-Pile Splice
2010 11 (R2019)	3000.201	1	Foundation, Piles, Steel HP 310 Oslo Point
2017 11 (R2019)	3001.100	2	Foundation, Piles, Steel Tube Pile Driving Shoe

DATE	OPSD	REV.	TITLE
2019 11	3001.150	2	Foundation, Piles, Steel Tube Pile Splice
2010 11 (R2019)	3002.200	1	Foundation, Piles, Steel Sheet Pile Anchorage
2019 11	3003.100	2	Foundation, Piles, Wooden Pile Driving Shoe
2010 11 (R2019)	3003.150	1	Foundation, Piles, Wooden Pile Head Protection
2010 11	3090.100	1	Foundation, Frost Penetration Depths for Northern Ontario
2010 11	3090.101	1	Foundation, Frost Penetration Depths for Southern Ontario
2010 11 (R2019)	3101.150	1	Walls, Abutment, Backfill, Minimum Granular Requirement
2020 11	3101.200	2	Walls, Abutment, Backfill, Rock
2010 11 (R2019)	3102.100	1	Walls, Abutment, Backfill Drain
2010 11 (R2019)	3120.100	2	Walls, Retaining, Concrete Toe Wall
2010 11 (R2019)	3121.150	1	Walls, Retaining, Backfill, Minimum Granular Requirement
2011 04 (R2019)	3190.100	2	Walls, Retaining and Abutment, Wall Drain
2022 04	3290.100	2	Piers, Cutwater Assembly
2019 11	3310.100	2	Deck, Girders, Concrete, Method of Obtaining Screed Elevations
2019 11	3311.100	2	Deck, Girders, Steel, Method of Obtaining Screed Elevations
2022 04	3311.900	3	Deck, Girders, Steel Box, Access Hatch
2017 11	3329.100	2	Deck, Reinforcement, Supports for Reinforcing Steel for Slab Depths 300 mm or Less
2017 11	3329.101	2	Deck, Reinforcement, Supports for Reinforcing Steel for Slab Depths Greater Than 300 mm
2022 11	3332.100	2	Deck, Round Voids, Form Supports and Tie-Downs
2010 11 (R2019)	3333.100	1	Deck, Round Voids, Drains
2010 11 (R2019)	3333.101	1	Deck, Trapezoid Void, Drains
2022 11	3339.100	3	Deck, Voids, Access Hatch for Concrete Bridges, Assembly
2011 11 (R2022)	3339.101	1	Deck, Voids, Access Hatch for Concrete Bridges, Installation
2014 11	3340.100	2	Deck, Drains with Downspout
2014 11	3340.102	2	Deck, Drains with Sloped Downspout
2022 11	3340.150	3	Deck, Drains with Transverse Bar Openings
2022 04	3340.153	3	Deck, Drains, Median with Transverse Bar Openings
2022 04	3340.200	3	Deck, Drains with Downspout Modification for Addition of Asphalt to Existing Structure
2022 11	3340.201	3	Deck, Drains, with Sloped Downspout Modification for Addition of Asphalt to Existing Structure

DATE	OPSD	REV.	TITLE
2022 11	3340.250	3	Deck, Drains, with Transverse or Longitudinal Bar Openings, Modification for Addition of Asphalt to Existing Structure
2022 11	3349.100	3	Deck, Drains, Drainage of New Deck Below Asphalt Wearing Surface
2022 11	3349.101	3	Deck, Drains, Drainage of Existing Deck Below Asphalt Wearing Surface
2016 04	3360.100	2	Deck, Light Pole Bases, Structures with Barrier Walls
2016 04	3360.200	2	Deck, Light Pole Bases, Structures with Parapet Walls
2008 11 (R2019)	3370.100	2	Deck, Waterproofing Hot Applied Asphalt Membrane with Protection Board
2008 11 (R2019)	3370.101	2	Deck, Waterproofing Hot Applied Asphalt Membrane at Active Cracks Greater Than 2 mm Wide and Construction Joints
2012 11 (R2020)	3390.100	2	Deck, Drip Channel
2005 11	3390.150	0	Falsework Clearance to Traffic Lanes
2022 04	3419.100	2	Barriers and Railings, Steel Beam, Guide Rail and Channel Anchorage
2021 11	3419.150	2	Barriers and Railings, Steel, Single Railing Anchorage
2021 11	3419.155	2	Barriers and Railings, Steel, Double Railing Anchorage
2012 11	3900.100	1	Utilities, Duct Location
2011 11	3900.150	1	Utilities, Duct Termination at Bridge Approaches
2015 11	3920.100	0	Precast Reinforced Concrete Box Culvert with Height of Fill ≥ 0.6 m
2016 04	3920.110	1	Precast Reinforced Concrete Box Culvert with Height of Fill < 0.6 m
2010 11 (R2020)	3940.150	2	Figures in Concrete, Warning Message, Layout
2020 11	3940.151	3	Figures in Concrete, Warning Message, Letters
2020 11	3941.200	3	Figures in Concrete, Site Number and Date, Layout
2011 11	3950.100	1	Joints, Concrete Expansion and Construction on Structure

Aban (ed)	abandon (ed)
Abut or A	abutment
AC	asphalt coated, asphalt curb, or asphalt cement
AC&G	asphalt curb with gutter
AC PI	asphalt coated and paved invert
Add'l	additional
AG	asphalt gutter
AISC	American Institute of Steel Construction
ALT	alternate
Allce	allowance
Asph	asphalt
ASTM	ASTM International (formerly American Society for Testing and Materials)
A S/W	asphalt sidewalk
Ave	avenue
B or Bot	bottom
BB–BEAT	box beam bursting energy absorbing terminal
BBGR	box beam guide rail
BC	beginning of curve
BCA	Bell cable aerial
BCU	Bell cable underground
BCUM	Bell cable underground marker
BF	back face
Bfl	backfill
BFS	beginning of full superelevation
BH	button head bolt
B/L	base line
Bld (y)	boulder (y)
Bldg	building
Blk	block
Blvd	boulevard
BM	bench mark
Br	brick
B/R	bottom of rail
Brg	bearing
BS	beginning of superelevation
BVC	beginning of vertical curve
BWF	barbed wire fence
C	coated
CaB	carriage bolt
CAH	controlled access highway
Can	Canadian
CB	catch basin
CBMH	catch basin–maintenance hole
CC	concrete curb
C/C	centre to centre
CC&G	concrete curb with gutter
CG	concrete gutter
CGR	cable guide rail
Chkd	checked
CI	cast iron
CIP	clay pipe
Circ	circular
CJ	construction joint
C/L or ℄	centreline
CLF	chain link fence
Co	county
Con	concession
Conc or C	concrete
Const or C	construction
Cont	contract
CP	concrete pipe
CPCI	Canadian Precast/Prestressed Concrete Institute
Cr	creek or crushed
CS	circular curve to spiral
CSA	CSA Standards (formerly Canadian Standards Association)
CSP	corrugated steel pipe
CSPA	corrugated steel pipe arch
C S/W	concrete sidewalk
Culv	culvert
C/W	come with
CWB	Canadian Welding Bureau

D	ditch
Def	deflection
Deg	degree
DI	ditch inlet or ductile iron
Dia	diameter
DICB	ditch inlet catch basin
Dist	district
Div	division
D/W	driveway
Dwg	drawing
EB	eastbound
EBL	eastbound line
EC	end of curve
ED	earth ditching
EF	each face
EFS	end of full superelevation
Elev or El	elevation
EMH	electrical maintenance hole
Ent	entrance
EP	edge of pavement
Eq	equally
ES	edge of shoulder or end of superelevation
EVC	end of vertical curve
EW	each way
Exc	excavation
Exist	existing
Exp	expansion
Expy	expressway
Extn	extension
E_T	external distance of a spiralled curve
Fdn	foundation
FF	front face
FL	fence line
Ftg	footing
Fr	frame

G	grading
Ga	gauge
Galv	galvanized
GB	granual base
GBC	granual base course
GBfl	granular backfill
GC	grading and culverts
GD	grading and drainage
GL	ground level
GP	grade point
Gran	granular
GSB	granular sub base
HL	hot laid
HM	hot mix
HOC	hub on curve
HOST	hub on subtangent
HOT	hub on tangent
Hor	horizontal
HP	high point
HPC	high performance concrete
Ht	height
HT	high tension
HTL	high tension line
Hw	headwall
HWL	high water level
HWM	high water mark
Hwy	highway
Hyd	hydrant
IB	iron bar
ID	inside diameter
IF	iron fence or inside face
Incl (ing) (sive)	include (ing)(sive)
Inst	instrument
Inv Elev	invert elevation
IP	iron pipe
Jt or J	joint

L	length or length of curve
La	length of spiral between circular curve
LG	long
LH	left hand
Ls	length of spiral curve
LT	long tangent
LVC	length of vertical curve
LWL	low water level
M	middle
Max	maximum
Med	median
MH	maintenance hole
Min	minimum
Mon	monument
MTO	Ontario Ministry of Transportation
Mun	municipal
N (ing)	north (ing)
NB	northbound
NBL	northbound lane
NC	normal crown
NCHRP	National Cooperative Highway Research Program
NIC	not in contract
NTS	not to scale
OC	on centre
OD	outside diameter
OF	outside face
OG	original ground
Opass	overpass
OPSD	Ontario Provincial Standard Drawing
OPSS	Ontario Provincial Standard Specification
Org M	organic matter
Orig or O	original
Pavt	pavement
Perf	perforated
PF	picket fence
PG	plain galvanized or profile grade
PC	profile control
PCC	point of compound curve
PE	polyethylene
PI	point of intersection
PL	property line
POC	point on curve
PRC	point of reverse curve
Prof	profile
Prop	proposed
PVC	point on vertical curve or polyvinyl chloride
PVT	point of vertical tangent
R	radius
RC	rock cut
REF	reference
Reg (al)	region (al)
Reinf	reinforced
Reqd	required
Resurf	resurfacing
Rev	revision
R Exc	rock excavation
RF	rail fence or rock fill
RH	right hand
Rk	rock
Rnd	rounding
ROW	right–of–way
RP	reference point or registered plan
RR	rip–rap
RS	ripple strip
RSIC	Reinforced Steel Institute of Canada
RSS	retained soil system
RW	retaining wall
Rwy	railway

S	rate of superelevation
San	sanitary
SB	southbound
SBEAT	steel beam energy attenuating terminal
SBGR	steel beam guide rail
SBL	southbound lane
SC	spiral to circular curve
SD	side ditch
Sec (ary)	second (ary)
Serv Rd	service road
SF	stone fence
Sh Rk	shot rock
SHLG, Sh or SH	shoulder
SP	special provision
Spec	specification
SQ	square
SR	side road
ST	spiral to tangent or short tangent or storm sewer
St	stripping
Sta	station
Std	standard
Stm	storm
Str (al)	structure (al)
Sty	storey
SPCSA	structural plate corrugated steel arch (with footings)
SPCSP	structural plate corrugated steel pipe
SPCSPA	structural plate corrugated steel pipe arch
Surf	surface
S/W	sidewalk
T	top
TB	top of bank or turning basin
T&B	top and bottom
TCH	Trans Canada Highway
TG or T/G	top of grate
TP	top of pavement
TR or T/R	top of rail
Trans	transverse or transferred
TS	tangent to spiral or tensile strength
Twp	township
Typ	typical
UNO	unless noted otherwise
Upass	underpass
U/S	underside
Var	varies, variable
VC	vertical curve
VCP	vitrified clay pipe
Vert	vertical
Vol	volume
W	water main
WB	westbound
WBL	westbound lane
WF	wire fence
WIF	wrought iron fence
WL	water level
WMF	wire mesh fence
W/O	water out
WP	work project
WT	water table
WW	wing wall
WWF	welded wire fabric
WWR	welded wire reinforcement

NUMBER OF UNITS	NUMBER OF STOREYS OF THE BUILDING	MATERIAL USED IN SUPERSTRUCTURE OF BUILDING	NAME–OF–BUILDING	BASEMENT	REMARKS
A number followed by a hyphen for the number of units.	A number of designating the number of storeys of the building.	Letter preceding the name–of–building group.	Letter that designates the name of the building.	The letter B after name–of–building group denotes basement.	All descriptions shall contain a name–of–building group.
		Br brick C concrete CB concrete block F insulbrick F metal clad Fr frame M metal S stone St stucco	A apartment B barn C cabin F factory G garage Gr greenhouse H house O office PO post office R restaurant S shed SS service station ST store W warehouse	If no letter appears after the name, the building has no basement.	As a general rule, if there is ambiguity in the description, then the full abbreviated or long form description shall be written out.
2–	1 1/2 2				Examples: Arena Building Church Fire Hall Hotel Library Motel Rec Hall School
If description involves only one building, this group is omitted.	If description of building involves only one storey,this group is omitted.				
		Or combination of letters as a group, e.g., Br&St Brick & Stucco Br&S Brick & Stone.	Or combination of letters as a group, e.g., SS&R Service Station and Restaurant.		
		All descriptions shall contain this group.	All descriptions shall contain this group.		

ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2006 | Rev 1

ABBREVIATIONS

BUILDING DESCRIPTIONS

OPSD 100.050

Accep	acceptable
Agg	aggregate
Amor	amorphous
Asph	asphalt
BH	borehole
Bl	blue
Bld (y)	boulder (y)
Blds	boulders
Blk	black
Br	brown
BR	bedrock
BU	break up
CF	channel face
Cl (y)	clay (ey)
Co	coarse
Cob	cobbles
Comp	compact
Conc	concrete
Contam	contaminated
Cord	corduroy
Cr	crushed
D	dense
Decomp	decomposed
Dk	dark
D_R	relative density
E	earth
F	fine
FB	frost boil
FH	frost heave
Fib	fibrous
Fr Wat	free water
Gr (y)	gravel (ly)
Gran	granular
Grn	green
Gry	grey
H	heavy
Hi	highly
HM	hot mix
HP	high plasticity
Ip	plasticity index
L	loose
Liq	liquid
Lo	loam
Lt	light
Matl	material
Max	maximum
MDD	maximum dry density
Med	medium
Mod	moderate
Mott	mottled
MP	medium plasticity
Mrl	marl
Mul	mulch
MWD	maximum wet density
NFP	no further progress
NFP (blds)	no further progress (boulders)
Num	numerous
Ob	overburden
Occ	occasional
Ora	orange
Org	organic
Org M	organic matter
Pavt	pavement
Pedo	pedological
Pen Mac	penetration macadam
Poss	possible
PST	prime and surface treated
Psty	polystyrene
Quant	quantity
Reinf	reinforced
RF	rock fill
RSS	remoulded shear strength
Sa (y)	sand (y)
Sat	saturated
SH	shale
Sh Rk	shot rock
Si (y)	silt (y)
Sl (y)	slight (ly)
SP	slight plasticity
SSM	select subgrade material
St	sensitivity
Stn (y)	stone (y)
Stks	streaks
Surf	surface
Temp	temperature
TH	test hole
TP	test pit
Tps	topsoil
Tr	trace
Unreinf	unreinforced
USS	undisturbed shear strength
Varv	varved
VF	very fine
w	field moisture content
W	with
W_L	liquid limit
Wd (y)	wood (y)
Weath	weathered
Wopt	optimum moisture content
Wp	plastic limit
WT	water table
Yel	yellow

SUSCEPTIBILITY TO FROST HEAVING

HSFH – High
MSFH – Medium
LSFH – Low

ONTARIO PROVINCIAL STANDARD DRAWING

ABBREVIATIONS

GEOTECHNICAL

Nov 2006 | Rev 1


OPSD 100.060

CM	concrete monument
SIB	standard iron bar
SSIB	short standard iron bar
RB	rock bar
RP	rock post
RPL	rock plug
RIB	round iron bar
CC	cut cross
CP	concrete pin
IB	iron bar
PK	spike, nail, rock rivet, etc.
GBM 819768123	geodetic bench mark (primary vertical control point)
BM	Ministry of Transportation bench mark (vertical project control point)
HCP	horizontal project control point
HCM plus number	primary horizontal control monument
PI 9+916.211	point of intersection
	hub on tangent
NAIL	nail

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2006	Rev	1
TOPOGRAPHY PLAN FEATURES MONUMENT FEATURES			
	OPSD 101.010		



top of rock cut
hachure for rock/earth cut/fill
bottom of rock cut




rock outline & string
of rock outcrop, Note 1



asphalt outline &
asphalt string, Note 1



bank of river, Note 1




concrete outline &
concrete string, Note 1



door sill, Note 1

entrance centreline, Note 1




gravel outline &
gravel string, Note 1

railway ballast edge, Note 1

railway ballast top, Note 1

original ground string, Note 1



stream bed, Note 1


stock pile or pit

toe of fill sideslope, Note 1

NOTE:

1 These items are not normally plotted.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2006	Rev	1
TOPOGRAPHY PLAN FEATURES GROUND FEATURES			
	OPSD 101.011		



NOTE:

1 These items are not normally plotted.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2006	Rev	1
TOPOGRAPHY PLAN FEATURES ROAD FEATURES			
	OPSD 101.012		

BARRIER FEATURES


gate


guide rail

fence line at grade



barrier top, Note 1

barrier bottom


inertial barrier outline

fence line – not for terrain model



guide rail post elevation, Note 1



guide rail wire elevation, Note 1


noise barrier at grade

VEGETATION FEATURES



bush outline


tree


hedge

woods trunkline, Note 1

NOTE:

1 These items are not normally plotted.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2006	Rev	1
TOPOGRAPHY PLAN FEATURES BARRIER AND VEGETATION FEATURES			

ONTARIO STANDARDS – MUNICIPAL – PROVINCIAL

OPSD 101.013

AN	anchor for pole		
⊠	hydro tower outline		
● GM	gas meter	○ H	hydro pole
● GV	gas valve	○ LS	light standard
● WM	water meter	○ PO	pole other
● WV	water valve	◯ PW	pole well (crib)
○ B	Bell pole	□ TB	terminal box
○ B&H	Bell & hydro pole	⋈ TS	traffic signal pole
○ FH	fire hydrant	● V	vent

○ BCUM ○ GUM ○ PCUM	underground bell, gas, or power cable markers
○ W	well
+ HC	hydro crossing ground elevation, Note 1
+ HW	hydro crossing wire elevation, Note 1
——— G ———	gas main
——— W ———	water main
——— TVU ———	TV cable
——— HCU ———	hydro cable underground
Description	pipeline
——— BCU ———	Bell cable underground
——— UT ———	Utility, other underground

NOTE:

1 These items are not normally plotted.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2006	Rev	1
TOPOGRAPHY PLAN FEATURES			
UTILITY FEATURES			
	OPSD 101.014		

□ CB	catch basin, center
□ DI	ditch inlet, centre of grate
○ MH	maintenance hole
+ CV	culvert invert elevation, Note 1
+ DB	ditch inlet bottom of opening, Note 1
+ DT	ditch inlet top of opening, Note 1
+ FR	frustum elevation, Note 1
+ SU	sump elevation, Note 1
———	high water mark
═══	culvert
——— ◄	bottom of ditch with flow
———	drainage centerline
Lake	edge of water
RR	rip–rap outline
Swamp	swamp or muskeg
——— ST ———	storm sewer
——— SAN ———	sanitary sewer

NOTE:



1 These items are not normally plotted.

ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2006 | Rev 1




TOPOGRAPHY PLAN FEATURES

DRAINAGE FEATURES

OPSD 101.015

CBP	concrete bridge pillar
	building, silo
	grid north orientation
DD	deck drain
Com S	commercial sign

BN	bullnose, Note 1
BO	borehole
EV	miscellaneous elevation, Note 1
GFL	gate with flashing light
RLS	railway sign/signal
RCS	railway crossing sign

	railway track
	cemetery outline
	wooden deck/dock outline
	expansion joint
	gabion baskets
	hand rail
	overhead sign
	retaining wall
	sidewalk
	walkway/trail/path
N 4 750 000	co–ordinate grid
	existing alignment/reference line
	existing entrance alignment
	existing sideroad alignment

NOTE:

1 These items are not normally plotted.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2006	Rev	1
TOPOGRAPHY PLAN FEATURES MISCELLANEOUS FEATURES			
	OPSD 101.016		

property limit

city, town or village boundary

general boundary/property line

subdivision lot line

original concession/lot line

fence on highway right–of–way or property limit

highway right–of–way, highway property limit, no fence

right–of–way, except highway ROW, no fence

fences excluding those outlinings ROW limits

limited interest, permanent


limited interest, temporary

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2008	Rev	3
TOPOGRAPHY PLAN FEATURES RIGHT–OF–WAY FEATURES			

OPSD 101.017

To indicate removal of a feature, use the appropriate topography plan feature with cross out lines.

Examples:




guide rail removal




culvert removal




maintenance hole and sewer removal




concrete pavement with bituminous surface to be removed



bituminous pavement to be removed




concrete pavement to be removed




area to be close cut cleared



area to be cleared



area to be grubbed



area to be cleared and grubbed

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2006	Rev	1
REMOVALS LEGEND			
			OPSD 102.010


○ NUMBER	MH	existing	maintenance hole	● NUMBER	MH	new	
□ NUMBER	CB	existing	catch basin	■ NUMBER	CB	new	


□□ TICB, TIMH, TDICB, TDIMH — twin inlet catch basin or maintenance hole, twin ditch, inlet catch basin or maintenance hole

 sub–drain, flow indicated

 curb, gutter, or curb with gutter transition

 drop curb


 gutter outlet 90 °


 gutter outlet 45 °

 storm sewer


 sanitary sewer

 culvert

 culvert with headwall

 culvert with steel end apron

 ditches, V type

 ditches, flat bottom

 watercourse, 3m wide and over

 flow arrow


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2006	Rev	1
NEW CONSTRUCTION LEGEND 1			

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · O P S

OPSD 103.010




backfill




gore area




rip rap



gabions




pavement



miscellaneous paving




concrete section




earth section



rock section




rock shatter



paved shoulder




pier



retaining wall with height
RSS–retained soil system
CIP–cast–in–place



sidewalk




guide rail (cable, steel beam or box beam) or guide post



sod (nursery or field)



Inertial barrier modules



plan orientation

Traffic flow 

direction of traffic

ONTARIO PROVINCIAL STANDARD DRAWING

April 2008 | Rev 2

NEW CONSTRUCTION

LEGEND 2

OPSD 103.011




machined surface

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2007 | Rev | 0

MISCELLANEOUS SYMBOLS


OPSD 104.010



TANGENT SECTION



SUBDRAIN DETAIL
WHERE APPLICABLE




SUPERELEVATED SECTION

NOTES:

1 Cut slope shall be 3H:1V or steeper when specified.
2 Fill slope shall be 3H:1V or flatter when specified.
3 Distance shall be 1.5m minimum when ditch is not required.


A This OPSD to be read in conjunction with OPSD 202.010 and OPSD 202.020.
B All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2009	Rev	2
EARTH/SHALE GRADING			
UNDIVIDED RURAL			
	OPSD 200.010		




TANGENT SECTION

CUT SECTION



TANGENT SECTION

FILL SECTION



SUPERELEVATED SECTION


NOTES:

1 Cut slope shall be 3H:1V or steeper when specified.
2 Fill slope shall be 4H:1V or flatter when specified.
3 Distance shall be 2.5m minimum when ditch is not required.


A This OPSD to be read in conjunction with OPSD 202.010 and OPSD 202.020.
B All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2009	Rev	2
EARTH/SHALE GRADING DIVIDED RURAL			
	OPSD 200.020		


CUT SECTION




FILL SECTION



TANGENT SECTION



SUPERELEVATED SECTION



ALTERNATIVE DETAIL
WHERE SPECIFIED

NOTES:

1 Distance shall be 1.5m minimum when ditch is not required.

2 Where top of rock fill embankment is less than 2.0m above original ground, flatten slope with surplus excavated material.

A Shale shall be treated according to earth grading standards.

B This OPSD to be read in conjunction with OPSD 202.010 and OPSD 202.020.

C All dimensions are in metres unless otherwise shown.

LEGEND:

h – Height of rock face


ONTARIO PROVINCIAL STANDARD DRAWING

ROCK GRADING

UNDIVIDED RURAL

Nov 2009 | Rev 2

OPSD 201.010



NOTES:

1 Distance shall be 1.5m minimum when ditch is not required.

2 Where the top of rock fill embankment is less than 2.0m above original ground, flatten slope with surplus excavated material.

A Shale shall be treated according to earth grading standards.

B This OPSD to be read in conjunction with OPSD 202.010 and OPSD 202.020.

C All dimensions are in metres unless otherwise shown.

LEGEND:

h – Height of rock face

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2009 | Rev 2

ROCK GRADING


DIVIDED RURAL

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS

OPSD 201.020



EARTH EMBANKMENT



ROCK EMBANKMENT

NOTES:


1 Benches 2m minimum in width are required along slopes at maximum vertical intervals as shown.

A Height of fill is the vertical difference between top of subgrade and top of original ground measured at new road centreline.


B Surplus excavated material placed shall not extend beyond the right–of–way.

C All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	3
SLOPE FLATTENING USING SURPLUS EXCAVATED MATERIAL ON EARTH OR ROCK EMBANKMENT			
	OPSD 202.010		



CONTOUR PLAN



ISOMETRIC VIEW

LEGEND:

h – Height of fill

NOTES:


1 Slope shall be as specified.

2 Embankment material shall be rock fill or other granular material.


A Height of fill shall be the vertical difference between top of subgrade and top of original ground measured at new road centreline.

B All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2013	Rev	3
DRAINAGE GAP FOR SLOPE FLATTENING ON ROCK OR GRANULAR EMBANKMENT			
	OPSD 202.020		



PLAN




SECTION A–A




SECTION B–B

FILL SECTION



SECTION A–A



SECTION B–B

CUT SECTION

NOTES:

1 Measured from traffic side face of steel beam at the first post.


2 Slope shall be flatter when specified.

3 Slope shall be steeper when specified.

A For leaving end and constrained approach end applications, see OPSD 202.032.


B All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	1
ROADWAY WIDENING FOR STEEL BEAM ENERGY ATTENUATING TERMINAL APPROACH END			
		OPSD 202.031	




LEAVING END **CONSTRAINED APPROACH END**

PLAN



SECTION A–A **SECTION B–B**

FILL SECTION



SECTION A–A **SECTION B–B**

CUT SECTION

NOTES:

1 Measured from traffic side face of steel beam at the first post.


2 Slope shall be flatter when specified.

3 Slope shall be steeper when specified.


A For approach end application see OPSD 202.031.

B All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	2
ROADWAY WIDENING FOR STEEL BEAM ENERGY ATTENUATING TERMINAL LEAVING END AND CONSTRAINED APPROACH END			
			OPSD 202.032



PLAN




SECTION A–A




SECTION B–B

FILL SECTION



SECTION A–A



SECTION B–B

CUT SECTION

NOTES:


1 Measured from impact head or nose assembly of terminal.

2 Slope shall be flatter when specified.

3 Slope shall be steeper when specified.

A All dimensions are in meters unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	1
ROADWAY WIDENING SINGLE SIDED ENERGY ATTENUATING TERMINALS APPROACH END			
	OPSD 202.033		




NOTES:

1 Measured from edge of shoulder to face of post ①.
2 Slope shall be flatter when specified.
3 Slope shall be steeper when specified.
A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	0
ROADWAY WIDENING FOR STEEL BEAM TERMINAL ON INSIDE OF CURVE			
	OPSD 202.037		



PLAN




SECTION A–A
FILL SECTION




SECTION A–A
CUT SECTION

NOTES:
1 Measured from edge of shoulder to face of post ①.
2 Slope shall be flatter when specified.
3 Slope shall be steeper when specified.
A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	0
ROADWAY WIDENING FOR STEEL BEAM TERMINAL ON OUTSIDE OF CURVE			
	OPSD 202.038		



PLAN




SECTION A–A




SECTION B–B

FILL SECTION



SECTION A–A




SECTION B–B

CUT SECTION


NOTES:

1 Existing earth slope shall be benched according to OPSD 208.010.
2 Slope shall be flatter when specified.
3 Slope shall be steeper when specified.
4 Start point for length of need shall be used as reference point.
A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2018	Rev	0
ROADWAY WIDENING FOR HIGH TENSION CABLE TERMINALS SLOPE INSTALLATION			
	OPSD 202.040		



PLAN




SECTION A–A




SECTION B–B

FILL SECTION



SECTION A–A




SECTION B–B

CUT SECTION

NOTES:

1 Existing earth slope shall be benched according to OPSD 208.010.
2 Slope shall be flatter when specified.
3 Slope shall be steeper when specified.
4 Start point for length of need shall be used as reference point.
A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2018	Rev	0
ROADWAY WIDENING FOR HIGH TENSION CABLE TERMINALS SHOULDER INSTALLATION			
	OPSD 202.041		



LEGEND:

Embankment materials as specified

Excavated swamp material

Excavate and backfill as specified

h – Height of fill

d – Depth of sub–excavation

NOTE:

A Height of fill is the vertical difference between subgrade and top of swamp measured at new road centreline.


ONTARIO PROVINCIAL STANDARD DRAWING

EMBANKMENTS OVER SWAMP


NEW CONSTRUCTION

Nov 2017 | Rev 4


OPSD 203.010



WIDENING



GRADE CHANGE



RE–ALIGNMENT AND GRADE CHANGE

LEGEND:


- *h* – Height of fill
- *d* – Depth of sub–excavation
- Embankment materials as specified
- Excavated swamp material
- Excavate and backfill as specified

NOTES:

A Height of fill is the vertical difference between subgrade and top of swamp measured at new road centreline.


B Widening of existing earth embankments shall be benched according to OPSD 208.010.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	4
EMBANKMENTS OVER SWAMP EXISTING SLOPE EXCAVATED			
			OPSD 203.020



WIDENING

GRADE CHANGE



RE–ALIGNMENT AND GRADE CHANGE

NOTES:

A Topsoil shall be stripped from existing slopes.

B Height of fill is the vertical difference between subgrade and top of swamp measured at new road centreline.

C Widening of existing earth embankments shall be benched according to OPSD 208.010.

LEGEND:

h – Height of fill


d – Depth of sub–excavation


Embankment materials as specified


Excavated swamp material

Excavate and backfill as specified

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	4
EMBANKMENTS OVER SWAMP EXISTING SLOPES MAINTAINED			
			OPSD 203.030







LEGEND:

h – Height of fill
d – Depth of sub–excavation
D – Outside diameter or width

Embankment materials as specified

Excavate and backfill as specified

NOTES:

1 Width of excavation shall be *D* +1.0m for culverts ≤1000mm *D* and 2*D* for culverts >1000mm *D*.

A Height of fill is the vertical difference between subgrade and top of swamp measured at new road centreline.

SECTION A–A – BOX

SECTION A–A – PIPE


ONTARIO PROVINCIAL STANDARD DRAWING

EMBANKMENTS OVER SWAMP AT CULVERTS ≤ 1500mm

Nov 2022 | Rev 5

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 203.040



LEGEND:

d = Depth of roadbed granular

NOTES:

1 Boulders partially within depth d but not deeper than 1.0m below profile grade shall be removed completely.


2 Boulders partially within depth d but deeper than 1.0m below profile grade shall be shattered to 0.6m below subgrade and then excavated to a minimum of 0.3m below subgrade.

A Excavation below subgrade shall be backfilled with approved material.


B Profile grade and subgrade lines apply across the transverse section.

C All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	3
BOULDER TREATMENT CUT SECTIONS–SUBGRADE			
	OPSD 204.010		



LONGITUDINAL SECTION



TRANSVERSE SECTION A–A


NOTES:

1 Longitudinal runout Y start and finish points vary across the transverse section, due to original overburden thickness. Profile grade and subgrade lines apply across the transverse section.

LEGEND:

d – Depth of granular base and subbase
t – Transition treatment depth, as specified
D_a – Depth of organic, leached, and accumulated layers, as specified
Y – Transition length through D_a


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	3
TRANSITION TREATMENT			
EARTH CUT TO EARTH FILL			
	OPSD 205.010		



WITHOUT OVERBURDEN

WITH OVERBURDEN

LONGITUDINAL SECTIONS



TRANSVERSE SECTION A–A

NOTES:

1 Excavate overburden for transition where applicable.

2 Rock or granular fill.


A All dimensions are in metres unless otherwise shown.

LEGEND:


t – Transition treatment depth, as specified

d – Depth of granular base and subbase, as specified

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	3
TRANSITION TREATMENT ROCK CUT TO ROCK FILL			
	OPSD 205.020		




WITHOUT OVERBURDEN



WITH OVERBURDEN

LONGITUDINAL SECTIONS



TRANSVERSE SECTION A–A

NOTES:

1 Longitudinal runout Y start and finish points vary across the transverse section due to differences in original overburden thickness. Profile grade and subgrade lines apply across the transverse section.

2 Rock or granular fill.

A Carry out sufficient shatter at transition to obtain drainage.

B All dimensions are in metres unless otherwise shown.

LEGEND:

t –Transition treatment depth, as specified

d_e –Depth of granular base and subbase over earth

d_r –Depth of granular base and subbase over rock

X –Taper to subgrade over $20(t - d_e)$

Y –Transition length, 15m maximum

ONTARIO PROVINCIAL STANDARD DRAWING


TRANSITION TREATMENT

ROCK CUT TO EARTH FILL


Nov 2016 | Rev 3

ONTARIO STANDARDS · MUNICIPAL–PROVINCIAL · O P S

OPSD 205.030



EARTH FILL TO ROCK FILL



EARTH FILL TO GRANULAR FILL

NOTES:

1 Rock or granular fill.

A Embankment slopes to transition uniformly over distance X_R and X_E.

B Profile grade and subgrade lines apply across the transverse section.

LEGEND:

d_e – Depth of granular base and subbase over earth


d_r – Depth of granular base and subbase over rock fill

t – Transition treatment depth, as specified


X_E – Length of transition for earth fill, 15m maximum

X_R – Length of transition in rock fill

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev 3
TRANSITION TREATMENT EARTH FILL TO ROCK FILL AND EARTH FILL TO GRANULAR FILL		OPSD 205.040




NON–FROST SUSCEPTIBLE SOILS



FROST SUSCEPTIBLE SOILS

LONGITUDINAL SECTIONS



TRANSVERSE SECTION A–A

NOTES:

1 Longitudinal runout Y start and finish points vary across the transverse section due to differences in original overburden thickness. Profile grade and subgrade line apply across the transverse section.

2 Rock or granular fill.

A Carry out sufficient shatter at transitions to obtain drainage.

B All dimensions are in metres unless otherwise shown.

LEGEND:

t – Transition treatment depth, as specified


d_e – Depth of granular base and subbase over earth

d_r – Depth of granular base and subbase over rock


X – Taper to subgrade over $20(t - d_e)$

Y – Transition length, 15.0m maximum


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	3
TRANSITION TREATMENT ROCK CUT TO EARTH CUT			
	OPSD 205.050		



LONGITUDINAL SECTION



TRANSVERSE SECTION WITH DITCH



TRANSVERSE SECTION WITH SUBDRAIN

NOTES:

1 Material shall be excavated and replaced with specified granular material.

A Profile grade and subgrade lines apply across the transverse sections.


B All dimensions are in metres unless otherwise shown.

LEGEND:


d – Depth of granular base and subbase

k – Depth of frost treatment below profile grade as specified

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	4
FROST HEAVE TREATMENT			
	OPSD 205.060		



TANGENT SECTION



SUPERELEVATED SECTION

NOTES:

1 Rounding shall be 0.5m or greater when specified.
2 Slope shall be 3H:1V or flatter when specified.
3 Crossfall shall be as specified in the contract documents.
A All dimensions are in metres unless otherwise shown.

LEGEND:

Granular base Granular subbase


ONTARIO PROVINCIAL STANDARD DRAWING

GRANULAR COURSES


UNDIVIDED RURAL

Nov 2018 | Rev 2


OPSD 206.010



TANGENT SECTION



SUPERELEVATED SECTION
MEDIAN ON LOW SIDE



SUPERELEVATED SECTION
MEDIAN ON HIGH SIDE

LEGEND:

Granular base Granular subbase

NOTES:

1 Rounding shall be 1.0m or greater when specified.
2 Slope shall be 4H:1V or flatter when specified.
3 Crossfall shall be as specified in the contract documents.

A All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GRANULAR COURSES


DIVIDED RURAL

Nov 2018 | Rev 2


OPSD 206.020




SUBDRAIN OUTLET PIPE DETAIL




SINGLE OUTLET PIPE TRENCH DETAIL



OUTLET PIPE RUNOUT DETAIL



OUTLET PIPE CONNECTION TO CATCH BASIN DETAIL



DUAL OUTLET PIPE TRENCH DETAIL

NOTES:

1 Embedment material shall be 19mm clear stone or granular as specified.
2 Outlet pipe and subdrain trench embedment material shall be wrapped with geotextile.
3 For catch basin connections, outlet pipe trenches backfilled with granular do not require geotextile wrap.
4 Install outlet pipe flush with inside face of catch basin.

A Use compatible manufactured fittings for all connectors and couplings.

B All dimensions are in millimetres unless otherwise shown

ONTARIO PROVINCIAL STANDARD DRAWING


SUBDRAIN PIPE CONNECTION AND OUTLET

RURAL


Nov 2018 | Rev 2

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 206.050



TANGENT SECTION



SUPERELEVATED SECTIONS

LEGEND:

S – rate of superelevation in %

- Open graded drainage layer
- Granular
- Concrete pavement

NOTES:

1 For longitudinal joint details refer to OPSD 552.010.
2 Paved shoulder as specified.
3 Rounding shall be 0.5m or greater as specified.
4 For drainage system details refer to OPSD 207.041 and 207.044.
5 Slope shall be 4H:1V or flatter when specified.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

CONCRETE PAVEMENT ON OPEN GRADED DRAINAGE LAYER DIVIDED HIGHWAY


Nov 2016 | Rev 3


ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 207.010



TANGENT SECTION





SUPERELEVATED SECTIONS

NOTES:

1 For longitudinal joint details refer to OPSD 552.020.
2 Paved shoulder as specified.
3 Rounding shall be 0.5m or greater as specified.
4 For drainage system details refer to OPSD 207.041 and 207.044.
5 Slope shall be 4H:1V or flatter when specified.

A All dimensions are in millimetres unless otherwise shown.

LEGEND:

S – rate of superelevation in %
Open graded drainage layer
Granular
Concrete base


ONTARIO PROVINCIAL STANDARD DRAWING

COMPOSITE PAVEMENT ON OPEN GRADED DRAINAGE LAYER DIVIDED HIGHWAY


Nov 2016 | Rev 3

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S


OPSD 207.020



CONCRETE PAVEMENT



COMPOSITE PAVEMENT



SUBDRAIN DETAIL

LEGEND:

- Granular
- Open graded drainage layer

NOTES:

1 For longitudinal joint details refer to OPSD 552.010 and 552.020.

A Drainage system outlets at every catch basin per OPSD 207.044.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


CONCRETE AND COMPOSITE PAVEMENT ON OPEN GRADED DRAINAGE LAYER

URBAN SECTION

Nov 2016 | Rev 2

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL

OPSD 207.030



HOT MIX ASPHALT PAVEMENT

EXPOSED CONCRETE OR COMPOSITE PAVEMENT

LEGEND:

- Open graded drainage layer
- Granular
- Concrete pavement


NOTES:

1 To prevent contamination of the trench embedment material, the 300mm geotextile flaps shall be fastened to securely enclose the subdrain trench until immediately prior to placing the open graded drainage layer, at which time the flaps shall be opened.


A This standard to be read in conjunction with OPSD 207.044.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev 4
SUBDRAIN PIPE OPEN GRADED DRAINAGE LAYER HOT MIX ASPHALT, CONCRETE, OR COMPOSITE PAVEMENT		**OPSD 207.041**




SUBDRAIN OUTLET PIPE DETAIL




SINGLE OUTLET PIPE TRENCH DETAIL



OUTLET PIPE RUNOUT DETAIL



OUTLET PIPE CONNECTION TO CATCH BASIN DETAIL



DUAL OUTLET PIPE TRENCH DETAIL

NOTES:

1 Embedment material shall be open graded drainage layer aggregate.
2 Outlet pipe trench embedment material shall be wrapped with geotextile.
3 For catch basin connections, outlet pipe trenches backfilled with granular do not require geotextile wrap.
4 Install outlet pipe flush with inside face of catch basin.

A This standard to be read in conjunction with OPSD 207.041.
B Use compatible manufactured fittings for all connectors and couplings.
C All dimensions are in millimetres unless otherwise shown.

LEGEND:

- Open graded drainage layer
- Granular
- Concrete pavement


ONTARIO PROVINCIAL STANDARD DRAWING

SUBDRAIN PIPE CONNECTION AND OUTLET OPEN GRADED DRAINAGE LAYER

Nov 2016 | Rev 5

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 207.044




NOTES:

1 When the subgrade is below the existing outside edge of rounding, benching shall be carried out below the point where the subgrade intersects the existing slope.


2 Benches shall be excavated one level at a time and the fill placed and compacted before the next bench is excavated.

A Benching is not required on existing slopes flatter than 3H:1V.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2019	Rev	4
BENCHING OF EARTH SLOPES			
	OPSD 208.010		



TYPE 1
HALF GRADING SECTION
HOT MIX WITH GRANULAR GRADE RAISE



TYPE 2
HALF GRADING SECTION
RESURFACING AND GRANULAR WIDENING

LEGEND:


Granular base Granular subbase

NOTES:


1 Rounding shall be 0.5m or greater when specified.
2 Depth of excavation shall be as specified, and should be equal to or lower than existing subgrade.
3 Slope shall be as specified.
4 Crossfall shall be as specified.
5 Existing pavement under granular grade raise shall be removed, processed, or left in–place, as specified.

A This OPSD to be read in conjunction with OPSD 208.010.
B All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
RURAL PAVEMENT WIDENING			
	OPSD 209.010		



FILL SECTION



CUT SECTION

NOTES:

1 Rounding shall be 0.5m or greater when specified.
2 Depths and locations of paving courses as specified.
3 Subgrade elevation for widening shall be lower than or match existing subgrade level to ensure drainage.
4 Slope shall be as specified.
5 Crossfall shall be as specified.

LEGEND:

Granular base Granular subbase


A For grading requirements beyond toe of embankment or CL of ditch, this OPSD to be read in conjunction with OPSD 200.010 or 200.020, as applicable.
B All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

RURAL PAVEMENT WIDENING CURB WITH GUTTER

Nov 2018 | Rev 3

OPSD 209.011



ALTERNATIVE DETAIL
when specified

NOTES:

1 Approved rock or granular material.

2 Distance shall be 1.5m minimum when ditch is not required.

A Shale shall be treated according to earth grading standards.

B All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


WIDENING

EXISTING ROCK CUT WITH GRADE RAISE


Nov 2016 | Rev 3

ONTARIO STANDARD MUNICIPAL – PROVINCIAL


OPSD 209.020



TYPE 1 – GRANULAR SHOULDER



TYPE 2 – FULLY PAVED SHOULDER



TYPE 3 – PARTIALLY PAVED SHOULDER

NOTES:

1 Rounding shall be 0.5m or greater when specified.


2 Slope shall be 3H:1V or flatter when specified.

3 Where cable and steel beam guide rail has been installed prior to shoulder paving and where shoulder paving is to be placed adjacent to the guide rail, the outside edge of shoulder paving shall end 300mm from the face of the guide rail.


4 Partially paved shoulder width shall be 0.5m minimum.

A All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
TANGENT SHOULDERS RURAL			
	OPSD 210.010		



TYPE 1 – GRANULAR SHOULDER



TYPE 2 – FULLY PAVED SHOULDER



TYPE 3 – PARTIALLY PAVED SHOULDER


CROSSFALL, %													
Paved driving lane and partially paved shoulder	+6	+5	+4	+3	+2	+1	0	−1	−2	−3	−4	−5	−6
Shoulder	−2	−2	−2	−3	−3	−3	−4	−5	−6	−6	−6	−6	−6

NOTES:


1 Rounding shall be 0.5m or greater when specified.
2 Slope shall be 3H:1V or flatter when specified.
3 Where cable and steel beam guide rail has been installed prior to shoulder paving and where shoulder paving is to be placed adjacent to the guide rail, the outside edge of shoulder paving shall end 300mm from the face of the guide rail.
4 Partially paved shoulder width shall be 0.5m minimum.

A All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
SUPERELEVATED SHOULDERS RURAL			
	OPSD 210.020		



GRANULAR SHOULDER WITH OR WITHOUT GUIDE RAIL



PAVED SHOULDER WITH GUIDE RAIL



PAVED SHOULDER WITHOUT GUIDE RAIL


NOTES:

1 Extent of granular sealer.


2 When the width of granular shoulder in front of the guide rail is 300mm or less, granular sealer may be applied by hand spraying for the full width of this application.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	4
GRANULAR SEALING			
	OPSD 210.070		



TANGENT SECTION



SUPERELEVATED SECTION


CROSSFALL TABLE, %													
Paved driving lane and partially paved shoulder	+6	+5	+4	+3	+2	+1	0	−1	−2	−3	−4	−5	−6
Granular shoulder	−2	−2	−2	−3	−3	−3	−4	−5	−6	−6	−6	−6	−6

NOTES:


1 Minimum width of granular shoulder 1.0m.
2 Rounding shall be 0.5m or greater, when specified.
3 Thickness of hot mix paving courses as specified.
4 Partially paved shoulder shall be 0.5m minimum.

A All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
PARTIALLY PAVED SHOULDERS EXISTING PAVEMENT MAINTAINED			
	OPSD 211.010		



TANGENT SECTION



SUPERELEVATED SECTION


CROSSFALL TABLE, %													
Paved driving lane and partially paved shoulder	+6	+5	+4	+3	+2	+1	0	−1	−2	−3	−4	−5	−6
Granular shoulder	−2	−2	−2	−3	−3	−3	−4	−5	−6	−6	−6	−6	−6

NOTES:


1 Minimum width of granular shoulder 1.0m.
2 Rounding shall be 0.5m or greater, when specified.
3 Partially paved shoulder shall be 0.5m minimum.

A All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
PARTIALLY PAVED SHOULDERS EXISTING PAVEMENT RESURFACED			
			OPSD 211.020



CASE 1



CASE 2


LEGEND:

- Existing pavement
- Hot mix padding, Note 2
- Hot mix surface, hot mix binder, Note 1


NOTES:

1 Depths and locations of paving or levelling courses or both shall be as specified.
2 Pavement widening or padding or both when specified.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
RESURFACING WITH CROSSFALL CORRECTION WITH HOT MIX ASPHALT TANGENT SECTION			
	OPSD 212.010		




CASE 1



CASE 2



CASE 3



CASE 4

CROSSFALL TABLE, %													
Paved driving lane	+6	+5	+4	+3	+2	+1	0	−1	−2	−3	−4	−5	−6
Granular shoulder	−2	−2	−2	−3	−3	−3	−4	−5	−6	−6	−6	−6	−6

LEGEND:


- Existing pavement
- Hot mix padding, Note 2
- Hot mix surface, hot mix binder, Note 1

NOTES:


1 Depths and locations of paving or levelling courses or both shall be as specified.

2 Pavement widening or padding or both when specified.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
RESURFACING WITH CROSSFALL CORRECTION WITH HOT MIX ASPHALT SUPERELEVATED SECTION			
	OPSD 212.020		



TANGENT



SUPERELEVATED

CROSSFALL TABLE, %													
Paved driving lane	+6	+5	+4	+3	+2	+1	0	−1	−2	−3	−4	−5	−6
Granular shoulder	−2	−2	−2	−3	−3	−3	−4	−5	−6	−6	−6	−6	−6

LEGEND:

Existing pavement


Hot mix surface, hot mix binder, Note 1

NOTES:


1 Depths and locations of paving or levelling courses or both shall be as specified.

2 Pavement widening or padding or both when specified.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
RESURFACING EXISTING CROSSFALL MAINTAINED			
			OPSD 212.030



CURVE WITHOUT SPIRAL



CURVE WITH SPIRAL

NOTES:

A $L = L_S$ Length of spiral curve or equivalent spiral.

B Full widening shall be attained over spiral curve or equivalent spiral.

C Widening shall be divided evenly between the inside and outside of the curve.

D Widening at intermediate points shall be proportioned to produce a smooth edge of pavement.


ONTARIO PROVINCIAL STANDARD DRAWING

PAVEMENT WIDENING ON CURVES


WIDENING ON BOTH SIDES OF CURVE
WITH OR WITHOUT SPIRALS

Apr 2022 | Rev 1

OPSD 213.010



CURVE WITHOUT SPIRAL



CURVE WITH SPIRAL

NOTES:

A $L = L_S$ Length of spiral curve or equivalent spiral.

B Full widening shall be attained over spiral curve or equivalent spiral.

C Widening at intermediate points shall be proportioned to produce a smooth edge of pavement.

ONTARIO PROVINCIAL STANDARD DRAWING


PAVEMENT WIDENING ON CURVES

WIDENING ON INSIDE OF CURVES
WITH OR WITHOUT SPIRALS


Apr 2022 | Rev 1

ONTARIO STANDARDS • MUNICIPAL - PROVINCIAL • O P S

OPSD 213.020



TANGENT SECTION



SUPERELEVATED SECTION

LEGEND:

S – rate of superelevation in %

NOTES:

1 Fill and cut slopes shall be 3H:1V or flatter when specified.

2 Where steel beam guide rail is specified, the minimum rounding shall be 1.0m, with 0.5m specified from edge of shoulder to rounding breakpoint.

A All dimensions are in metres unless otherwise shown.

TABLE
FOR SUPERELEVATED SECTION

	CROSS FALL %												
Paved driving lane	+6	+5	+4	+3	+2	+1	0	−1	−2	−3	−4	−5	−6
Granular shoulder	−2	−2	−2	−3	−3	−3	−4	−5	−6	−6	−6	−6	−6


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2016 | Rev 2


SINGLE LANE RAMP GRADING FOR ASPHALT PAVEMENT WITH GRANULAR BASE AND SHOULDER

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 214.010



TANGENT SECTION



SUPERELEVATED SECTION

LEGEND:

S – rate of superelevation in %

NOTES:

1 Fill and cut slopes shall be 3H:1V or flatter when specified.

2 Where steel beam guide rail is specified, the minimum rounding shall be 1.0m, with 0.5m specified from edge of paved shoulder to rounding breakpoint.

A All dimensions are in metres unless otherwise shown.

TABLE
FOR SUPERELEVATED SECTION


CROSS FALL %													
Paved driving lane	+6	+5	+4	+3	+2	+1	0	−1	−2	−3	−4	−5	−6
Paved shoulder	−2	−2	−2	−3	−3	−3	−4	−5	−6	−6	−6	−6	−6

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2016 | Rev | 2

SINGLE LANE RAMP GRADING FOR ASPHALT PAVEMENT WITH GRANULAR BASE AND ASPHALT SHOULDER

OPSD 214.020



TANGENT SECTION



SUPERELEVATED SECTION

LEGEND:

S – rate of superelevation in %

NOTES:

1 Fill and cut slopes shall be 3H:1V or flatter when specified.
2 Where steel beam guide rail is specified, the minimum rounding shall be 1.0m, with 0.5m specified from edge of paved shoulder to rounding breakpoint.
3 Where steel beam guide rail is specified, width of berm shall be 1.0m.

A All dimensions are in metres unless otherwise shown.


TABLE
FOR SUPERELEVATED SECTION

CROSS FALL %													
Paved driving lane	+6	+5	+4	+3	+2	+1	0	−1	−2	−3	−4	−5	−6
Paved shoulder	−2	−2	−2	−3	−3	−3	−4	−5	−6	−6	−6	−6	−6


ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2016 | Rev 3

SINGLE LANE RAMP GRADING FOR ASPHALT PAVEMENT WITH GRANULAR BASE, ASPHALT SHOULDER, AND CURB WITH GUTTER

OPSD 214.030



TANGENT SECTION



SUPERELEVATED SECTION

TABLE
FOR SUPERELEVATED SECTION

	CROSS FALL %												
Paved driving lane	+6	+5	+4	+3	+2	+1	0	−1	−2	−3	−4	−5	−6
Paved shoulder	−2	−2	−2	−3	−3	−3	−4	−5	−6	−6	−6	−6	−6

LEGEND:

S – rate of superelevation in %

NOTES:

1 Fill and cut slopes shall be 3H:1V or flatter when specified.


2 Where steel beam guide rail is specified, the minimum rounding shall be 1.0m, with 0.5m specified from edge of shoulder to rounding breakpoint.

A All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2016 | Rev 2

TWO LANE RAMP GRADING FOR ASPHALT PAVEMENT WITH GRANULAR BASE AND ASPHALT SHOULDER

OPSD 215.010



FILL



CUT


NOTES:


1 Fill and cut slopes shall be 3H:1V or flatter when specified.

2 Where steel beam guide rail is specified, width of berm shall be 1.0m, with the face of guide rail installed 100mm beyond the gutter line.

A All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	2
TWO LANE RAMP GRADING FOR ASPHALT PAVEMENT WITH GRANULAR BASE, ASPHALT SHOULDER, AND CURB WITH GUTTER FOR TANGENT SECTION			
	OPSD 215.020		





LEGEND:

S – rate of superelevation in %

NOTES:

1 Fill and cut slopes shall be 3H:1V or flatter when specified.

2 Where steel beam guide rail is specified, the minimum rounding shall be 1.0m, with 0.5m specified from edge of paved shoulder to rounding breakpoint.

3 Where steel beam guide rail is specified, width of berm shall be 1.0m.

A All dimensions are in metres unless otherwise shown.

TABLE
FOR SUPERELEVATED SECTION

	CROSS FALL %												
Paved driving lane	+6	+5	+4	+3	+2	+1	0	−1	−2	−3	−4	−5	−6
Paved shoulder	−2	−2	−2	−3	−3	−3	−4	−5	−6	−6	−6	−6	−6


ONTARIO PROVINCIAL STANDARD DRAWING

TWO LANE RAMP GRADING FOR ASPHALT PAVEMENT WITH GRANULAR BASE, ASPHALT SHOULDER, AND CURB WITH GUTTER FOR SUPERELEVATED SECTION


Nov 2016 | Rev 3

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 215.030



CUT AND FILL SECTION WITH BARRIER CURB




CUT AND FILL SECTION WITH MOUNTABLE CURB

NOTES:


1 Where steel beam guide rail is indicated, the minimum rounding shall be 1.0m, with 0.5m required from edge of sidewalk to rounding breakpoint.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	2
BOULEVARD TREATMENTS URBAN SECTION			
	OPSD 216.010		



HOT MIX PAVEMENT



CONCRETE PAVEMENT




COMPOSITE PAVEMENT

NOTES:


A Drainage system connection at every catch basin.

B Tie bars at all longitudinal joints.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	2
HOT MIX, CONCRETE, AND COMPOSITE PAVEMENT ON GRANULAR BASE URBAN SECTION			
	OPSD 216.020		




LONGITUDINAL SUBDRAIN CONNECTION TO CATCH BASIN



UNWRAPPED TRENCH



WRAPPED TRENCH



LATERAL SUBDRAIN OUTLET PIPE CONNECTION TO CATCH BASIN

NOTES:

1 Core hole diameter to allow outlet pipe into structure.

2 Install outlet pipe flush with inside face of catch basin.

3 Annular space around pipe shall be filled with non–shrink grout.

A Use compatible manufactured fittings for all connectors, couplings, and caps.

B Trench dimensions shown to accommodate 100 or 150mm diameter subdrain pipe.

C Longitudinal subdrain pipe shall be installed parallel to the grade of the gutter.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


SUBDRAIN PIPE CONNECTION AND OUTLET

URBAN SECTION


Nov 2017 | Rev 3

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S


OPSD 216.021



PLAN



SECTION A–A




SECTION B–B

NOTE:


1 Slope shall be 2H:1V or flatter.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2011	Rev	2
ACCESS TO HYDRANT ACROSS DITCH			
	OPSD 217.050		




DITCH BEYOND AREAS 1 AND 2




DITCH BOTTOM WITHIN AREA 1



DITCH BOTTOM WITHIN AREA 2





SECTION A–A

NSD ALTERNATIVE USING CULVERT
NOTE 1

NOTES:

1 When pipe cover is less than Dia/3, NSD Alternative Using Culvert shall not be used.

A All dimensions are in millimetres unless otherwise shown.

LEGEND:


— · — · — – Boundary of theoretical area

NSD – Normal setting depth


D – The difference in elevation between the ditch bottom and the ground line at the pole

b – The horizontal distance between pole and ditch centre line minus 1.5m


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2011	Rev	2
UTILITY POLE SETTING DEPTH AT DITCH LOCATIONS			
	OPSD 217.060		




PERSPECTIVE VIEW



PLAN



ISOMETRIC VIEW



SECTION A–A


NOTES:

1 Straw bales shall be butted tightly against adjoining bales to prevent sediment flow through barrier.


2 Fill and compact gaps with loose straw.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	3
LIGHT–DUTY STRAW BALE BARRIER			
		OPSD 219.100	




PERSPECTIVE VIEW



PLAN



SECTION A–A




JOINT DETAIL


NOTE:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	3
LIGHT–DUTY SILT FENCE BARRIER			
	OPSD 219.110		




PERSPECTIVE VIEW



PLAN



FIBRE ROLL PLAN VIEW



SECTION A–A


NOTES:

1 Remove all surface obstructions greater than 50mm from ground surface.


2 Ends of rolls shall be butted tightly together.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	1
LIGHT–DUTY FIBRE ROLL BARRIER			
	OPSD 219.120		




PERSPECTIVE VIEW



PLAN



SECTION A–A




JOINT DETAIL


NOTE:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	3
HEAVY–DUTY SILT FENCE BARRIER			
		OPSD 219.130	




PERSPECTIVE VIEW



PLAN



SECTION A-A




JOINT DETAIL


NOTE:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	1
HEAVY-DUTY WIRE-BACKED SILT FENCE BARRIER			
	OPSD 219.131		



PERSPECTIVE VIEW



PLAN




SECTION A–A


NOTE:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	2
SANDBAG BARRIER			
	OPSD 219.150		



PERSPECTIVE VIEW



FIBRE ROLL SLOPE



SECTION A–A


NOTES:

A This OPSD shall be read in conjunction with OPSD 219.120.

B All dimensions are in millimetres unless otherwise shown.


C Remove all surface obstructions greater than 50mm from ground surface.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev 1
FIBRE ROLL GRADE BREAKS		OPSD 219.160




PLAN

FLAT BOTTOM DITCH




Bottom of end bales of downstream row shall be higher than the low point of flow check. Downstream bale position outlined. Typ

SECTION A–A




PLAN

V–DITCH



SECTION B–B




SECTION C–C


NOTES:

1 Number of bales varies and shall suit ditch.
2 Straw bales shall be butted tightly against adjoining bales and shaped to conform to the sides of the ditch to prevent water flow through barrier.
A Fill and compact gaps with loose straw.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	3
STRAW BALE FLOW CHECK DAM			
	OPSD 219.180		




PLAN
FLAT BOTTOM DITCH



SECTION A–A



PLAN
V–DITCH




SECTION B–B

NOTES:


A Refer to OPSD 219.120 Section A–A installation detail.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev 1
FIBRE ROLL FLOW CHECK DAMS		
		OPSD 219.191




PLAN



SECTION A–A
FLAT BOTTOM DITCH



SECTION A–A
V–DITCH



SECTION B–B


NOTES:

1 Sufficient sandbags shall be placed to prevent end scouring.


2 For sandbag dimensions see OPSD 219.150.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	3
SANDBAG FLOW CHECK DAM			
	OPSD 219.200		



PLAN
SPILLWAY




SECTION A–A




SECTION B–B

NOTE:
A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	3
TEMPORARY ROCK FLOW CHECK DAM V–DITCH			
			OPSD 219.210



PLAN
SPILLWAY




SECTION A–A




SECTION B–B

NOTE:
A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	3
TEMPORARY ROCK FLOW CHECK DAM FLAT BOTTOM DITCH			
	OPSD 219.211		



PLAN



SECTION B–B



SECTION A–A


NOTES:

A Ditch cross–section upstream or downstream of sediment trap may be flat bottom or V–shaped. Flat bottom shown.


B This OPSD shall be read in conjuction with OPSD 219.210 or 219.211.

C All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	2
SEDIMENT TRAP IN DITCH			
	OPSD 219.220		



PERSPECTIVE VIEW




SECTION A–A


NOTES:

1 Scour protection according to OPSD 810.010.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	4
TEMPORARY SLOPE DRAIN FOR SEDIMENT TRAP			
	OPSD 219.230		



PLAN



SECTION A–A


NOTES:

1 Scour protection according to OPSD 810.010.

A This OPSD shall be read in conjunction with OPSD 219.230.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	2
TEMPORARY BERM BARRIER FOR SLOPE DRAIN			
	OPSD 219.231		




PLAN

DEWATERING TRAP WITH SILT FENCE




PLAN

DEWATERING TRAP WITH STRAW BALES



SECTION A–A




SECTION B–B

STRAW BALE BARRIER SHOWN


NOTE:

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	2
SEDIMENT TRAP FOR DEWATERING			
	OPSD 219.240		



PLAN




SECTION A–A

NOTES:

1 Additional ballast may be required depending on local conditions.

A All dimensions are in millimeters unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	3
# TURBIDITY CURTAIN			
	OPSD 219.260		




OBLIQUE VIEW

NOTES:

1 Additional ballast may be required depending on local conditions.


A All dimensions are in millimeters.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	3
TURBIDITY CURTAIN SEAM DETAIL			
	OPSD 219.261		




SECTION A–A


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	1
BARRIER FOR TREE PROTECTION			
	OPSD 220.010		



PLAN



SECTION A–A



SECTION B–B

NOTE:

A Schematic only.

B Implement erosion protection when required.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2021 | Rev 1


TEMPORARY FLOW PASSAGE SYSTEM

CULVERT IN WATERCOURSE

OPSD 221.010



PLAN



SECTION A–A

NOTE:
A Schematic only.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2021 | Rev 1

TEMPORARY FLOW PASSAGE SYSTEM

PUMPING AND PIPING

OPSD 221.020



1) WATER CONVEYANCE DEVICE INSTALLED

2) PLUGS REMOVED AND FLOW CONTROL DEVICE OPENED

3) WORK AREA ISOLATED

4) ORIGINAL CHANNEL RESTORED

PLAN VIEWS

NOTES:

A Representative stages only.

B Schematic only.

C Temporary channel lining as specified


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2021 | Rev 1


TEMPORARY FLOW PASSAGE SYSTEM

TEMPORARY CHANNEL OR CULVERT OUTSIDE WATERCOURSE


OPSD 221.030



PLAN



SECTION A–A



SECTION B–B

NOTE:

A Approaches to the temporary crossing shall be clearly marked

B Schematic only.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2021 | Rev 1


TEMPORARY WATERBODY CROSSING

FILL AND CULVERT

OPSD 221.040




PLAN
LOW WATER LEVEL




SECTION

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2022	Rev	2
ROOTWAD STRUCTURES			
			OPSD 222.010




PLAN
NORMAL WATER LEVEL




SECTION

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	1
LARGE WOODY DEBRIS			
	OPSD 222.020		



SECTION




SCHEMATIC OF COVER STONE AND SPACER STONE SUPPORTS


NOTES:

A Sound rock shall be placed so that there is solid contact and no movement.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	2
STONE LUNKERS			
	OPSD 222.030		



SECTION




SCHEMATIC OF WOOD LUNKERS


NOTES:

A All lumber sizes are nominal.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev 1
WOOD LUNKERS		
	OPSD 222.040	



PLAN



SECTION A–A




SECTION B–B


NOTES:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	0
RIFFLES ON STREAMBEDS			
	OPSD 222.050		




PLAN
WATERCOURSE REACH POOL



SECTION
WATERCOURSE REACH POOL



PLAN
CULVERT OUTLET POOL




LONGITUDINAL VIEW
FOR CULVERT OUTLET POOL


NOTES:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	1
POOLS IN STREAMBEDS			
	OPSD 222.060		




PLAN
LOW PROFILE OBSTRUCTION



SECTION A–A



SECTION
LOW PROFILE OBSTRUCTION




SECTION
HIGH PROFILE OBSTRUCTION


NOTES:

A A low flow channel shall extend the length of the rocky ramp and have a slope of ≤4%.
B The channel side slopes on the rocky ramp shall be ≤3%.
C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	0
ROCKY RAMPS ON STREAMBEDS			
	OPSD 222.070		




SECTION
LOW FLOW CHANNEL INSIDE OF CULVERT




SECTION
LOW FLOW CHANNEL

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	0
LOW FLOW CHANNEL			
	OPSD 222.080		



PLAN




SECTIONAL A–A


NOTES:

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	0
BAFFLES IN A CULVERT			
	OPSD 222.090		



VEGETATION BLOCK DETAIL




CROSS SECTIONAL VIEW

NOTES:


A Plant location may differ depending on geographic region and specific hydrologic characteristic.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	0
LOCAL VEGETATION BLOCKS			
	OPSD 222.100		



CROSS SECTIONAL VIEW




LONGITUDINAL VIEW


NOTES:

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	0
LIVE FASCINES			
	OPSD 222.110		



PLAN




SECTION A–A


NOTES:

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	0
LIVE STAKES			
	OPSD 222.120		



PLAN




SECTION A–A


NOTES:

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	0
BRUSH MATTRESS			
	OPSD 222.130		



PLAN VIEW A–A




CROSS SECTIONAL VIEW


NOTES:

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	0
BRUSH LAYERS			
	OPSD 222.140		



PLAN



SECTION A–A

GRADE TABLE	
Downgrade %	L m
3	4
4	8
5	12
6	16
7	20
8	24
9	28
Max 10	32

LEGEND:

L – Length of vertical curve
R – Side road radius
W – Pavement width

NOTES:

1 When curb and gutter is specified, W shall be 8.5m minimum. Taper to existing pavement width at 1:25 along each pavement edge.

2 Side road radii and pavement and shoulder widths shall be as specified.

3 Culvert type, dimensions, and location shall be as specified.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

SIDE ROAD INTERSECTION


FILL

Nov 2018 | Rev 3

OPSD 300.010



PLAN



SECTION A–A

GRADE TABLE	
Upgrade %	L m
1	6
2	10
3	14
4	18
5	22
6	26
7	30
8	34
9	38
Max 10	42

LEGEND:

L – Length of vertical curve
R – Side road radius
W – Pavement width

NOTES:

1 When curb and gutter is specified, W shall be 8.5m minimum. Taper to existing pavement width at 1:25 along each pavement edge.

2 Side road radii and pavement and shoulder widths shall be as specified.

3 Culvert type, dimensions, and location shall be as specified.

A This OPSD shall be read in conjunction with OPSD 200.010 and 201.010.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

SIDE ROAD INTERSECTION


CUT

Nov 2018 | Rev 3


OPSD 300.020



PLAN



SECTION B–B



SECTION A–A

NOTES:


1 Radius shall be 8.0m when entrance is used for farm equipment.

2 Maximum gradient: 6% for residential entrances and 10% for farm and field entrances.

3 Slope shall be 3H:1V or flatter when specified.

A All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2010	Rev	2
RURAL ENTRANCES TO ROADS ON FILL			
	OPSD 301.010		



NOTES:


1 Radius shall be 8.0m when entrance is used for farm equipment.

2 Maximum gradient: 6% for residential entrances and 10% for farm and field entrances.


3 Slope shall be 3H:1V or flatter when specified.

A All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2010	Rev	2
RURAL ENTRANCES TO ROADS IN EARTH CUT			
	OPSD 301.020		



PLAN



SECTION A–A



SECTION B–B
Note 3

NOTES:

1 Radius shall be 8.0m when entrance is used for farm equipment.

2 Maximum gradient: 6% for residential entrances, and 10% for farm and field entrances.

3 For rock grading details see OPSD 201.010.


A All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

RURAL ENTRANCE ROCK CUT


Nov 2010 | Rev 2

OPSD 301.030



MEDIAN WIDTH 15 TO < 20m

TABLE 1	
Median Width	a
15.0	20.68
16.0	21.02
18.0	21.54




MEDIAN WIDTH ≥ 20m

NOTES:

1 Slope shall be 10H:1V without a culvert.
2 Slope shall be 6H:1V with a culvert.

A No signs, guide rails, etc., are to be placed within the turning arc.

B All dimensions are in metres unless otherwise shown.



SECTION A–A

ONTARIO PROVINCIAL STANDARD DRAWING


MEDIAN CROSSOVERS

FOR SERVICE AND EMERGENCY VEHICLES


Nov 2015 | Rev 2

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL ·


OPSD 302.010



PLAN A, AUXILIARY LANE OR TAPER – GRAVEL SHOULDER




PAVED SHOULDER RADIUS WITH GRAVEL SHOULDER ON HIGHWAY




PAVED SHOULDER RADIUS WITH PARTIALLY PAVED SHOULDER ON HIGHWAY

PLAN B, PAVED SHOULDER OR PARTIALLY PAVED SHOULDER



SECTION A–A




PLAN C, CURB AND GUTTER

NOTES:


1 Highway shoulder width tapers to sideroad shoulder width over length of radius.
2 For gravel sideroad, distance shall be 15.0m.
3 Recovery taper is required when traffic lanes include auxiliary lane or taper.
4 Sideroad radii as specified.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
# SHOULDER TREATMENT SIDEROAD INTERSECTIONS			
			OPSD 304.010




TYPICAL SECTION




DUMMY JOINT (OPTIONAL)



CONTRACTION JOINT (Note 4)



EXPANSION JOINT



JOINT LAYOUT

NOTES:

1 Sidewalk thickness at residential driveways and adjacent to curb shall be 150mm. At commercial and industrial driveways, the thickness shall be 200mm.


2 Sidewalk width shall be wider when specified.

3 This OPSD shall be read in conjunction with OPSD 310.030, 310.031, 310.033, and 310.039.


4 Contraction Joint may be tooled or sawcut.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	3
CONCRETE SIDEWALK			
		OPSD 310.010	




TYPICAL SECTION




DUMMY JOINT



CONTRACTION JOINT



EXPANSION JOINT



JOINT LAYOUT

NOTES:


1 At commercial and industrial driveways, the thickness shall be 200mm.

2 Sidewalk width shall be wider when specified.


3 This OPSD shall be read in conjunction with OPSD 310.030, 310.031, 310.033, and 310.039.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	3
CONCRETE SIDEWALK ADJACENT TO CURB WITH GUTTER			OPSD 310.020



DOUBLE RAMP WITHOUT BOULEVARD




DOUBLE RAMP WITH BOULEVARD




The plates shall extend the entire width of the sidewalk ramp at a minimum length of 610mm, in accordance with OPSD 310.039

RAMP PLAN



RAMP ELEVATION



RAMP SECTION

NOTES:


1 Slope of ramp shall not exceed 8%.
2 Cross slope of ramp shall not exceed 2% in either direction.
3 Cross slope of flared side of ramp shall not exceed 8%.
4 Dropped curb at ramp shall be modified to eliminate 30 mm step at gutter.
5 Accessible pedestrian signal to have tactile arrow that aligns with direction of crosswalk.
6 Minimum thickness of ramp is 200mm. Minimum thickness of sidewalk and flared sides adjacent to ramp is 150mm.

A Where only one crosswalk is present at an intersection, only one curb ramp is required.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	1

CONCRETE SIDEWALK RAMPS AT SIGNALIZED INTERSECTIONS


OPSD 310.030




DOUBLE RAMP WITHOUT BOULEVARD




DOUBLE RAMP WITH BOULEVARD



RAMP PLAN



RAMP ELEVATION




RAMP SECTION

NOTES:


1 Slope of ramp shall not exceed 8%.
2 Cross slope of ramp shall not exceed 2% in either direction.
3 Cross slope of flared side of ramp shall not exceed 8%.
4 Dropped curb at ramp shall be modified to eliminate 30 mm step at gutter line.
5 Accessible pedestrian signal to have tactile arrow that aligns with direction of crosswalk.
6 Minimum thickness of ramp is 200mm. Minimum thickness of sidewalk and flared sides adjacent to ramp is 150mm.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	0
# CONCRETE SIDEWALK RAMPS AT SIGNALIZED INTERSECTIONS WITH INTERSECTING CROSSWALKS			
	OPSD 310.031		




DOUBLE RAMP WITHOUT BOULEVARD




RAMPS WITH BOULEVARD



RAMP PLAN



RAMP ELEVATION




RAMP SECTION


NOTES:

1 Slope of ramp shall not exceed 8%.
2 Cross slope of ramp shall not exceed 2% in either direction.
3 Cross slope of flared side of ramp shall not exceed 8%.
4 Dropped curb at ramp shall be modified to eliminate 30 mm step at gutter line.
5 Minimum thickness of ramp is 200mm. Minimum thickness of sidewalk and flared sides adjacent to ramp is 150mm.
A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	1
# CONCRETE SIDEWALK RAMPS AT UNSIGNALIZED INTERSECTIONS			
	OPSD 310.033		




PLAN



ELEVATION



DETAIL A
TRUNCATED DOMES PLAN




SECTION A–A


NOTES:

1 Vents shall be as specified by the manufacturer.
2 Length of plate may be increased to suit the curb depression width.
3 Material of plate shall be as specified in Contract Documents.
A Adjacent cast iron plates shall be permanently connected using a locking mechanism and any hardware shall be hot dipped galvanized.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	1
CONCRETE SIDEWALK RAMPS TACTILE WALKING SURFACE INDICATORS COMPONENT			
	OPSD 310.039		



CATCH BASIN



UTILITY APPURTENANCE



UTILITY POLE

NOTES:

1 Expansion joint through sidewalk is required when curb and gutter is poured integral with sidewalk.

2 Adjust joints to coincide with centre of utility, with minimum slab length of 1m.


3 Expansion joint material shall be placed around Utility appurtenance flush with concrete surface.

4 For concrete alternative use expansion joint material around boxout.


A For expansion joint detail, see OPSD 310.010.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	3
# UTILITY ISOLATION IN CONCRETE SIDEWALKS			
	OPSD 310.040		




FULLY DEPRESSED




PARTIALLY DEPRESSED


PLAN




SIDEWALK WITHOUT BOULEVARD
SECTION A–A



SIDEWALK WITH BOULEVARD
SECTION C–C



SECTION B–B



SECTION D–D

NOTES:

1 At commercial and industrial driveways, the thickness shall be 200mm.

A For contraction joint detail, see OPSD 310.010.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


CONCRETE SIDEWALK DRIVEWAY ENTRANCE DETAILS

Nov 2019 | Rev | 3

OPSD 310.050



PLAN



COMPOSITE PAVEMENT
SECTION A–A

FLEXIBLE PAVEMENT
SECTION B–B


NOTES:

1 For expansion joint detail, see OPSD 552.020.


2 Dowel bar with cap shall be installed at 300mm centres.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	2
JOINT DETAIL FOR CONCRETE PEDESTRIAN CROSSWALK AT SIGNALIZED AND ALL–WAY STOP CONTROLLED INTERSECTIONS			
	OPSD 310.060		




DRIVEWAY DIMENSIONS						
LAND USE	WIDTH m				RADIUS m	
	One–Way		Two–Way			
	min	max	min	max	min	max
Light Industrial, Commercial, and Apartment	4.5	7.5	7.2	12.0	4.5	12.0
Heavy Industrial	5.0	9.0	9.0	15.0	9.0	15.0



DETAIL A




PLAN




NOTES:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
URBAN INDUSTRIAL, COMMERCIAL, AND APARTMENT ENTRANCES			
			OPSD 350.010



PLAN



ISOMETRIC VIEW



SECTION A–A

DRIVEWAY DIMENSIONS				
LAND USE	WIDTH m			
	Single		Double	
	min	max	min	max
Residential	3.0	4.3	6.0	7.3

NOTES:

1 Maximum upgrade shall be 10%.


2 Maximum downgrade shall be 8%.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2

URBAN RESIDENTIAL ENTRANCE


OPSD 351.010




SQUARE FRAME PLAN
SQUARE CORNER



SQUARE FRAME PLAN
MID–SECTION



SQUARE FRAME PLAN
ROUND CORNER



SECTION A–A

NOTES:

1 For OPSD 402.030, the hoisting hook rib thickness shall be 29mm.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


HOISTING HOOK RIB FOR CAST IRON FRAMES FOR CATCH BASINS, MAINTENANCE HOLES, AND VALVE CHAMBERS

Nov 2018 | Rev 2


OPSD 400.001



FRAME PLAN




SECTION A–A




GRATE PLAN


SECTION C–C




SECTION B–B



SECTION D–D



SECTION E–E




SLOT DETAIL

NOTES:


A This OPSD shall be read in conjunction with OPSD 610.010 and 610.020.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
CAST IRON, SQUARE FRAME WITH SQUARE FLAT GRATE FOR CATCH BASINS, HERRING BONE OPENINGS			
	OPSD 400.020		




FRAME PLAN



SECTION B–B



SECTION A–A




SLOT DETAIL

NOTES:


A This OPSD shall be read in conjunction with OPSD 400.090.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	1
CAST IRON, SQUARE FRAME FOR CURB INLET OVERFLOW			
	OPSD 400.021		



FRAME PLAN




SECTION A–A




GRATE PLAN


SECTION C–C




SECTION B–B



SECTION D–D



SECTION E–E




SLOT DETAIL

NOTE:


A This OPSD shall be read in conjunction with OPSD 610.010.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
CAST IRON, SQUARE FRAME WITH SQUARE V GRATE FOR CATCH BASINS, HERRING BONE OPENINGS			
			OPSD 400.030




A FRAME PLAN




SECTION A–A



INSTALLATION



SECTION B–B



SECTION C–C

NOTE:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

CAST IRON, ONE–PIECE FRAME AND FLAT SQUARE GRATE FOR TEMPORARY INSTALLATION, HERRING BONE OPENINGS


Nov 2018 | Rev 3

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL


OPSD 400.040




FRAME PLAN




SECTION A–A




GRATE PLAN




SECTION C–C




SECTION B–B



SECTION D–D



SECTION E–E




SLOT DETAIL

NOTES:


A This OPSD shall be read in conjunction with OPSD 610.010 and 610.020.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
CAST IRON, SQUARE FRAME WITH SQUARE OVERFLOW TYPE DISHED GRATE FOR CATCH BASINS, HERRING BONE OPENINGS			
	OPSD 400.010		




PLAN




SECTION B–B




BOTTOM VIEW



SECTION A–A



SECTION C–C



FISH DETAIL

NOTE:

A This OPSD shall be read in conjunction with OPSD 400.020.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


CAST IRON, SQUARE FRAME FISH TYPE COVER

Nov 2019 | Rev 0


OPSD 400.050




FRAME PLAN




GRATE PLAN




SECTION A–A



SECTION C–C



SECTION B–B




SECTION D–D


NOTES:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	6
CAST IRON, RAISED SQUARE FRAME WITH CIRCULAR FLAT GRATE FOR CATCH BASINS, HERRING BONE OPENINGS			OPSD 400.070




FRAME PLAN



SECTION A–A



SECTION B–B




SLOT DETAIL

NOTES:


A For grate see OPSD 400.020 or 400.100.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	4
CAST IRON, SIDE INLET FOR CATCH BASINS			
	OPSD 400.080		



PLAN




SECTION A–A




PLAN

SECTION C–C

COVER




PLAN




SECTION D–D

SQUARE COVER




SECTION B–B




CURB ELEVATION

FRAME



BOTTOM VIEW



SECTION E–E

ROUND COVER

NOTE:

A Installation shall be according to OPSD 610.030.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

CAST IRON, CURB INLET FRAME WITH TWO–PIECE RAISED COVER FOR CATCH BASINS OUT OF ROADWAY


Nov 2018 | Rev | 3

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL


OPSD 400.081




PLAN



CURB ELEVATION



SECTION A–A




SECTION B–B


NOTES:

A Installation shall be according to OPSD 610.030.
B For cover types, see OPSD 401.010 or 401.080.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	4
CAST IRON, RAISED CURB INLET FRAME WITH COVER FOR CATCH BASINS OUT OF ROADWAY			
	OPSD 400.082		




PLAN



CURB ELEVATION



SECTION A–A




SECTION B–B


NOTES:

A Installation shall be according to OPSD 610.030.
B For cover types, see OPSD 401.010 or 401.080.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	5
CAST IRON, RAISED CURB INLET FRAME WITH COVER FOR CATCH BASINS OUT OF ROADWAY			
	OPSD 400.082		



TOP VIEW





FRONT VIEW




SECTION C–C

OVERFLOW PLATE





SECTION B–B



SECTION A–A

INSTALLATION DETAIL


NOTES:

1 Temporary brick bulkhead prior to setting final grade of the frame with grate.


A Catch basin shall have 250mm diameter minimum lead.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
CAST IRON CURB INLET OVERFLOW FOR CATCH BASINS			
	OPSD 400.090		




FRAME PLAN




SECTION A–A




GRATE PLAN



SECTION B–B



SECTION C–C




SLOT DETAIL

NOTE:


A This OPSD shall be read in conjunction with OPSD 610.010 and 610.020.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
CAST IRON, SQUARE FRAME WITH SQUARE FLAT GRATE FOR CATCH BASINS, PERFORATED OPENINGS			
	OPSD 400.100		




FRAME PLAN




SECTION A–A




GRATE PLAN



SECTION B–B



SECTION C–C




SLOT DETAIL

NOTES:


A This OPSD shall be read in conjunction with OPSD 610.010 and 610.020.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
CAST IRON, SQUARE FRAME WITH SQUARE OVERFLOW TYPE FLAT GRATE FOR CATCH BASINS, PERFORATED OPENINGS			
	OPSD 400.110		




FRAME PLAN




SECTION A–A




GRATE PLAN




SECTION C–C



SECTION B–B



SECTION D–D




SLOT DETAIL


NOTES:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
CAST IRON, SQUARE FRAME WITH BIRDCAGE GRATE FOR CATCH BASINS			
			OPSD 400.120




FRAME PLAN




TYPE A
CLOSED COVER




TYPE B
OPEN COVER



SECTION A–A



SECTION C–C




SECTION D–D

NOTES:

A Covers shall be Type A or Type B, as specified.

B All dimensions are in millimetres unless otherwise shown.



SECTION B–B


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2018 | Rev 4


CAST IRON, SQUARE FRAME WITH CIRCULAR CLOSED OR OPEN COVER FOR MAINTENANCE HOLES

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 401.010




FRAME PLAN
NOTE 1




COVER PLAN



SECTION B–B



SECTION A–A




COVER BOTTOM VIEW

NOTE:


1 As an option, frame may be completely round.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	4
CAST IRON, CIRCULAR FRAME WITH CIRCULAR 745mm COVER FOR MAINTENANCE HOLES			
	OPSD 401.020		




FRAME PLAN




COVER PLAN



SECTION A–A




SECTION C–C




HOLE DETAIL

BAR HANDLE DETAIL



SECTION B–B




SECTION D–D


NOTE:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	4
CAST IRON, SQUARE FRAME WITH CIRCULAR WATERTIGHT COVER FOR MAINTENANCE HOLES			
	OPSD 401.030		




FRAME PLAN




SECTION A–A




SECTION B–B




TYPE A
CLOSED COVER



TYPE B
OPEN COVER



SECTION C–C




SECTION D–D

NOTES:


A Covers shall be Type A or Type B, as specified.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	5
CAST IRON, RAISED SQUARE FRAME WITH CIRCULAR CLOSED OR OPEN COVER FOR MAINTENANCE HOLES			
	OPSD 401.040		




FRAME PLAN




COVER PLAN




SECTION C–C




SECTION A–A




HOLE DETAIL




BAR HANDLE DETAIL



SECTION B–B
SHOWN WITH COVER IN PLACE



SECTION D–D




BOTTOM VIEW


NOTES:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	5
CAST IRON, RAISED SQUARE FRAME WITH CIRCULAR WATERTIGHT COVER FOR MAINTENANCE HOLES	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 401.050		




COVER




SECTION A–A
FRAME WITH COVER SHOWN






DETAIL A




LOCKED POSITION




OPEN POSITION


DETAIL B



ISOMETRIC VIEW



PLAN



ELEVATION


LOCKING LUG

NOTES:


A Locking bolt shall be securely tightened.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	4
CAST IRON **CIRCULAR LOCKING COVER** FOR MAINTENANCE HOLES			
			OPSD 401.060




PLAN




SECTION A–A



BOTTOM VIEW



SECTION B–B



FISH DETAIL

NOTE:
A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2019 | Rev 1


CAST IRON, CURB INLET
FISH TYPE COVER FOR CATCH BASINS
OUT OF ROADWAY

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPS


OPSD 401.080




FRAME PLAN




PLAN



PLUG DETAIL




SECTION A–A



SECTION C–C

NOTES:

A All dimensions are in millimetres unless otherwise shown.



SECTION B–B


ONTARIO PROVINCIAL STANDARD DRAWING

CAST IRON, SQUARE FRAME WITH CIRCULAR COVER AND PLUG FOR VALVE CHAMBERS


Nov 2019 | Rev 4

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · SO


OPSD 402.010




FRAME PLAN




PLAN



PLUG DETAIL




SECTION A–A



SECTION C–C

NOTES:

A All dimensions are in millimetres unless otherwise shown.



SECTION B–B


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2019 | Rev 4


CAST IRON, SQUARE FRAME WITH VENTED CIRCULAR COVER AND PLUG FOR VALVE CHAMBERS

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS


OPSD 402.011




FRAME PLAN




PLAN




PLUG DETAIL



SECTION A–A



SECTION C–C




SECTION B–B


NOTES:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	5
CAST IRON, RAISED SQUARE FRAME WITH CIRCULAR COVER AND PLUG FOR VALVE CHAMBERS			
	OPSD 402.020		




FRAME PLAN




PLAN




PLUG DETAIL



SECTION A–A



SECTION C–C



SECTION B–B

NOTES:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2019 | Rev 4


CAST IRON, RAISED SQUARE FRAME WITH VENTED CIRCULAR COVER AND PLUG FOR VALVE CHAMBERS

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS


OPSD 402.021




FRAME PLAN




SECTION A–A




LARGE COVER PLAN




SECTION D–D




SECTION B–B




SECTION E–E



SECTION F–F



CIRCULAR COVER SECTION G–G



SECTION C–C

NOTE:
A All bolts to be 304 stainless steel.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2019 | Rev 5

CAST IRON, RECTANGULAR FRAME WITH TWO PIECE COVER FOR METER AND VALVE CHAMBERS

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPS

OPSD 402.030




Grating Type	Grating Size	
	Length L	Width W
A	762	768
B	1338	768
C	1465	768

A PLAN OF GRATE


SECTION A–A




SECTION B–B




FASTENER DETAIL




AUXILIARY VIEW



SECTION C–C



FASTENER EMBEDMENT DETAIL



OFFSET WASHER DETAIL

NOTES:

1 Equivalent (13x100mm Galvanized J–Bolt) cast–in–place anchor may be used.


A Fastener shall be inserted to maintain minimum concrete cover requirements.

B All steel components and rivets shall be galvanized.


C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	3
GALVANIZED STEEL HONEYCOMB GRATING FOR DITCH INLETS			
	OPSD 403.010		


Slope of Grating	Dimension *a*
2H:1V	343
3H:1V	243
4H:1V	186




GRATE ISOMETRIC VIEW




OFFSET WASHER DETAIL



PLAN OF GRATE



FASTENER DETAIL



SECTION A–A

NOTES:

1 Equivalent (13x100mm Galvanized J–Bolt) cast–in–place anchor may be used.

A Grate dimensions shall be according to OPSD 705.030.

B Bearing bars shall be welding quality steel having the minimum tensile strength of SAE 1015.

C When specified, all surfaces shall be painted in the shop with one coat of asphalt or tar base black paint having a minimum softening point of 71 C.
All joints and crevices shall be thoroughly coated.

D Bearing bars shall be welded to angle bar along both legs with a 5mm fillet weld.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

RAISED BAR GRATE FOR DITCH INLET 600 x 600mm


Nov 2017 | Rev 1

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S


OPSD 403.011




SAFETY PLATFORM IN CHIMNEY



SECTION A–A



CORNER LADDER DETAIL



LADDER DETAIL

NOTES:

A Safety platform required if combined height of chamber and chimney is 5.0m or greater.

B All aluminum shall be 6061–T6.

C All aluminum surfaces in contact with concrete shall receive two coats of bituminous paint.

D Welding shall be according to CSA W47.2 and CSA W59.2.

E Grind rough edges smooth. Welded surfaces shall remain as welded.

F Fabricate safety platform same as OPSD 404.020 for 1500mm diameter maintenance hole and modified as required to fit.

G This OPSD shall be read in conjunction with OPSD 1101.012, 1101.013, 1101.014, 1101.015, 1101.016, 1101.017, 1101.018, and 1101.019.

H All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ALUMINUM SAFETY PLATFORM AND LADDER FOR RECTANGULAR PRECAST CONCRETE VALVE CHAMBERS


Nov 2018 | Rev 2

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 404.010




GRATING OPEN
SECTION A–A




OPEN POSITION
SIDE VIEW




DETAIL A




DETAIL B



DETAIL OF GRATING AND BOLT–ON SUPPORT
PLAN



GRATING RUNG
DETAIL



SECTION B–B

NOTES:

1 All hinge brackets and mounting brackets shall be welded all around to support angle.

A All aluminum in contact with concrete shall be thoroughly coated with asphalt paint.

B Maintenance hole depth between 5.0m and 10.0m, grate shall be placed at midpoint. Maintenance hole depth between 10.0m and 15.0m, grates shall be placed at third–points.

C All fasteners shall be 304 stainless steel.

D All welding shall be according to CSA W47.2 and W59.2.

E All aluminum components shall be 6000 series structural aluminum.

F All dimensions are in millimetres unless otherwise shown.

MH Diameter	No of Grates	*a*	*b*	*c*	*d*	*e*	*f*	*g*
1200	2	900	850	850	225	352	65	10
1500	2	1128	1078	1078	311	419	65	12
1800	3	1344	1293	1293	308	360	65	12
2400	4	1774	1724	1724	401	360	65	12


ONTARIO PROVINCIAL STANDARD DRAWING

ALUMINUM SAFETY PLATFORM FOR CIRCULAR MAINTENANCE HOLES


Nov 2018 | Rev 4

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS


OPSD 404.020




GRATING OPEN
SECTION A–A



OPEN POSITION
SIDE VIEW



DETAIL A DETAIL B



DETAIL OF GRATING AND BOLT–ON SUPPORT
PLAN

GRATING RUNG
DETAIL

SECTION B–B

NOTES:

1 All hinge brackets and mounting brackets shall be welded all around to support angle.

A All aluminum in contact with concrete shall be thoroughly coated with asphalt paint.

B Maintenance hole depth between 5.0m and 10.0m, grate shall be placed at midpoint. Maintenance hole depth between 10.0m and 15.0m, grates shall be placed at third–points.

C All fasteners shall be 304 stainless steel.

D All welding shall be according to CSA W47.2 and W59.2.

E All aluminum components shall be 6000 series structural aluminum.

F All dimensions are in millimetres unless otherwise shown.

INSIDE DIA DROP PIPE	a	b	c	OUTSIDE DIA DROP PIPE, MAX
150	932	1143	59	160
200	866	1254	62	213
250	799	1335	76	267
300	799	1335	25	318


ONTARIO PROVINCIAL STANDARD DRAWING

ALUMINUM SAFETY PLATFORM FOR 1500mm DIAMETER CIRCULAR MAINTENANCE HOLES WITH DROP PIPE


Nov 2018 | Rev 3

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL


OPSD 404.021




GRATING OPEN
SECTION A–A




OPEN POSITION
SIDE VIEW




DETAIL A




DETAIL B



DETAIL OF GRATING AND BOLT–ON SUPPORT
PLAN



GRATING RUNG DETAIL



SECTION B–B

NOTES:

1 All hinge brackets and mounting brackets shall be welded all around to support angle.

A All aluminum in contact with concrete shall be thoroughly coated with asphalt paint.

B Maintenance hole depth between 5.0m and 10.0m, grate shall be placed at midpoint. Maintenance hole depth between 10.0m and 15.0m, grates shall be placed at third–points.

C All fasteners shall be 304 stainless steel.

D All welding shall be according to CSA W47.2 and W59.2.

E All aluminum components shall be 6000 series structural aluminum.

F All dimensions are in millimetres unless otherwise shown.

INSIDE DIA DROP PIPE	a	b	c	OUTSIDE DIA DROP PIPE, MAX
150	1218	1316	79	160
200	1218	1316	29	213
250	1150	1433	47	267
300	1082	1524	65	318
375	1014	1610	58	389


ONTARIO PROVINCIAL STANDARD DRAWING

ALUMINUM SAFETY PLATFORM FOR 1800mm DIAMETER CIRCULAR MAINTENANCE HOLES WITH DROP PIPE


Nov 2018 | Rev 3

ONTARIO STANDARDS • MUNICIPAL–PROVINCIAL •


OPSD 404.022




PLAN




PLAN




PLAN




SIDE VIEW




SIDE VIEW




FRONT VIEW




SECTION C–C




AUXILIARY
VIEW



EXTRUDED
CIRCULAR SECTION A–A



SECTION B–B



AUXILIARY
VIEW

CIRCULAR ALUMINUM

CIRCULAR ALUMINUM WITH POLYETHYLENE ENCASEMENT

RECTANGULAR STAINLESS STEEL

NOTE:

1 The company undertaking welded fabrication shall be certified according to CSA W47.1. All welding shall be according to CSA W59.

A All aluminum components shall be 6000 series structural aluminum.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2018 | Rev 4


MAINTENANCE HOLE STEPS

HOLLOW


OPSD 405.010




PLAN




SECTION A–A




PLAN




SECTION B–B



AUXILIARY VIEW




AUXILIARY VIEW




SECTION C–C

TYPE A **TYPE B**


RECTANGULAR ALUMINUM




PLAN




SECTION D–D




FORMED ANCHOR LOCK DETAIL




PLAN




SIDE VIEW



AUXILIARY VIEW



AUXILIARY VIEW



SIDE VIEW

TYPE A **TYPE B**

CIRCULAR ALUMINUM


NOTES:

A All aluminum components shall be 6000 series structural aluminum.


B All aluminum in contact with concrete shall be thoroughly coated with asphalt paint.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	4
MAINTENANCE HOLE STEPS SOLID			
	OPSD 405.020		




PLAN




ELEVATION




SIDE VIEW



SECTION A–A



BRACKET DETAIL



SECTION THROUGH SPLICE DETAIL

NOTES:

A All aluminum in contact with concrete shall be thoroughly coated with asphalt paint.

B All bolts, nuts, and washers shall be made of Type 304 stainless steel.

C All welding shall be according to CSA W47.2 and W59.2.

D All brackets, bars, rungs, and stringers shall be fabricated from 6000 series structural aluminum.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2018 | Rev 3


ALUMINUM LADDER

FOR MAINTENANCE HOLES


OPSD 406.010



TYPE A



TYPE B



TYPE C

NOTES:

1 Width of pavement, shoulder, and rounding to match terminated roadway.

A Drainage and grading as specified.

B All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

TURNING BASINS FOR TERMINATED RURAL ROADWAYS


Nov 2018 | Rev 1

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 500.010




TYPE A



TYPE C



TYPE B



TYPE D

NOTES:

1 Width of pavement to match terminated roadway.
2 Type of curb to match terminated roadway.
3 Island curb shall be according to OPSD 600.090.


A Drainage and grading as specified.
B All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


TURNING BASINS FOR TERMINATED URBAN ROADWAYS RESIDENTIAL

Nov 2018 | Rev | 1


OPSD 500.020




TYPE A



TYPE C



TYPE B



TYPE D

NOTES:

1 Width of pavement to match terminated roadway.


2 Type of curb to match terminated roadway.

A Drainage and grading as specified.


B Minimum radius should be increased to accommodate design vehicles.

C All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	1
TURNING BASINS FOR TERMINATED URBAN ROADWAYS INDUSTRIAL AND COMMERCIAL			
	OPSD 500.030		



BETWEEN INTERSECTIONS



CORNER LOCATION



TYPICAL CROSS SECTION


NOTES:

1 Where the use of articulated buses is anticipated, the bus bay dimensions shall be increased to provide a 25.0m loading area and 35.0m tapers.


2 When the bus bay surface is concrete on an asphalt road, it shall be extended by 3.0m.

A All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
BUS BAYS			
	OPSD 501.010		



FLEXIBLE PAVEMENT



CONCRETE PAVEMENT

NOTES:

A Joint spacing in concrete pavement shall be according to OPSD 551.010.

B Joint details in concrete pavement shall be according to OPSD 552.010.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


ACCESS LANES

FOR REAR LOTS


Nov 2018 | Rev 2

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S


OPSD 502.010




PLAN



SECTION B–B



SECTION A–A




DETAIL A

NOTES:


1 Expansion and contraction joint spacing shall coincide with adjacent concrete pavement or where adjacent to asphalt pavement joint spacing shall not exceed 4.0m.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2011	Rev	1
CONCRETE RIPPLE STRIP			
	OPSD 503.010		



PLAN




ASPHALT SURFACE



CONCRETE SURFACE

Note 2



CONCRETE SLAB


Note 3

NOTES:

1 For electrical chamber and duct details refer to electrical drawings.
2 For concrete surfaced island, place contraction joints in median to match curb joints.
3 For concrete slab island, place contraction joints in median to match pavement joints where placed on a concrete base.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	1
RAISED TRAFFIC ISLAND			
	OPSD 504.010		



NOTES:

1 As an alternative, cold mill existing hot mix to provide a butt joint for full binder course thickness.

2 For integral and semi–integral abutments provide for a 25 x 25mm sawn joint filled with hot poured rubberized asphalt joint sealing compound in the hot mix over the end of the approach slab.


A All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


HOT MIX RESURFACING TREATMENT AT STRUCTURE APPROACHES

Nov 2018 | Rev 2


OPSD 506.010



FLUSH FILL OF CRACKS WITHOUT OVERLAY



OVERFILL OF CRACKS WITHOUT OVERLAY




CRACKS WITH ASPHALT OVERLAY

NOTE:


1 Final overfill geometry after cooling of sealant material.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	2
ROUTING AND SEALING CRACKS UP TO 20mm IN WIDTH IN ASPHALT PAVEMENT			
	OPSD 508.010		



HOT POURED RUBBERIZED SEALANT



SILICONE SEALANT
NOTE 4



COMPRESSION SEAL
NOTE 4

NOTES:

1 Shape factor has a width to depth ratio of
  – 1H:1V for hot poured rubberized sealant
  – 2H:1V for silicone sealant.
2 Initial saw cut is only required in fresh concrete.
3 Dimensions of compression seal and reservoir as per manufacturer's requirements.
4 Silicone sealant or compression seals shall be used when specified.

A Reservoir width design to accommodate anticipated slab movement.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

SEALING OR RESEALING OF JOINTS AND CRACKS IN CONCRETE PAVEMENT AND CONCRETE BASE


Nov 2018 | Rev 3

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 508.020



COMPOSITE PAVEMENT



EXPOSED CONCRETE PAVEMENT



HOT MIX ASPHALT PAVEMENT

NOTES:

1 Hot mix asphalt type and thickness as specified. The surface course shall not be less than 40mm.

2 Dowels shall be installed at 300mm intervals along all transverse faces. The dowel bars shall be placed mid–depth of the specified slab thickness and parallel to the longitudinal axis and the horizontal plane of the pavement within the following tolerances:
   a) Vertical Alignment: ± 15mm along the length of the dowel bar.
   b) Horizontal Alignment: ± 15mm along the length of the dowel bar.
   c) Side Shift: The centre of the dowel bar shall lie within ± 40mm from the transverse joint.

   Tie bars shall be installed at 600mm intervals along all longitudinal faces and shall be aligned perpendicular to the longitudinal axis of the pavement. The tie bars shall be installed within a tolerance of ± 15mm from the specified depth.

   Where reinforcement is present, dowel and tie bars may be adjusted 25mm horizontally and raised or lowered 10mm to avoid drilling reinforcement.


   All dowels and tie bars shall be set with epoxy grout.

3 If the total pavement thickness is less than 80mm, step joint is not required.

4 Joint treatment as specified.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev	3
PAVEMENT REINSTATEMENT FOR UTILITY CUTS			
			OPSD 509.010




NOTES:

1 Minimum cover for protection from construction traffic:

Min polystyrene comp. strength	Min depth of cover
275kPa	300mm
400kPa	225mm

2 Taper to top of subgrade for a length of 4.8m.

A All dimensions are in millimetres unless otherwise shown.



LEGEND:


25mm polystyrene thickness


D = Depth to bottom of polystyrene below profile grade

H = Depth of existing granular courses


W = Shoulder width or 1.8m whichever is the lesser

Y = Length of excavation taper = *4H*





ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
EXTRUDED EXPANDED POLYSTYRENE FROST HEAVE TREATMENT 25mm THICKNESS			
	OPSD 514.010		



LONGITUDINAL GRADE RAISE SECTION

LONGITUDINAL CUT SECTION


NOTES:

1 Minimum cover for protection from construction traffic:


Min polystyrene comp. strength	Min depth of cover
275kPa	300mm
400kPa	225mm

2 Taper to top of subgrade for a length of 4.8m.

A All dimensions are in millimetres unless otherwise shown.



POLYSTYRENE PLAN



POLYSTYRENE ELEVATION

LEGEND:


- 25mm polystyrene thickness
- 40mm polystyrene thickness

D = Depth to bottom of polystyrene below profile grade


H = Depth of existing granular courses

W = Shoulder width or 1.8m whichever is the lesser

Y = Length of excavation taper = *4H*



TRANSVERSE GRADE RAISE SECTION



TRANSVERSE CUT SECTION

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2018 | Rev 2

EXTRUDED EXPANDED POLYSTYRENE FROST HEAVE TREATMENT


40mm THICKNESS

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 514.020



RIGHT ANGLE JOINT



SKEWED JOINT



JOINT LAYOUT TRANSITION AT STRUCTURE APPROACH

NOTES:

1 The transverse joint adjacent to the skewed expansion joint shall be placed so the slab length is not shorter than 3.0m nor longer than 5.0m.

2 Expansion joints shall be placed at each end of both structure approach slabs.


A All joints shall be according to OPSD 552.010 or OPSD 552.020.

B Construction joints shall be right angled joints located a minimum of 2.0m from adjacent transverse joints.


C Transverse joints shall be extended to include the full width of the concrete shoulders and curb with gutter.

D All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	2
CONCRETE AND COMPOSITE PAVEMENT JOINT SPACING			
			OPSD 551.010




DIVERGING LANE



DETAIL



CONVERGING LANE



OUTSIDE LANE TAPER

NOTES:

1 Joint F is fixed at the end of the bullnose. Adjust the location of the joint immediately previous to Joint F, based on the side from which paving is approaching, so that the slabs on each side of the last joint are not shorter than 3.0m nor longer than 5.0m. Where the ramp is concrete pavement, Joint H shall be an expansion joint.

2 Joint G location shall be fixed to that of the closest joint to give a taper width of not less than 600mm. The taper from 0 to 600mm wide shall be constructed as an integral part of the first lane to be placed.


3 When paving in the opposite direction, this area shall be the adjustment area.

4 Taper shall be run out in one slab length.

A All joints shall be according to OPSD 552.010 or 552.020.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	2
CONCRETE AND COMPOSITE PAVEMENT JOINT LAYOUT AT CONVERGING OR DIVERGING LANES	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 551.020		



NOTES:

1 Tapers on lane transitions and at curves shall terminate with a minimum 500mm width. The taper from 0 to 500mm shall be constructed as an integral part of the adjacent slab.

2 Joint F is a fixed joint which meets the longitudinal joint from the intersecting road. Joints immediately adjacent to the fixed joint are adjustment joints.

A Expansion joints shall be located immediately beyond the radius of the intersecting roads.

B All joints shall be according to OPSD 552.010 or 552.020.

C All joints shall be adjusted so that the slabs on either side of the joint have a minimum length of 3.0m and maximum length of 5.0m.

D Standard maximum joint spacing is 4.5m.


E Pavement joints shall be sawn through curb and gutter.

F Angles less than 60° between joints shall be avoided.

G All radii shall be as specified in geometric design.

H All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	3
CONCRETE AND COMPOSITE PAVEMENT SKEWED JOINT LAYOUT AT INTERSECTIONS	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 551.030		



NOTES:

1 Tapers on lane transitions and at curves shall terminate with a minimum 500mm width. The taper from 0 to 500mm shall be constructed as an integral part of the adjacent slab.

2 Joint F is a fixed joint which meets the longitudinal joint from the intersecting road. Joints immediately adjacent to the fixed joint are adjustment joints.

A Expansion joints shall be located immediately beyond the radius of the intersecting roads.

B All joints shall be according to OPSD 552.010 or 552.020.

C All joints shall be adjusted so that the slabs on either side of the joint have a minimum length of 3.0m and maximum length of 5.0m.

D Standard maximum joint spacing is 4.5m.


E Pavement joints shall be sawn through curb and gutter.

F Angles less than 60° between joints shall be avoided.


G All radii shall be as specified in geometric design.

H All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	3
CONCRETE AND COMPOSITE PAVEMENT RIGHT ANGLE JOINT LAYOUT AT INTERSECTIONS	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 551.031		



ISOLATION WITHIN A SLAB



ISOLATION ADJACENT TO CURB



TYPICAL ADJUSTMENTS OF JOINTING AT UTILITY ISOLATION
NOTE 2


NOTES:

1 Isolation joint shall consist of 12mm expansion joint filler material placed full depth and flush with concrete surface.

2 When a longitudinal or transverse joint is within 600mm of an isolation joint, adjust the longitudinal or transverse joint accordingly.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	3
CONCRETE AND COMPOSITE PAVEMENT UTILITY ISOLATION			
	OPSD 551.032		




CONTRACTION JOINT
WITHOUT DOWEL BAR

CONTRACTION JOINT

EXPANSION JOINT

CONSTRUCTION JOINT



LONGITUDINAL KEYWAY JOINT
WITHOUT TIE BAR

LONGITUDINAL JOINT
SINGLE LANE PAVING

LONGITUDINAL JOINT
MULTI–LANE PAVING

LONGITUDINAL JOINT
CONCRETE SLAB ADJACENT TO CURB WITH GUTTER

NOTES:

1 Field cut 20mm thick expansion joint filler material, the width of pavement plus shoulder and depth of concrete slab less the depth of reservoir.

2 Use 15x760mm epoxy coated deformed tie bars spaced at 600mm OC at 0.5*T*.


3 Depth of curb and gutter shall be extended to coincide with bottom of concrete slab.

A Paving width shall not exceed 4.5m without a longitudinal joint. Where paving width is greater than 4.5m, the longitudinal joints shall be located at the lane delineations.

B All dimensions are in millimetres unless otherwise shown.

LEGEND:

T – Concrete slab thickness



DETAIL X **DETAIL Y**


JOINT DETAILS
RESERVOIR CUT TYPE

ONTARIO PROVINCIAL STANDARD DRAWING

CONCRETE PAVEMENT JOINT DETAILS

Nov 2017 | Rev 2

OPSD 552.010




CONTRACTION JOINT
WITHOUT DOWEL BAR

CONTRACTION JOINT

EXPANSION JOINT

CONSTRUCTION JOINT



LONGITUDINAL KEYWAY JOINT
WITHOUT TIE BAR

LONGITUDINAL JOINT
SINGLE LANE PAVING

LONGITUDINAL JOINT
MULTI–LANE PAVING

LONGITUDINAL JOINT
CONCRETE BASE ADJACENT
TO CURB WITH GUTTER

NOTES:

1 Field cut 20mm thick expansion joint filler material, the width of pavement plus shoulder and depth of concrete base.

2 Use 15x760mm epoxy coated deformed tie bars spaced at 600mm OC at 0.5*T*.


3 Depth of curb and gutter shall be extended to coincide with bottom of concrete slab.

A Paving width shall not exceed 4.5m without a longitudinal joint. Where paving width is greater than 4.5m, the longitudinal joints shall be located at the lane delineations.

B All dimensions are in millimetres unless otherwise shown.

LEGEND:

T – Concrete base thickness




JOINT DETAIL X

ONTARIO PROVINCIAL STANDARD DRAWING


COMPOSITE PAVEMENT JOINT DETAILS

Nov 2017 | Rev 2


OPSD 552.020




SECTION A–A




SECTION B–B



LEG DETAIL



STAKE DETAIL



PLAN

NOTES:

1 A minimum of 3 stakes shall be uniformly spaced per side per lane.

2 Spacer wire shall be cut in two places and the mid section removed after staking assembly is in position. Section removed shall be a minimum length of 300mm.

3 Arc or resistance spot weld, alternate ends of adjacent dowels only, top or bottom of dowel bar.

A At bridge approaches the skew shall match the approach slab skew.

B Load transfer device shall be shop coated with RC–250, Tectyl 506, or Protec 6116–DS Amber.

C Load transfer devices not required in shoulders or gore areas.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


LOAD TRANSFER DEVICE SKEWED CONTRACTION JOINT

CONCRETE OR COMPOSITE PAVEMENT


Nov 2017 | Rev 3

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 552.050




SECTION A–A




SECTION B–B



LEG DETAIL



STAKE DETAIL



PLAN

NOTES:

1 A minimum of 3 stakes shall be uniformly spaced per side per lane.

2 Spacer wire shall be cut in two places and the mid section removed after staking assembly is in position. Section removed shall be a minimum length of 300mm.

3 Arc or resistance spot weld, alternate ends of adjacent dowels only, top or bottom of dowel bar.

A At bridge approaches the load transfer device shall match the skew of the approach slab.

B Load transfer device shall be shop coated with RC–250, Tectyl 506, or Protect 6116–DS Amber.

C Load transfer devices not required in shoulders or gore areas.


D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2017 | Rev 3


LOAD TRANSFER DEVICE
RIGHT ANGLE CONTRACTION JOINT
CONCRETE OR COMPOSITE PAVEMENT

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 552.051




SECTION A–A




SECTION B–B




ISOMETRIC VIEW WITHOUT EXPANSION JOINT MATERIAL



EXPANSION JOINT MATERIAL HOLDER DETAIL



PLAN



DOWEL CAP DETAIL

NOTES:

1 A minimum of 3 stakes shall be uniformly spaced per side per lane.

2 The compressible cap material shall be a non–absorptive, closed cell polyethylene foam.

3 The expansion joint material shall be machined punched with 35mm diameter holes to accommodate the dowels.

4 Expansion joint material to extend for the full width of the concrete slab.

5 Expansion joint material holder may be continuous or broken as shown.

6 Arc or resistance spot weld, alternate ends of adjacent dowels only, top or bottom of dowel bar.

A At bridge approaches the skew of the device shall match the approach slab skew.

B Load transfer device shall be shop coated with RC–250, Tectyl 506, or Protec 6116–DS Amber.

C Load transfer devices not required in shoulders or gore areas, however, expansion joint material shall extend through the shoulder, gore areas, and curb and gutter to edge of concrete slab.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2017 | Rev 3

LOAD TRANSFER DEVICE SKEWED EXPANSION JOINT


CONCRETE OR COMPOSITE PAVEMENT

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 552.060




SECTION A–A



PLAN




SECTION B–B




DOWEL CAP DETAIL

NOTES:

1 A minimum of 3 stakes shall be uniformly spaced per side per lane.
2 The compressible cap material shall be a non–absorptive, closed cell polyethylene foam.
3 The expansion joint material shall be machined punched with 35mm diameter holes to accommodate the dowels.
4 Expansion joint material to extend for the full width of the concrete slab.
5 Expansion joint material holder may be continuous or broken as shown.
6 Arc or resistance spot weld, alternate ends of adjacent dowels only, top or bottom of dowel bar.



ISOMETRIC VIEW
WITHOUT EXPANSION JOINT MATERIAL



EXPANSION JOINT MATERIAL HOLDER DETAIL

A At bridge approaches the skew of the device shall match the approach slab skew.
B Load transfer device shall be shop coated with RC–250, Tectyl 506, or Protec 6116–DS Amber.
C Load transfer devices not required in shoulders or gore areas however, expansion joint material shall extend through the shoulder, gore areas, and curb and gutter to edge of concrete slab.
D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2017 | Rev 3

LOAD TRANSFER DEVICE
RIGHT ANGLE EXPANSION JOINT
CONCRETE OR COMPOSITE PAVEMENT


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 552.061




DETAIL


PLAN




PLAN



SECTION A–A



SECTION C–C



SECTION B–B

NOTES:

1 Depth of curb with gutter shall be extended to coincide with bottom of concrete slab.

2 When base is open graded drainage layer, a minimum of 100mm of Granular A material is required beneath the base.

A Exit ramp shown. Entrance ramp requires similar treatment.

B All joints shall be according to OPSD 551.020 and 552.010.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

CONCRETE PAVEMENT IN GORE AREAS

Nov 2017 | Rev 2


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 553.010




DETAIL


PLAN




PLAN



SECTION A–A



SECTION B–B



SECTION C–C

NOTES:

1 Depth of curb with gutter shall be extended to coincide with bottom of concrete slab.

2 When base is open graded drainage layer, a minimum of 100mm of Granular A material is required beneath the base.

A Exit ramp shown. Entrance ramp requires similar treatment.

B All joints shall be according to OPSD 551.020 and 552.020.


C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


COMPOSITE PAVEMENT IN GORE AREAS

Nov 2017 | Rev 2


OPSD 553.020




PLAN



DETAIL



SECTION A–A



SECTION B–B

NOTES:

1 Depth of curb and gutter shall be extended to coincide with bottom of concrete pavement.


2 When base is open graded drainage layer, a minimum 100mm of Granular A material is required beneath the base.

A All concrete surfaces in contact with asphalt pavement shall be treated with a tack coat prior to hot mix paving.


B All joints shall be according to OPSD 551.010 and 552.010.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	2
CONCRETE PAVEMENT SHOULDER TERMINAL			
	OPSD 554.010		




PLAN



DETAIL



SECTION A–A



SECTION B–B

NOTES:

1 Depth of curb and gutter shall be extended to coincide with bottom of concrete base.


2 When base is open graded drainage layer, a minimum of 100mm of Granular A material is required beneath the base.

A All concrete surfaces in contact with hot mix pavement shall be treated with a tack coat prior to hot mix paving.


B All joints shall be according to OPSD 551.010 and 552.020.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	2
COMPOSITE PAVEMENT SHOULDER TERMINAL			
	OPSD 554.020		




PLAN



TYPE A: LONGITUDINAL SECTION
CONCRETE PAVEMENT TO HOT MIX PAVEMENT WITH GRANULAR BASE



TYPE B: LONGITUDINAL SECTION
CONCRETE PAVEMENT TO COMPOSITE PAVEMENT



TYPE C: LONGITUDINAL SECTION
CONCRETE PAVEMENT TO STRUCTURE APPROACHES

NOTES:

1 Adjust the position of the last joint immediately previous to the fixed location joint, so that the slabs on each side of this last joint are not shorter than 3.0m, nor longer than 5.0m. Last joint shall be an expansion joint for Type B section.

A When base is open graded drainage layer, a minimum 100mm of Granular A material is required beneath it.

B For Type C details of approach slab see structural drawing(s).

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

CONCRETE PAVEMENT
APPROACH TREATMENT TO HOT MIX AND COMPOSITE PAVEMENTS AND STRUCTURE APPROACHES


Nov 2017 | Rev 2

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS


OPSD 555.010




PLAN



TYPE A: LONGITUDINAL SECTION
COMPOSITE PAVEMENT TO HOT MIX PAVEMENT WITH GRANULAR BASE



TYPE B: LONGITUDINAL SECTION
COMPOSITE PAVEMENT TO CONCRETE PAVEMENT



TYPE C: LONGITUDINAL SECTION
COMPOSITE PAVEMENT TO STRUCTURE APPROACHES

NOTES:

1 Adjust the position of the last joint immediately previous to the fixed location joint, so that the slabs on each side of this last joint are not shorter than 3.0m, nor longer than 5.0m. Last joint shall be an expansion joint for Type B section.

A When base is open graded drainage layer, a minimum of 100mm of Granular A is required beneath it.

B All concrete surfaces in contact with hot mix pavement shall be treated with a tack coat prior to hot mix paving.

C For Type C details of approach slab see structural drawing(s).

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2017 | Rev 2

COMPOSITE PAVEMENT


APPROACH TREATMENT TO
HOT MIX AND CONCRETE PAVEMENTS AND
STRUCTURE APPROACHES

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S

OPSD 555.020



PLAN VIEW
CONCRETE REPAIR GREATER THAN 4m IN LENGTH



PLAN VIEW
CONCRETE REPAIR 4m OR LESS IN LENGTH

LEGEND:

New concrete

NOTES:

1 Tie bars are required at longitudinal joints except where the new concrete abuts existing concrete. Prior to placing new concrete, exposed longitudinal joints shall be treated with a bond breaker.


2 All dowel bar and tie bar sections shown for new concrete are according to OPSD 552.010 and 552.020.

3 Alternative J5 expansion joint when specified.


A This OPSD to be read in conjunction with OPSD 560.020 and 560.030.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev 6
COMPOSITE OR EXPOSED CONCRETE PAVEMENTS FULL DEPTH CONCRETE SLAB REPAIR LAYOUT		OPSD 560.010




SECTION A–A
EXPANSION JOINT




SECTION B–B
CONTRACTION JOINT




SECTION C–C
LONGITUDINAL JOINT




SECTION D–D




J1, CONTRACTION JOINT




J2, CONTRACTION JOINT




J3, LONGITUDINAL JOINT



J4, LONGITUDINAL JOINT



J5, EXPANSION JOINT



J6, EXPANSION JOINT

NOTES:


1 The free end of dowel bars shall be coated with an approved bond breaking material immediately prior to placing concrete.
2 The epoxy resin shall envelop the bar within the drill hole and shall be set prior to placing the concrete.
A Waxed building paper or equivalent bond breaker required at all joints.
B This standard to be read in conjunction with OPSD 560.010.
C Grout retention disks shall be used on all bars.
D All dimensions are in millimetres unless otherwise shown.

LEGEND:


New concrete

T_1 = Thickness of concrete

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
EXPOSED CONCRETE PAVEMENT FULL DEPTH CONCRETE SLAB REPAIR JOINT DETAILS			
			OPSD 560.020



PLAN



SECTION A–A

Cross–Stitching Drill Hole and Tie Bar Requirements				
T	Drilling Angle	Drill Hole Offset from Longitudinal Crack	Drill Hole Length	Length of Tie Bar
200	35	140	280	220
210	35	145	300	240
220	35	150	310	250
230	35	155	330	270
240	35	160	350	290
250	35	170	370	310
260	35	175	380	320
270	35	180	400	340
280	35	190	420	360
290	35	195	430	370
300	45	140	360	310
310	45	145	380	330
320	45	150	390	340
330	45	155	410	360
340	45	160	420	370
350	45	165	430	380
360	45	170	450	400

NOTES:

1 Tie bars shall be spaced at 600mm centre to centre.
2 Tie bars shall not be placed within 600mm of a transverse joint, longitudinal joint, or the edge of pavement.
3 Holes shall be drilled perpendicular to the face of the longitudinal crack.

A All dimensions are in millimetres unless otherwise shown.


LEGEND:

T – Concrete pavement thickness


ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2017 | Rev 1

CONCRETE PAVEMENT AND CONCRETE BASE CROSS–STITCHING LONGITUDINAL CRACKS


OPSD 560.025




SECTION A–A
EXPANSION JOINT




SECTION B–B
CONTRACTION JOINT




SECTION C–C
LONGITUDINAL JOINT




SECTION D–D




J1, CONTRACTION JOINT
J4, LONGITUDINAL JOINT




J2, CONTRACTION JOINT



J3
LONGITUDINAL JOINT



J5, EXPANSION JOINT



J6, TRANSVERSE EXPANSION JOINT

NOTES:

1 The free end of dowel bars shall be coated with an approved bond breaking material immediately prior to placing concrete.

2 The epoxy resin shall envelop the bar within the drill hole and shall be set prior to placing the concrete.

A This standard to be read in conjunction with OPSD 560.010.

B Grout retention disks shall be used on all bars.


C All dimensions are in millimetres unless otherwise shown.

LEGEND:

New concrete

T_1 = Thickness of concrete

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
COMPOSITE PAVEMENT FULL DEPTH CONCRETE SLAB REPAIR JOINT DETAILS			
			OPSD 560.030



PLAN VIEW
OF CONCRETE PAVEMENT SURFACE

CROSS SECTION VIEWS

NOTES:

1 Compressible material to extend 75mm beyond sawcut into existing transverse or longitudinal joints or working cracks.

2 Compressible material to extend 25mm below concrete removal areas.

A Repair areas to be screeded from centre of patch to the patch boundaries to achieve maximum bond.


B All dimensions are in millimetres unless otherwise shown.

LEGEND:

Repair area

Surface distress

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
PARTIAL DEPTH REPAIRS IN CONCRETE PAVEMENT			
	OPSD 560.040		



VEHICULAR **NON–VEHICULAR**

NOTES:


1 Concrete paver thickness:
  – for vehicular traffic – 80mm minimum.
  – for non–vehicular traffic – 60mm minimum.

2 This OPSD shall be read in conjunction with OPSD 200 and 600 series drawings.

3 Edge restraint according to manufacturer's requirements.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	2
INTERLOCKING CONCRETE PAVERS ON GRANULAR BASE			
	OPSD 561.010		



NOTES:

1 Concrete paver thickness:
  – for vehicular traffic – 80mm minimum.
  – for non–vehicular traffic – 60mm minimum.

2 Drains shall be installed at low points and selected intervals through concrete or asphalt base to suit subgrade conditions.

3 This OPSD shall be read in conjunction with OPSD 200 and 600 Series drawings.

4 Edge restraint according to manufacturer's requirements.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

INTERLOCKING CONCRETE PAVERS ON CONCRETE OR ASPHALT BASE

Nov 2016 | Rev 2

OPSD 561.020



NOTES:

1 Drains shall be installed at low points and selected intervals through concrete or asphalt base to suit subgrade conditions.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


INTERLOCKING CONCRETE PAVERS FOR RETROFIT CROSSWALK INSTALLATION

Nov 2016 | Rev 2

OPSD 561.030



TANGENT



SUPERELEVATED

LEGEND:

S – Rate of pavement superelevation in percent, %.

NOTES:

1 When curb and gutter is adjacent to concrete pavement or base, this drawing shall be used in conjunction with OPSD 552.010 and 552.020.

2 Flexible and composite pavement shall be placed 5mm above the adjacent edge of gutter.

3 For slipforming procedure a 5% batter is acceptable.


A Treatment at entrances shall be according to OPSD 351.010.

B Outlet treatment shall be according to the OPSD 610 Series.


C The transition from one curb type to another shall be a minimum length of 3.0m, except in conjunction with guide rail where it shall be according to the OPSD 900 Series.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
CONCRETE BARRIER CURB WITH WIDE GUTTER			
	OPSD 600.010		



TANGENT



SUPERELEVATED

LEGEND:

S – Rate of pavement superelevation in percent, %.

NOTES:

1 When curb and gutter is adjacent to concrete pavement or base, this OPSD shall be used in conjunction with OPSD 552.010 and 552.020.

2 Flexible and composite pavement shall be placed 5mm above the adjacent edge of gutter.


3 For slipforming procedure a 5% batter is acceptable.

A The transition from one curb type to another shall be a minimum length of 3.0m, except in conjunction with guide rail where it shall be according to the OPSD 900 series.

B This OPSD shall be read in conjunction with OPSD 912.450, 912.451, and 912.452.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev 0	
CONCRETE BARRIER CURB WITH WIDE GUTTER AND WIDE BACK			OPSD 600.011



TANGENT **SUPERELEVATED**

LEGEND:

S – Rate of pavement superelevation in percent, %.

NOTES:

1 When curb and gutter is adjacent to concrete pavement or base, this drawing shall be used in conjunction with OPSD 552.010 and 552.020.

2 Flexible and composite pavement shall be placed 5mm above the adjacent edge of gutter.

3 For slipforming procedure a 5% batter is acceptable.


A Treatment at entrances shall be according to OPSD 351.010.

B Outlet treatment shall be according to the OPSD 610 Series.


C The transition from one curb type to another shall be a minimum length of 3.0m, except in conjunction with guide rail where it shall be according to the OPSD 900 Series.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
CONCRETE SEMI–MOUNTABLE CURB WITH WIDE GUTTER			
	OPSD 600.020		



TANGENT



SUPERELEVATED

LEGEND:

S – Rate of pavement superelevation in percent, %.

NOTES:

1 When curb and gutter is adjacent to concrete pavement or base, this drawing shall be used in conjunction with OPSD 552.010 and 552.020.

2 Flexible and composite pavement shall be placed 5mm above the adjacent edge of gutter.

3 For slipforming procedure a 5% batter is acceptable.


A Treatment at entrances shall be according to OPSD 351.010.

B Outlet treatment shall be according to the OPSD 610 Series.


C The transition from one curb type to another shall be a minimum length of 3.0m, except in conjunction with guide rail where it shall be according to the OPSD 900 Series.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
CONCRETE MOUNTABLE CURB WITH WIDE GUTTER			
	OPSD 600.030		



TANGENT



SUPERELEVATED

LEGEND:

S – Rate of pavement superelevation in percent, %.

NOTES:

1 Flexible and composite pavement shall be placed 5mm above the adjacent edge of gutter.
2 When sidewalk is continuously adjacent, the dropped curb at entrances shall be reduced to 75mm.
3 For slipforming procedure a 5% batter is acceptable.
4 For composite pavement the depth of concrete curb shall be adjusted to depth of concrete pavement.
5 When tie bars are specified, refer to OPSD 552.010 and 552.020 for details.

A Treatment at entrances shall be according to OPSD 351.010.
B Outlet treatment shall be according to the OPSD 610 Series.
C The transition from one curb type to another shall be a minimum length of 3.0m, except in conjunction with guide rail where it shall be according to the OPSD 900 Series.
D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

CONCRETE BARRIER CURB WITH STANDARD GUTTER


Nov 2012 | Rev 2

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · O P S

OPSD 600.040



TANGENT



SUPERELEVATED

LEGEND:

S – Rate of pavement superelevation in percent, %.

NOTES:

1 When curb and gutter is adjacent to concrete pavement or base, this drawing shall be used in conjunction with OPSD 552.010 and 552.020.

2 Flexible and composite pavement shall be placed 5mm above the adjacent edge of gutter.

3 For slipforming procedure a 5% batter is acceptable.


A Treatment at entrances shall be according to OPSD 351.010.

B Outlet treatment shall be according to the OPSD 610 Series.


C The transition from one curb type to another shall be a minimum length of 3.0m, except in conjunction with guide rail where it shall be according to the OPSD 900 Series.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
CONCRETE SEMI–MOUNTABLE CURB WITH STANDARD GUTTER			
	OPSD 600.060		



TANGENT



SUPERELEVATED


LEGEND:


S – Rate of pavement superelevation in percent, %.

NOTES:


1 When curb and gutter is adjacent to concrete pavement or base, this OPSD shall be used in conjunction with OPSD 552.010 and 552.020.
2 Flexible and composite pavement shall be placed 5mm above the adjacent edge of gutter.
3 For slipforming procedure a 5% batter is acceptable.
A The transition from one curb type to another shall be a minimum length of 3.0m, except in conjunction with guide rail where it shall be according to the OPSD 900 series.
B This OPSD shall be read in conjunction with OPSD 912.450, 912.451, and 912.452
C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev 0	ONTARIO STANDARDS MUNICIPAL – PROVINCIAL
CONCRETE SEMI–MOUNTABLE CURB WITH WIDE GUTTER AND NARROW BACK			OPSD 600.061





STIRRUP DETAIL



DETAIL AT CATCH BASIN

NOTES:

1 Flexible and composite pavement shall be placed 5mm above the adjacent edge of gutter.

2 When sidewalk is continuously adjacent, the dropped curb at entrances shall be reduced to 75mm.

3 For slipforming procedure a 5% batter is acceptable.

A Stage I surface shall be cleaned of foreign material prior to placement of Stage II material.


B Treatment at entrances shall be according to OPSD 351.010.

C Outlet treatment shall be according to the OPSD 610 Series.

D The transition from one curb type to another shall be a minimum length of 3.0m, except in conjunction with guide rail, when it shall be according to the OPSD 900 Series.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
CONCRETE BARRIER CURB WITH STANDARD GUTTER TWO STAGE CONSTRUCTION			
			OPSD – 600.070



NOTES:

1 When curb and gutter is adjacent to concrete pavement or base, this drawing shall be used in conjunction with OPSD 552.010 and 552.020.

2 Flexible and composite pavement shall be placed 5mm above the adjacent edge of gutter.

3 For slipforming procedure a 5% batter is acceptable.


A Treatment at entrances shall be according to OPSD 351.010.

B Outlet treatment shall be according to the OPSD 610 Series.

C The transition from one curb type to another shall be a minimum length of 3.0m, except in conjunction with guide rail where it shall be according to the OPSD 900 Series.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
CONCRETE BARRIER CURB WITH NARROW GUTTER			
	OPSD 600.080		



NOTES:

1 When curb and gutter is adjacent to concrete pavement or base, this drawing shall be used in conjunction with OPSD 552.010 and 552.020.

2 Flexible and composite pavement shall be placed 5mm above the adjacent edge of gutter.

3 For slipforming procedure a 5% batter is acceptable.


A Treatment at entrances shall be according to OPSD 351.010.

B Outlet treatment shall be according to the OPSD 610 Series.

C The transition from one curb type to another shall be a minimum length of 3.0m, except in conjunction with guide rail where it shall be according to the OPSD 900 Series.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
CONCRETE SEMI-MOUNTABLE CURB WITH NARROW GUTTER			
	OPSD 600.090		



NOTES:

1 When curb and gutter is adjacent to concrete pavement or base, this drawing shall be used in conjunction with OPSD 552.010 and 552.020.

2 Flexible and composite pavement shall be placed 5mm above the adjacent edge of gutter.

3 For slipforming procedure a 5% batter is acceptable.


A Treatment at entrances shall be according to OPSD 351.010.

B Outlet treatment shall be according to the OPSD 610 Series.

C The transition from one curb type to another shall be a minimum length of 3.0m, except in conjunction with guide rail where it shall be according to the OPSD 900 Series.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
CONCRETE MOUNTABLE CURB WITH NARROW GUTTER			
	OPSD 600.100		



NOTES:

1 When sidewalk is continuously adjacent, the dropped curb at entrances shall be reduced to 75mm.

2 For slipforming procedure a 5% batter is acceptable.


A Treatment at entrances shall be according to OPSD 351.010.

B Outlet treatment shall be according to the OPSD 610 Series.


C The transition from one curb type to another shall be a minimum length of 3.0m, except in conjunction with guide rail where it shall be according to the OPSD 900 Series.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
CONCRETE BARRIER CURB			
	OPSD 600.110		



ASPHALT BARRIER CURB
(MACHINE LAID)




ASPHALT MOUNTABLE CURB WITH WIDE GUTTER

NOTES:


1 Depth of asphalt curb with gutter at pavement edge shall equal depth of new pavement, but in no case less than 130mm.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2013	Rev	2
ASPHALT CURB AND ASPHALT CURB WITH GUTTER			
	OPSD 601.010		



ISOMETRIC VIEW




SECTION

NOTES:


A Class of concrete shall be C2 according to CSA A23.1.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
PRECAST CONCRETE CURB			
	OPSD 603.020		




TYPICAL PLAN VIEW




SECTION X–X **SECTION Y–Y** **SECTION Z–Z**

BARRIER CURB with GUTTER



SECTION X–X **SECTION Y–Y** **SECTION Z–Z**

SEMI–MOUNTABLE CURB with GUTTER



SECTION X–X **SECTION Y–Y** **SECTION Z–Z**


MOUNTABLE CURB with GUTTER

NOTES:


A For asphalt spillway details refer to OPSD 605.040.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
90° CONCRETE OUTLET FOR CONCRETE CURB WITH GUTTER			
	OPSD 604.010		



PLAN



SECTION Y–Y




SECTION Z–Z

NOTES:

A For asphalt spillway details refer to OPSD 605.040.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2013	Rev	2
90° ASPHALT OUTLET FOR ASPHALT CURB WITH GUTTER			
	OPSD 604.020		




TYPICAL PLAN VIEW

CURB with GUTTER Type	D m	R m
Barrier	1.9	2.1
Semi–Mountable	2.5	2.8
Mountable	2.9	2.9




SECTION X–X




SECTION Y–Y

BARRIER CURB with GUTTER




SECTION X–X




SECTION Y–Y

SEMI–MOUNTABLE CURB with GUTTER



SECTION X–X



SECTION Y–Y

MOUNTABLE CURB with GUTTER

NOTES:

A For asphalt spillway details refer to OPSD 605.040.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2


45° CONCRETE OUTLET

FOR CONCRETE CURB WITH GUTTER


OPSD 605.010




30° ASPHALT OUTLET



45° ASPHALT OUTLET



SECTION X–X, Typ



SECTION Y–Y, Typ


NOTES:

1 For asphalt curb with gutter refer to OPSD 601.010.


A For asphalt spillway details refer to OPSD 605.040.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2013	Rev	2
30° AND 45° ASPHALT OUTLETS FOR ASPHALT CURB WITH GUTTER			
	OPSD 605.020		



PLAN




SECTION X–X

CURB with GUTTER Type	*x*
Barrier	200
Semi–Mountable	300
Mountable	400

NOTES:


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
45° CONCRETE OUTLET FOR CONCRETE CURB WITH GUTTER AT END OF RUN			
	OPSD 605.030		




PLAN

WITH 30° or 45° ASPHALT OR CONCRETE OUTLET




PLAN

WITH 90° ASPHALT OUTLET




SECTION X–X



PLAN

WITH 90° CONCRETE OUTLET

Outlet OPSD	Curb with Gutter Type	*a*	*b*
604.020 605.020	Mountable	400	–
605.010 605.030	Barrier	200	–
	Semi–mountable	300	–
	Mountable	400	–
604.010	Barrier	–	200
	Semi–mountable	–	300
	Mountable	–	400




SECTION Y–Y

NOTES:


1 Depression of spillway shall coincide with outlet end of gutter outlet.

2 All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2013	Rev	2
ASPHALT SPILLWAYS			
	OPSD 605.040		



PLAN




WITHOUT CATCH BASIN




WITH CATCH BASIN

SECTION X–X



SECTION Y–Y



SECTION Z–Z


NOTES:

1 Concrete fillet shall be poured integrally with concrete curb with gutter and shall extend to a point where the back to back distance between curbs is 300mm.


2 Surface between backs of curbs shall extend from end of fillet to point where back to back of curb width is 2.0m or as specified.

A All dimensions are in millimetres unless otherwise specified.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
600mm RADIUS BARRIER BULLNOSE			
	OPSD 606.010		




PLAN




WITHOUT CATCH BASIN **WITH CATCH BASIN**

SECTION X–X



SECTION Y–Y



SECTION Z–Z


NOTES:

1 Concrete fillet shall be poured integrally with concrete curb with gutter and shall extend to a point where the back to back distance between curbs is 300mm.


2 Surface between backs of curbs shall extend from end of fillet to point where back to back of curb width is 2.0m or as specified.

A All dimensions are in millimetres unless otherwise specified.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
600mm RADIUS MOUNTABLE BULLNOSE			
	OPSD 606.020		




PLAN



SECTION X–X



SECTION Y–Y



SECTION Z–Z


NOTES:

1 Concrete fillet shall be poured integrally with concrete curb with gutter and shall extend to a point where the back to back distance between curbs is 300mm.


2 Surface between backs of curbs shall extend from end of fillet to point where back to back of curb width is 2.0m or as specified.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
800mm RADIUS MOUNTABLE BULLNOSE CURB WITH GUTTER TWIN INLET			
	OPSD 606.030		



PLAN




WITHOUT CATCH BASIN



WITH CATCH BASIN

SECTION X–X



SECTION Y–Y

NOTES:

1 In transition from curb with gutter to offset curb, this portion shall be horizontal.


A All dimensions are in millimetres unless otherwise specified.

LEGEND:


G – Gutter width or offset distance.

$$a = \frac{G_1 + G_2}{2}$$


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
OVER 600mm RADIUS MOUNTABLE BULLNOSE			
	OPSD 607.010		



PLAN




WITHOUT CATCH BASIN



WITH CATCH BASIN

SECTION X–X



SECTION Y–Y

NOTES:

1 In transition from curb with gutter to offset curb, this portion shall be horizontal.


A All dimensions are in millimetres unless otherwise specified.

LEGEND:


G – Gutter width or offset distance

$$a = \frac{G_1 + G_2}{2}$$

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
OVER 600mm RADIUS BARRIER BULLNOSE			
	OPSD 607.020		



MOUNTABLE CURB WITH GUTTER



BARRIER AND SEMI-MOUNTABLE CURB WITH GUTTER


NOTES:

1 Slope shall match existing shoulder.


A This drawing shall be read in conjunction with OPSD 600 series curb with gutter drawings.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
METHOD OF TERMINATION FOR CONCRETE CURB WITH GUTTER			
	OPSD 608.010		



SECTION A–A




PLAN




BARRIER CURB

SEMI–MOUNTABLE or MOUNTABLE
CURB WITH GUTTER

DETAILS



BARRIER
CURB WITH GUTTER




SECTION B–B


NOTE:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
CATCH BASIN FRAME WITH GRATE INSTALLATION AT CURB WITH GUTTER			
			OPSD 610.010



PLAN



SECTION A–A




SECTION B–B

NOTES:


A When catch basins are placed back to back on both sides of the concrete barrier, backfill shall be unshrinkable backfill to the limits of the excavation and within 150mm of top of concrete catch basin structure. Where catch basins are not placed back to back they shall be staggered with a minimum spacing of 10m.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
CATCH BASIN FRAME WITH GRATE SHOULDER INSTALLATION AT CONCRETE BARRIER			
	OPSD 610.020		



PLAN



SECTION A–A


SECTION B–B


NOTES:

1 Catch basin to be centred within the sidewalk bay.
2 Concrete sidewalk thickness shall be 300mm for sidewalk bay with catch basin.
3 For expansion joint detail see OPSD 310.010.

A In grassed boulevard areas, install 300mm wide concrete support collar.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	2
FRAME WITH COVER INSTALLATION FOR INLET TYPE CATCH BASINS			
	OPSD 610.030		






SUMP DETAIL


ALTERNATIVES



A PRECAST SLAB BASE



B CAST-IN-PLACE BASE



C PRECAST FLAT CAP

NOTES:

1 The sump is measured from the lowest invert.

A Granular backfill shall be placed to a minimum thickness of 300mm all around the maintenance hole.

B Precast concrete components shall be according to OPSD 701.030, 701.031, or 701.032.

C Structure exceeding 5.0m in depth shall include safety platform according to OPSD 404.020.

D Pipe support according to OPSD 708.020.

E For benching and pipe opening details, see OPSD 701.021.

F For adjustment unit and frame installation, see OPSD 704.010.

G All dimensions are nominal.

H All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2014 | Rev 5


PRECAST CONCRETE MAINTENANCE HOLE

1200mm DIAMETER


OPSD 701.010




ALTERNATIVES




A PRECAST MONOLITHIC BASE




B CAST–IN–PLACE BASE



C TAPERED TRANSITION SLAB



D 1200mm PRECAST FLAT CAP



E 1500mm PRECAST FLAT CAP

NOTES:

1 For sump detail, see OPSD 701.010.

A Granular backfill shall be placed to a minimum thickness of 300mm all around the maintenance hole.

B Precast concrete components shall be according to OPSD 701.030, 701.031, 701.040, 701.041, 703.011, 703.021, and 706.010.

C Structures exceeding 5.0m in depth shall include safety platform according to OPSD 404.020 or 404.021.

D Pipe support shall be according to OPSD 708.020.

E For benching and pipe opening details, see OPSD 701.021.

F For adjustment unit and frame installation, see OPSD 704.010.

G All dimensions are nominal.


H All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2014 | Rev 5

PRECAST CONCRETE MAINTENANCE HOLE

1500mm DIAMETER

OPSD 701.011



NOTES:

1 For sump detail, see OPSD 701.010.

A Granular backfill shall be placed to a minimum thickness of 300mm all around the maintenance hole.

B Precast concrete components shall be according to OPSD 701.030, 701.031, 701.050, 701.051, 703.012, 703.022, and 706.020.

C Structures exceeding 5.0m in depth shall include safety platform according to OPSD 404.020 or 404.022.

D Pipe support shall be according to OPSD 708.020.


E For benching and pipe opening details, see OPSD 701.021.

F For adjustment unit and frame installation, see OPSD 704.010.


G All dimensions are nominal.

H All dimensions are in millimetres unless otherwise shown.


ALTERNATIVES




A CAST-IN-PLACE BASE



B TAPERED TRANSITION SLAB




C 1200mm PRECAST FLAT CAP




D 1800mm PRECAST FLAT CAP


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	5
PRECAST CONCRETE MAINTENANCE HOLE 1800mm DIAMETER			
			OPSD 701.012




ALTERNATIVES



A CAST-IN-PLACE BASE



B 1200mm PRECAST FLAT CAP



C 2400mm PRECAST FLAT CAP

NOTES:

1 For sump detail, see OPSD 701.010.

A Granular backfill shall be placed to a minimum thickness of 300mm all around the maintenance hole.

B Precast concrete components shall be according to OPSD 701.030, 701.031, 701.060, 701.061, 703.013, 703.023, 706.030 and 706.031.

C Structures exceeding 5.0m in depth shall include safety platform according to OPSD 404.020.

D Pipe support shall be according to OPSD 708.020.


E For benching and pipe opening details, see OPSD 701.021.

F For adjustment unit and frame installation, see OPSD 704.010.


G All dimensions are nominal.

H All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	5
PRECAST CONCRETE MAINTENANCE HOLE 2400mm DIAMETER			
	OPSD 701.013		




ALTERNATIVES



A CAST-IN-PLACE BASE



B 1200mm PRECAST FLAT CAP



C 3000mm PRECAST FLAT CAP

NOTES:

1 For sump detail, see OPSD 701.010.

A Granular backfill shall be placed to a minimum thickness of 300mm all around the maintenance hole.

B Precast concrete components shall be according to OPSD 701.030, 701.031, 701.070, 701.071, 703.014, 703.024, 706.040 and 706.041.

C Structures exceeding 5.0m in depth shall include safety platform according to OPSD 404.020.

D Pipe support shall be according to OPSD 708.020.


E For benching and pipe opening details, see OPSD 701.021.

F For adjustment unit and frame installation, see OPSD 704.010.


G All dimensions are nominal.

H All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev 4
PRECAST CONCRETE MAINTENANCE HOLE 3000mm DIAMETER		**OPSD 701.014**




ALTERNATIVES



A CAST–IN–PLACE BASE



B 1200mm PRECAST FLAT CAP



C 3600mm PRECAST FLAT CAP

NOTES:

1 For sump detail, see OPSD 701.010.

A Granular backfill shall be placed to a minimum thickness of 300mm all around the maintenance hole.

B Precast concrete components shall be according to OPSD 701.030, 701.031, 701.080, 701.081, and 703.015.

C Structures exceeding 5.0m in depth shall include safety platform according to OPSD 404.020.

D Pipe support shall be according to OPSD 708.020.


E For benching and pipe opening details, see OPSD 701.021.

F For adjustment unit and frame installation, see OPSD 704.010.


G All dimensions are nominal.

H All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	4
PRECAST CONCRETE MAINTENANCE HOLE 3600mm DIAMETER			
			OPSD 701.015




1. Right angle bend




2. Tee connection




3. Three way junction




4. Four way junction




5. Straight through




6. Dead end



7. Wye connection



8. 45° bend



Section

MAXIMUM SIZE HOLE IN THE WALL IN PRECAST RISER SECTIONS					
Maintenance Hole Diameter	No. 1–4	No. 5 and 6	No. 8	No.7	
				Inlet Hole	Outlet Hole
1200	700	860	780	700	860
1500	860	1220	960	860	1170
1800	1220	1485	1220	1220	1485
2400	1485	2020	1760	1485	2020
3000	1930	2450	2300	1930	2450
3600	2470	3085	2730	2470	3085

NOTES:

1 Slopes shall be maintained from the outlet hole opening for top of benching.

A Concrete for benching shall be 30MPa.

B When benching is hand–finshed, it shall be given wood float finish, channel shall be given steel trowel finish.

C Benching slope and height shall be as specified.

D When specified, maintenance holes that are 1200mm in diameter with a uniform channel for 200 or 250mm pipe may be prebenched at the manufacturer with standardized benching slope and channel orientation.


E All dimensions are nominal.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2014 | Rev 4

MAINTENANCE HOLE BENCHING AND PIPE OPENING ALTERNATIVES


OPSD 701.021




1200mm DIAMETER
MAINTENANCE HOLE




PLAN OF TAPERED TOP




PLAN OF FLAT CAP
WITH REINFORCING STEEL BARS




PLAN OF FLAT CAP
WITH WWR




SECTION A–A
TAPERED TOP WITH HOOP STEEL



SECTION A–A
TAPERED TOP WITH WWR



SECTION B–B




SECTION C–C


NOTES:

A This drawing shall be read in conjunction with OPSD 701.031 and 701.032.
B Centre reinforcing steel in riser ±20mm. All other reinforcing steel shall have 25mm minimum cover.
C Steps shall be according to OPSD 405.010 or 405.020.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	4
PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS 1200mm DIAMETER TAPERED TOP AND FLAT CAP			
	OPSD 701.030		




PLAN OF RISER
WITH HOOP STEEL




SECTION A–A
RISERS < 900mm HIGH




SECTION A–A
RISERS ≥ 900mm




PLAN OF RISER
WITH WWR




SECTION B–B




PLAN OF MONOLITHIC BASE WITH WWR



SECTION C–C



PLAN OF MONOLITHIC BASE
WITH REINFORCING STEEL BARS
AND WWR



SECTION D–D

NOTES:

A This drawing shall be read in conjunction with OPSD 701.030 and 701.032.
B Centre reinforcing steel in riser ±20mm. All other reinforcing steel shall have 25mm minimum cover.
C Steps shall be according to OPSD 405.010 or 405.020.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS


1200mm DIAMETER

RISER AND MONOLITHIC BASE


Nov 2014 | Rev 2

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · O P S


OPSD 701.031




PLAN OF BASE SLAB
WITH REINFORCING STEEL BARS



PLAN OF BASE SLAB
WITH WWF



SECTION A–A



SECTION B–B

NOTES:

1 Welded splice shall develop minimum 50% yield strength of bar or wire, as applicable.

A This drawing shall be read in conjunction with OPSD 701.030 and 701.031.
B Centre reinforcing steel in riser ±20mm. All other reinforcing steel shall have 25mm minimum cover.
C All dimensions are nominal.
D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS


1200mm DIAMETER

BASE SLAB


Nov 2014 | Rev 2

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPS


OPSD 701.032




1500 to 1200mm DIAMETER
MAINTENANCE HOLE




PLAN OF
TRANSITION CONE




SECTION A–A




PLAN OF TRANSITION SLAB
WITH REINFORCING STEEL BARS




SECTION B–B




PLAN OF TRANSITION SLAB
WITH WWR




SECTION C–C




PLAN OF TAPERED TRANSITION SLAB
WITH REINFORCING STEEL BARS



SECTION D–D



PLAN OF TAPERED TRANSITION SLAB WITH WWR



SECTION E–E

NOTES:

A This OPSD shall be read in conjunction with OPSD 701.041.
B Centre reinforcing in transition cone ±25mm. All other reinforcing steel shall have 25mm minimum cover.
C Steps shall be according to OPSD 405.010 or 405.020.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2014 | Rev 4

PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS


1500mm DIAMETER TRANSITION CONE AND SLABS

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPSS


OPSD 701.040




PLAN OF RISER WITH WWR




SECTION A–A




PLAN OF BASE SLAB WITH REINFORCING STEEL BARS




SECTION B–B




PLAN OF MONOLITHIC BASE WITH REINFORCING STEEL BARS




SECTION D–D




PLAN OF BASE SLAB WITH WWR






SECTION C–C



PLAN OF MONOLITHIC BASE WITH WWR



SECTION E–E

NOTES:

1 Welded splice shall develop minimum 50% yield strength of bar or wire, as applicable.

A This OPSD shall be read in conjunction with OPSD 701.040.

B If single cage of reinforcing in riser, centre reinforcing in wall ±25mm. All other reinforcing steel shall have 25mm minimum cover.

C Steps shall be according to OPSD 405.010 or 405.020.

D All dimensions are nominal.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS

1500mm DIAMETER RISER AND BASES


Nov 2014 | Rev 2

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · O P S


OPSD 701.041




1800 to 1200mm DIAMETER MAINTENANCE HOLE




PLAN OF TRANSITION SLAB WITH REINFORCING STEEL BARS




SECTION A–A




PLAN OF TRANSITION SLAB WITH WWR




SECTION B–B




PLAN OF TAPERED TRANSITION SLAB WITH REINFORCING STEEL BARS



SECTION C–C



PLAN OF TAPERED TRANSITION SLAB WITH WWR



SECTION D–D

NOTES:

A This OPSD shall be read in conjunction with OPSD 701.051.

B All reinforcing steel shall have 25mm minimum cover.

C Steps shall be according to OPSD 405.010 or 405.020.

D All dimensions are nominal.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS

1800mm DIAMETER TRANSITION SLABS


Nov 2014 | Rev 4

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · O P S


OPSD 701.050




PLAN OF RISER
WITH WWR




PLAN OF BASE SLAB
WITH REINFORCING STEEL BARS




PLAN OF BASE SLAB
WITH WWR



SECTION A–A



SECTION B–B



SECTION C–C

NOTES:

1 Welded splice shall develop 50% of yield strength of wires.

A This OPSD shall be read in conjunction with OPSD 701.050.

B If single cage of reinforcement in riser, centre reinforcement in wall ±25mm. All other reinforcing steel shall have 25mm minimum cover.

C Steps shall be according to OPSD 405.010 or 405.020.

D All dimensions are nominal.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS
1800mm DIAMETER
RISER AND BASE SLAB


Nov 2014 | Rev 2

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPSS


OPSD 701.051




2400 to 1200mm DIAMETER MAINTENANCE HOLE




PLAN OF TRANSITION SLAB WITH REINFORCING STEEL BARS



SECTION A–A



PLAN OF TRANSITION SLAB WITH WWR



SECTION B–B

NOTES:

A This OPSD shall be read in conjunction with OPSD 701.061.
B All reinforcing steel shall have 25mm minimum cover.
C Steps shall be according to OPSD 405.010 or 405.020.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS

2400mm DIAMETER TRANSITION SLAB


Nov 2014 | Rev 4

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPS


OPSD 701.060




PLAN OF RISER




PLAN OF BASE SLAB
WITH REINFORCING STEEL BARS




PLAN OF BASE SLAB
WITH WWR



SECTION A–A



SECTION B–B



SECTION C–C

NOTES:

1 Welded splice shall develop minimum 50% of yield strength of wires.

A This OPSD shall be read in conjunction with OPSD 701.060.

B All reinforcing steel shall have 25mm minimum cover.

C Steps shall be according to OPSD 405.010 or 405.020.

D All dimensions are nominal.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS

2400mm DIAMETER RISER AND BASE SLAB


Nov 2014 | Rev 2

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPSS


OPSD 701.061




3000 to 1200mm DIAMETER MAINTENANCE HOLE




PLAN OF TRANSITION SLAB WITH REINFORCING STEEL BARS



PLAN OF TRANSITION SLAB WITH WWR AND REINFORCING STEEL BARS



SECTION A–A



SECTION B–B

NOTES:

A This OPSD shall be read in conjunction with OPSD 701.071.
B All reinforcing steel shall have 25mm minimum cover.
C Steps shall be according to OPSD 405.010 or 405.020.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS


3000mm DIAMETER TRANSITION SLAB

Nov 2014 | Rev 3


OPSD 701.070




PLAN OF RISER




PLAN OF BASE SLAB
WITH REINFORCING STEEL BARS




PLAN OF BASE SLAB
WITH WWR



SECTION A–A



SECTION B–B



SECTION C–C

NOTES:

1 Welded splice shall develop minimum 50% of yield strength of reinforcing steel bars or wire, as applicable.

A This OPSD shall be read in conjunction with OPSD 701.070.
B All reinforcing steel shall have 25mm minimum cover.
C Steps shall be according to OPSD 405.010 or 405.020.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS

3000mm DIAMETER RISER AND BASE SLAB


Nov 2014 | Rev 2

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S


OPSD 701.071




3600 to 1200mm DIAMETER MAINTENANCE HOLE




PLAN OF TRANSITION SLAB WITH REINFORCING STEEL BARS



PLAN OF TRANSITION SLAB WITH REINFORCING STEEL BARS AND WWR



SECTION A–A



SECTION B–B

NOTES:

A This OPSD shall be read in conjunction with OPSD 701.081.
B All reinforcing steel shall have 25mm minimum cover.
C Steps shall be according to OPSD 405.010 or 405.020.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS

3600mm DIAMETER TRANSITION SLAB


Nov 2014 | Rev 3

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · O P S


OPSD 701.080




PLAN OF RISER




PLAN OF BASE SLAB
WITH REINFORCING STEEL BARS




PLAN OF BASE SLAB
WITH WWR



SECTION A–A



SECTION B–B



SECTION C–C

NOTES:

1 Welded splice shall develop minimum 50% of yield strength of reinforcing steel bars or wires, as applicable.

A This OPSD shall be read in conjunction with OPSD 701.080.

B All reinforcing steel shall have 25mm minimum cover.

C Steps shall be according to OPSD 405.010 or 405.020.

D All dimensions are nominal.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE MAINTENANCE HOLE COMPONENTS


3600mm DIAMETER RISER AND BASE SLAB

Nov 2014 | Rev 2


ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPSS

OPSD 701.081







DETAIL A



DETAIL B



DETAIL C



DETAIL D

NOTES:

1 Depth of frost strap shall be as specified.


A Frost straps shall be placed so they do not interfere with sewer pipe openings and the steps.

B Frost straps shall be placed when specified.


C Galvanizing shall be according to CAN/CSA G164.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
FROST STRAP INSTALLATION			
	OPSD 701.100		




PLAN



BENCHING DETAIL



SECTION A–A



SECTION B–B

NOTES:

1 The sump is measured from the lowest invert. Benching as shown in Benching Detail.
2 Lap horizontal 10M rebar 300mm. Laps shall be placed at corners.
3 Lap horizontal wires 300mm or weld. Welds to develop 75% of yield strength of wire. Laps or welds shall be placed at corners.
4 End rebar or WWR in base 75mm from outside face of wall.

A Where inlet is placed across ditch and is accessible to vehicular traffic, grating slope shall be 6H:1V or flatter.
B Granular backfill shall be placed a minimum thickness of 300mm all around the ditch inlet maintenance hole.
C Concrete for benching shall be 30MPa.
D Benching slope and height shall be as specified.
E Grating shall be according to OPSD 403.010.
F Steps shall be according to OPSD 405.010 or 405.020.
G Maximum pipe size: straight through–1200mm dia; right angle pipes–700mm diameter.
H Pipe support shall be according to OPSD 708.020.
I Centre reinforcing in walls ±35mm. All other reinforcing shall have a minimum cover of 25mm.
J All dimensions are nominal.
K All dimensions are in millimetres unless otherwise shown.


Opening Dimensions			
Grate		a	b
Type	Slope		
B	2H:1V	670	52
	3H:1V	632	71
	4H:1V	618	78
	6H:1V	608	83
	HOR	600	87

ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2014 | Rev 3


PRECAST CONCRETE DITCH INLET MAINTENANCE HOLE – TYPE A

1200 x 1200mm


OPSD 702.040



PLAN



BENCHING DETAIL



SECTION A–A

SECTION B–B

NOTES:

1 The sump is measured from the lowest invert. Benching as shown in Benching Detail.
2 Lap horizontal 10M rebar 300mm. Laps shall be placed at corners.
3 Lap horizontal wires 300mm or weld. Welds to develop 75% of yield strength of wire. Laps or welds shall be placed at corners.
4 End rebar or WWR in base 75mm from outside face of wall.
A Where inlet is placed across ditch and is accessible to vehicular traffic, grating slope shall be 6H:1V or flatter.
B Granular backfill shall be placed a minimum thickness of 300mm all around the ditch inlet maintenance hole.
C Concrete for benching shall be 30MPa.
D Benching slope and height shall be as specified.
E Grating shall be according to OPSD 403.010.
F Steps shall be according to OPSD 405.010 or 405.020.
G Maximum pipe size: straight through–1200mm dia; right angle pipes – – 700mm diameter.
H Pipe support shall be according to OPSD 708.020.
I Centre reinforcing in walls ±35mm. All other reinforcing shall have a minimum cover of 25mm.
J All dimensions are nominal.
K All dimensions are in millimetres unless otherwise shown.

Opening Dimensions				
Grate		a	b	c
Type	Slope			
C	2H:1V	1341	66	1473
	3H:1V	1265	104	1473
	4H:1V	1237	118	1473
B	6H:1V	1216	65	1346
	8H:1V	1210	68	1346
	10H:1V	1206	70	1346
	HOR	1200	73	1346

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2014 | Rev 3


PRECAST CONCRETE DITCH INLET MAINTENANCE HOLE – TYPE B

1200 x 1200mm


ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 702.050







1500mm DIAMETER MAINTENANCE HOLE




PLAN OF FLAT CAP WITH REINFORCING STEEL BARS



PLAN OF FLAT CAP WITH WWR



SECTION A–A



SECTION B–B

NOTES:

A All reinforcing steel shall have 25mm minimum cover.
B All dimensions are nominal.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE SINGLE INLET FLAT CAP

1500mm DIAMETER


Nov 2014	Rev	2

OPSD 703.011







1800mm DIAMETER MAINTENANCE HOLE




PLAN OF FLAT CAP WITH REINFORCING STEEL BARS



PLAN OF FLAT CAP WITH WWR



SECTION A–A



SECTION B–B


NOTES:


A All reinforcing steel shall have 25mm minimum cover.

B All dimensions are nominal.


C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	2
PRECAST CONCRETE SINGLE INLET FLAT CAP 1800mm DIAMETER			
	OPSD 703.012		







2400mm DIAMETER MAINTENANCE HOLE




PLAN OF FLAT CAP WITH REINFORCING STEEL BARS



PLAN OF FLAT CAP WITH WWR



SECTION A–A




SECTION B–B


NOTES:

A All reinforcing steel shall have 25mm minimum cover.
B All dimensions are nominal.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	2
PRECAST CONCRETE SINGLE INLET FLAT CAP 2400mm DIAMETER			
	OPSD 703.013		




3000mm DIAMETER MAINTENANCE HOLE




PLAN OF FLAT CAP WITH REINFORCING STEEL BARS



PLAN OF FLAT CAP WITH WWR



SECTION A–A



SECTION B–B

NOTES:

A All reinforcing steel shall have 25mm minimum cover.
B All dimensions are nominal.
C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE SINGLE INLET FLAT CAP


3000mm DIAMETER

Nov 2014	Rev	2


ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · O P S

OPSD 703.014







3600mm DIAMETER MAINTENANCE HOLE




PLAN OF FLAT CAP WITH REINFORCING STEEL BARS



PLAN OF FLAT CAP WITH WWR



SECTION A–A





SECTION B–B

NOTES:


A All reinforcing steel shall have 25mm minimum cover.
B All dimensions are nominal.
C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	2
PRECAST CONCRETE SINGLE INLET FLAT CAP 3600mm DIAMETER			
	OPSD 703.015		







1500mm DIAMETER MAINTENANCE HOLE




PLAN OF TWIN INLET FLAT CAP WITH REINFORCING STEEL BARS



PLAN OF TWIN INLET FLAT CAP WITH WWR



SECTION A–A





SECTION B–B

NOTES:


A All reinforcing steel shall have 25mm minimum cover.
B All dimensions are nominal.
C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	2
PRECAST CONCRETE TWIN INLET FLAT CAP 1500mm DIAMETER			
			OPSD 703.021







1800mm DIAMETER MAINTENANCE HOLE




PLAN OF TWIN INLET FLAT CAP WITH REINFORCING STEEL BARS



PLAN OF TWIN INLET FLAT CAP WITH WWR



SECTION A–A



SECTION B–B

NOTES:

A All reinforcing steel shall have 25mm minimum cover.
B All dimensions are nominal.
C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE TWIN INLET FLAT CAP


1800mm DIAMETER

Nov 2014 | Rev 2


ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · O P S

OPSD 703.022







2400mm DIAMETER MAINTENANCE HOLE




PLAN OF TWIN INLET FLAT CAP WITH REINFORCING STEEL BARS



PLAN OF TWIN INLET FLAT CAP WITH WWR



SECTION A–A





SECTION B–B

NOTES:


A All reinforcing steel shall have 25mm minimum cover.
B All dimensions are nominal.
C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	2
PRECAST CONCRETE TWIN INLET FLAT CAP 2400mm DIAMETER			
	OPSD 703.023		







3000mm DIAMETER MAINTENANCE HOLE




PLAN OF TWIN INLET FLAT CAP WITH REINFORCING STEEL BARS



PLAN OF TWIN INLET FLAT CAP WITH WWR AND REINFORCING STEELBARS



SECTION A–A




SECTION B–B


NOTES:

A All reinforcing steel shall have 25mm minimum cover.
B All dimensions are nominal.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	2
PRECAST CONCRETE TWIN INLET FLAT CAP 3000mm DIAMETER			
			OPSD 703.024




SECTION THROUGH TAPER TOP



SECTION THROUGH FLAT CAP



SECTION THROUGH CATCH BASIN



NOTES:

1 If first step is in an adjustment unit, the adjustment unit shall be of the type manufactured with a step in place.

2 Centre reinforcing in adjustment unit ±10mm.

3 Round and square adjustment units are available in sizes of 50, 75, 100, 150, and 300mm.

A Adjustment units shall not extend beyond the outside edge of the structure.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE ADJUSTMENT UNITS FOR MAINTENANCE HOLES, CATCH BASINS, AND VALVE CHAMBERS

Nov 2014 | Rev 3


OPSD 704.010




SECTION THROUGH TAPER TOP



SECTION THROUGH FLAT CAP



SECTION THROUGH CATCH BASIN



NOTES:

1 Adjustment units shall be bonded to the structure and each other as per manufacturer's recommendations.

A Installation and sealing of adjustment units and frame shall be according to adjustment unit manufacturer's recommendations.

B Adjustment units shall not extend beyond the outside edge of the structure.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

HIGH DENSITY POLYETHYLENE ADJUSTMENT UNITS FOR MAINTENANCE HOLES, CATCH BASINS, AND VALVE CHAMBERS


Nov 2018	Rev	2

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 704.011




SECTION THROUGH TAPER TOP



SECTION THROUGH FLAT CAP



SECTION THROUGH CATCH BASIN



NOTES:

1 First adjustment unit shall be bonded to structure with elastomeric adhesive.

A Installation and sealing of adjustment unit and frame shall be according to adjustment unit manufacturer's recommendations.

B Adjustment units shall not extend beyond the outside edge of the structure.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

EXPANDED POLYSTYRENE (EPS) ADJUSTMENT UNITS FOR MAINTENANCE HOLES, CATCH BASINS, AND VALVE CHAMBERS


Nov 2018 | Rev 1

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 704.012




SECTION THROUGH TAPER TOP



SECTION THROUGH FLAT CAP



SECTION THROUGH CATCH BASIN



NOTES:

1 First adjustment unit shall be bonded to structure with elastomeric adhesive.

A Installation and sealing of adjustment unit and frame shall be according to adjustment unit manufacturer's recommendations.

B Adjustment units shall not extend beyond the outside edge of the structure.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

RUBBER ADJUSTMENT UNITS FOR MAINTENANCE HOLES, CATCH BASINS, AND VALVE CHAMBERS


Nov 2018 | Rev | 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 704.013



PLAN



SECTION A–A




SECTION B–B

NOTES:


1 All construction joints shall be filled with fibre board or hot–poured rubberized asphalt joint sealing compound and joint filler.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	1
CONCRETE CATCH BASIN APRON MOUNTABLE CURB WITH WIDE GUTTER	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 705.001		



PLAN



SECTION A–A



SECTION B–B


NOTES:

A All construction joints shall be filled with fibre board or hot–poured rubberized asphalt joint sealing compound and joint filler.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	1
CONCRETE CATCH BASIN APRON BARRIER CURB WITH STANDARD GUTTER	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 705.002		


ALTERNATE STANDARD HEIGHTS	
ALTERNATIVE	DIMENSION
A	1980
B	1830
C	1520
D	1380



PLAN



SECTION A–A



SECTION B–B

NOTES:

1 Outlet hole size 525mm diameter maximum, location as required.

2 200mm diameter knockout to accommodate subdrain. Knockout shall be 60mm deep.

A Centre reinforcing in base slab and walls ±20mm.

B Granular backfill shall be placed to a minimum thickness of 300mm all around the catch basin.


C Frame, grate, and adjustment units shall be installed according to OPSD 704.010.

D Pipe support shall be according to OPSD 708.020.


E All dimensions are nominal.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev 4
PRECAST CONCRETE CATCH BASIN 600x600mm		
		OPSD 705.010




PLAN



BEAM DETAIL



SECTION A–A



SECTION B–B

Granular bedding


NOTES:

1 Outlet hole size 525mm diameter maximum, location as required.
2 200mm diameter knockout to accommodate subdrain. Knockout shall be 60mm deep.
3 Minimum clearance between beam recess and hole for pipe shall be 300mm or minimum clearance can be 150mm with addition of two 15M size rebar on 45 degree diagonal.

A Centre reinforcing in base slab and walls ±20mm.
B Granular backfill shall be placed to a minimum thickness of 300mm all around the catch basin.
C Frame, grate, and adjustment units shall be installed according to OPSD 704.010.
D Pipe support shall be according to OPSD 708.020.
E All dimensions are nominal.
F All dimensions are in millimetres unless otherwise shown.

ALTERNATE STANDARD HEIGHTS	
ALTERNATIVE	DIMENSION
A	1980
B	1830
C	1680


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	4
PRECAST CONCRETE TWIN INLET CATCH BASIN 600 x 1450mm			
		OPSD 705.020	




SECTION B–B

Alternate Standard Heights	
Alternate	Dimension
A	1980
B	1520
C	1380

Opening Dimensions			
Grate		*a*	*b*
Type	Slope		
A	2H:1V	670	52
	3H:1V	632	71
	4H:1V	618	78
	6H:1V	608	83
	HOR	600	87



SECTION A–A



FRONT VIEW

NOTES:

1 Outlet hole size 525mm maximum diameter, location as required.

A Where inlet is placed across ditch and is accessible to vehicular traffic, grating slope shall be 6H:1V or flatter.

B Center reinforcing in wall and slab ±25mm.

C Granular backfill shall be placed to a minimum thickness of 300mm all around the ditch inlet.


D Grating shall be according to OPSD 403.010.

E Pipe support shall be according to OPSD 708.020.

F All dimensions are nominal.

G All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	4
PRECAST CONCRETE DITCH INLET 600 x 600mm			
		OPSD 705.030	



TYPE A

Opening Dimensions			
Grate		*a*	*b*
Type	Slope		
B	2H:1V	670	52
	3H:1V	632	71
	4H:1V	618	78
	HOR	600	87

Alternate Standard Heights	
Alternate	Dimension
A	1980
B	1520
C	1380

TYPE B

Opening Dimensions				
Grate		*a*	*b*	*c*
Type	Slope			
C	2H:1V	1341	66	1473
	3H:1V	1265	104	1473
	4H:1V	1237	118	1473
B	6H:1V	1216	65	1346
	HOR	1200	73	1346

NOTES:

1 Outlet hole size 525mm max diameter.

A Where inlet is placed across ditch and is accessible to vehicular traffic, grating slope shall be 6H:1V or flatter.

B Center reinforcing in wall and base slab ±25mm.

C Lap riser horizontal wires 300mm. Laps shall be placed at corners.

D Granular backfill shall be placed to a minimum thickness of 300mm all around the ditch inlet.

E Grating shall be according to OPSD 403.010.

F Pipe support shall be according to OPSD 708.020.

G All dimensions are nominal.

H All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE DITCH INLETS 600 x 1200mm


Nov 2019 | Rev 4

ONTARIO STANDARDS – MUNICIPAL – PROVINCIAL


OPSD 705.040




TYPE A DITCH INLET




PLAN OF FLAT CAP WITH REINFORCING STEEL BARS



PLAN OF FLAT CAP WITH WWR




TYPE B DITCH INLET




FRONT VIEW

Opening Dimensions			
Grate		*a*	*b*
Type	Slope		
B	2H:1V	670	52
	3H:1V	632	71
	4H:1V	618	78
	Horizontal	600	87


Opening Dimensions				
Grate		*a*	*b*	*c*
Type	Slope			
C	2H:1V	1341	66	1473
	3H:1V	1265	104	1473
	4H:1V	1237	118	1473
B	6H:1V	1216	65	1346
	Horizontal	1200	73	1346




FRONT VIEW




SECTION A–A



SECTION C–C



SECTION B–B



SECTION D–D

NOTES:

A Where inlet is placed across ditch and is accessible to vehicular traffic, grating slope shall be 6H:1V or flatter.
B All reinforcing steel shall have 25mm minimum cover.
C Grating shall be according to OPSD 403.010.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE DITCH INLETS 600x1200mm WITH 1500mm DIAMETER FLAT CAP


Nov 2014 | Rev 3

ONTARIO STANDARD MUNICIPAL – PROVINCIAL

OPSD 706.010




TYPE A DITCH INLET




PLAN OF FLAT CAP WITH REINFORCING STEEL BARS

PLAN OF FLAT CAP WITH WWR




TYPE B DITCH INLET




FRONT VIEW

Opening Dimensions			
Grate		*a*	*b*
Type	Slope		
B	2H:1V	670	52
	3H:1V	632	72
	4H:1V	618	79
	Horizontal	600	87


Opening Dimensions				
Grate		*a*	*b*	*c*
Type	Slope			
C	2H:1V	1341	66	1473
	3H:1V	1265	104	1473
	4H:1V	1237	118	1473
B	6H:1V	1216	65	1346
	Horizontal	1200	73	1346




FRONT VIEW




SECTION A–A



SECTION C–C



SECTION B–B



SECTION D–D

NOTES:

A Where inlet is placed across ditch and is accessible to vehicular traffic, grating slope shall be 6H:1V or flatter.
B All reinforcing steel shall have 25mm minimum cover.
C Grating shall be according to OPSD 403.010.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE DITCH INLETS 600x1200mm WITH 1800mm DIAMETER FLAT CAP


Nov 2014 | Rev 3

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S


OPSD 706.020




TYPE A DITCH INLET




PLAN OF FLAT CAP WITH REINFORCING STEEL BARS




PLAN OF FLAT CAP WITH WWR



FRONT VIEW



SECTION A–A



SECTION B–B

Opening Dimensions			
Grate		*a*	*b*
Type	Slope		
B	2H:1V	670	52
	3H:1V	632	72
	4H:1V	618	79
	Horizontal	600	87

NOTES:

A Where inlet is placed across ditch and is accessible to vehicular traffic, grating slope shall be 6H:1V or flatter.
B All reinforcing steel shall have 25mm minimum cover.
C Grating shall be according to OPSD 403.010.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE DITCH INLET – TYPE A 600x1200mm WITH 2400mm DIAMETER FLAT CAP


Nov 2014 | Rev 3

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPSD

OPSD 706.030




PLAN OF FLAT CAP WITH REINFORCING STEEL BARS




SECTION A–A


Opening Dimensions				
Grate		*a*	*b*	*c*
Type	Slope			
C	2H:1V	1341	66	1473
	3H:1V	1265	104	1473
	4H:1V	1237	118	1473
B	6H:1V	1216	65	1346
	Horizontal	1200	73	1346




TYPE B DITCH INLET




FRONT VIEW OF FLAT CAP WITH REINFORCING STEEL BARS



PLAN OF FLAT CAP WITH WWR AND REINFORCING STEEL BARS



SECTION B–B



FRONT VIEW OF FLAT CAP WITH WWR

NOTES:


A Where inlet is placed across ditch and is accessible to vehicular traffic, grating slope shall be 6H:1V or flatter.
B All reinforcing steel shall have 25mm minimum cover.
C Grating shall be according to OPSD 403.010.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE DITCH INLET – TYPE B 600x1200mm WITH 2400mm DIAMETER FLAT CAP

Nov 2014 | Rev 2


OPSD 706.031




TYPE A
DITCH INLET




PLAN OF FLAT CAP
WITH REINFORCING STEEL BARS




PLAN OF FLAT CAP
WITH WWR



FRONT VIEW



SECTION A–A



SECTION B–B

Opening Dimensions			
Grate		*a*	*b*
Type	Slope		
B	2H:1V	670	52
	3H:1V	632	72
	4H:1V	618	79
	Horizontal	600	87

NOTES:

A Where inlet is placed across ditch and is accessible to vehicular traffic, grating slope shall be 6H:1V or flatter.
B All reinforcing steel shall have 25mm minimum cover.
C Grating shall be according to OPSD 403.010.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE DITCH INLET – TYPE A
600x1200mm
WITH 3000mm DIAMETER FLAT CAP


Nov 2014 | Rev 3

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS

OPSD 706.040




PLAN OF FLAT CAP WITH REINFORCING STEEL BARS




SECTION A–A


Opening Dimensions				
Grate		*a*	*b*	*c*
Type	Slope			
C	2H:1V	1341	66	1473
	3H:1V	1265	104	1473
	4H:1V	1237	118	1473
B	6H:1V	1216	65	1346
	Horizontal	1200	73	1346




TYPE B DITCH INLET




FRONT VIEW WITH REINFORCING STEEL BARS



FRONT VIEW WITH WWF



PLAN OF FLAT CAP WITH WWR



SECTION B–B

NOTES:


A Where inlet is placed across ditch and is accessible to vehicular traffic, grating slope shall be 6H:1V or flatter.
B All reinforcing steel shall have 25mm minimum cover.
C Grating shall be according to OPSD 403.010.
D All dimensions are nominal.
E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE DITCH INLET – TYPE B 600x1200mm WITH 3000mm DIAMETER FLAT CAP

Nov 2014 | Rev 2


OPSD 706.041



PLAN



SECTION A–A



SECTION B–B

NOTES:

1 Sewer pipe shall be according to CAN/CSA A257.2, class to match that of the higher class adjacent pipe.

A Bedding for MH tee to match pipe bedding either side of tee.

B Granular backfill shall be placed to a minimum thickness of 300mm all around the maintenance hole tee.

C Minimum steel in connection shall equal area of steel in pipe.

D Structures exceeding 5.0m in depth shall include safety platform according to OPSD 404.020.


E All dimensions are nominal.

F All dimensions are in millimetres unless otherwise shown.


LEGEND:

L = Standard length of pipe (2440mm minimum)

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	4
PRECAST CONCRETE MAINTENANCE HOLE MANUFACTURED TEE			
	OPSD 707.010		



CONNECTION WITHOUT RISER



CONNECTION WITH RISER

NOTES:

1 For sewers smaller than 450mm dia, connections shall be made using approved factory made tees. For all other sizes, either factory made tees or approved saddles may be used.

2 Riser bedding shall have a minimum width of riser pipe outside diameter plus 600mm.

A Approved cut–in tool shall be used for field installed tees and saddles.

B Maintenance holes shall be used at the main sewer to connect catch basin connections greater than 300mm.


C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

CATCH BASIN CONNECTION FOR RIGID MAIN PIPE SEWER


Nov 2016 | Rev 3

OPSD 708.010




ELEVATION

FLEXIBLE JOINT
RIGID AND FLEXIBLE PIPE



SECTION A–A



ELEVATION

CONCRETE CRADLE
RIGID PIPE

For installation of these connectors refer to manufacturer's instructions.

A full length of pipe may be used in conjunction with a flexible watertight connector.


FLEXIBLE, WATERTIGHT CONNECTOR
RIGID AND FLEXIBLE PIPE

NOTES:

1 Pipe shall be supported with concrete or unshrinkable fill to the first pipe joint.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	4
SUPPORT FOR PIPE AT CATCH BASIN OR MAINTENANCE HOLE			
			OPSD 708.020




NOTES:

1 For catch basin connections 300mm in diameter or less, factory made tees shall be used.


A For catch basin connections greater than 300mm in diameter, maintenance holes shall be used at the main sewer.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	3
CATCH BASIN CONNECTION FOR FLEXIBLE MAIN PIPE SEWER			
	OPSD 708.030		



STRUCTURE TREATMENT



SECTION
A–A, B–B, C–C

RECTANGULAR

CIRCULAR

CONCRETE SLAB DETAIL

SHAPE OF CAP	EXISTING STRUCTURE INSIDE DIMENSIONS		SLAB THICKNESS	BOTTOM STEEL REINFORCEMENT	
				SIZE	SPACING EACH WAY
RECTANGULAR	L	W	150	15M	175
	≤ 600	≤ 1450			
	> 600 ≤ 1200	1200			
CIRCULAR	$D \leq 2400$		200	15M	225
CIRCULAR	$2400 < D \leq 4000$		200	25M	150


NOTES:

A Class of concrete: 30MPa at 28 Days.


B Clear cover for steel reinforcement: 60mm±20mm.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2019	Rev	4
CAPPING EXISTING STRUCTURES MAXIMUM 4.0m COVER			
	OPSD 710.010		



LONGITUDINAL SECTION



SECTION A–A

Diameter of Concrete Pipe	Minimum Dia of CSP Extensions
300	500
375	600
450	600
525	700

NOTES:

1 Extend pipe beyond the toe of slope as specified.

2 Outside surface of concrete pipe shall be thoroughly scrubbed to ensure proper bond.

A Bedding and backfill as specified.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


CONCRETE PIPE CULVERT AND SEWER EXTENSIONS USING CORRUGATED STEEL PIPE

TEMPORARY CONDITIONS


Nov 2017 | Rev 3

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL

OPSD 800.010



FRONT ELEVATION
NOTE 2



LONGITUDINAL SECTION
NOTE 2

TABLE SHOWING DIMENSIONS								
Culvert *W x H*	CSP *d*	CSP Arch *s x r*	A_1	A_2	A_3	*B,K*	*M*	*N*
610x 610	800	—	300	300	840	300	380	95
900x 610	900	—	300	300	760	300	450	145
900x 900	1000	—	300	300	840	300	380	50
1220x 900	1200	—	300	300	760	300	450	150
1220x1220	1400	—	300	300	840	300	380	90
1520x 900	—	1390x 970	330	330	840	380	400	35
1520x1220	1500	—	330	330	760	380	480	140
1520x1520	1600	—	330	330	840	380	400	40
1830x 900	—	1880x1260	355	355	815	450	450	180
1830x1220	—	* 2060x1520	355	355	760	450	480	150
1830x1520	1800	—	355	355	760	450	500	140

* Structural plate construction

NOTES:

1 Corrugated steel pipe shall be cut 610mm +*B* from end and installed as in longitudinal section.

2 Open frame culvert shown. For box frame culverts, *K=0*. *T* is the same for open and box frame culverts.

A Culverts with headwalls: *K=0* and *M=0*.

B Class of concrete shall be 30MPa.

C Bedding and backfill as specified.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


CONCRETE RIGID FRAME BOX AND OPEN CULVERT EXTENSIONS USING CORRUGATED STEEL PIPE

TEMPORARY CONDITIONS

Nov 2017 | Rev 3

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 800.011



SQUARE END
END FINISH


ALL TYPES
CORRUGATED
STEEL PIPE

PARTIAL BEVEL
NOTE 1

STEP–BEVEL
NOTE 1

SKEW END

END FINISH
STRUCTURAL PLATE CORRUGATED STEEL PIPE



SKEW NUMBER TYPICAL

NOTES:

1 For a partial bevel or a step–bevel cut end finish, this OPSD shall be read in conjunction with OPSD 801.030.

A A skew end cut end finish shall not be combined with a partial bevel or a step–bevel cut end finish.

B Square end, partial bevel, or step–bevel cut end finish may be used on a culvert installed on a skew between skew numbers 60 and 120.


C A skew end cut end finish may be used on a culvert installed on a skew between skew numbers 50 and 130.

D Reinforcement of pipe ends or contour grading of embankment slope shall be as specified.


E Slope protection shall be as specified.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	3
CUT END FINISH CIRCULAR PIPE AND PIPE–ARCH CORRUGATED STEEL PIPE			
	OPSD 801.010		




SIDE ELEVATION



FRONT ELEVATION



PLAN



FRONT ELEVATION

PIPE–ARCH

Span x Rise	Steel Minimum Thickness	Dimensions					Approx slope	Body
		A ± 25	*B* Max	*H* ± 25	*L* ± 50	*W* ± 50		
560 x 420	1.6	175	280	175	610	915	2.000	1Pc
680 x 500	1.6	205	405	175	810	1220	2.000	1Pc
910 x 660	2.0	255	405	175	990	1525	1.875	1Pc
1030 x 740	2.0	305	460	205	1170	1905	1.875	1Pc
1150 x 820	2.8	330	535	255	1345	2130	1.750	2Pc
1390 x 970	2.8	430	660	330	1575	2285	1.875	2Pc
1630 x1120	2.8	455	760	330	1755	2590	1.875	2Pc
1880 x1260	2.8/3.5	455	915	330	1955	3200	1.625	3Pc

CIRCULAR PIPE

Pipe Dia	Steel Minimum Thickness	Dimensions					Approx slope	Body
		A ± 25	*B* Max	*H* ± 25	*L* ±50	*W* ±50		
300	1.6	150	150	175	535	610	2.250	1Pc
400	1.6	175	200	175	660	760	2.250	1Pc
500	1.6	225	300	175	915	1065	2.125	1Pc
600	1.6	250	330	175	1040	1220	2.125	1Pc
800	2.0	305	405	225	1295	1450	2.125	1Pc
900	2.0	355	485	255	1525	1830	2.000	1Pc
1000	2.8	405	635	320	1750	2135	2.125	2Pc
1200	2.8	455	740	330	1980	2285	2.000	2Pc
1400	2.8	455	840	330	2135	2590	2.000	2Pc
1600	2.8/3.5	455	915	330	2210	2895	1.875	3Pc
1800	2.8/3.5	455	1120	330	2210	3100	1.500	3Pc
2000	2.8/3.5	455	1220	330	2210	3350	1.375	3Pc
2200	2.8/3.5	455	1320	330	2210	3505	1.333	3Pc
2400	2.8/3.5	455	1475	330	2210	3710	1.125	3Pc

NOTES:

A When a toe plate extension is specified, it shall be the same thickness and material as the end section.

B All 3 piece bodies have 2.8mm sides and 3.5mm centre panels. Multiple panel bodies shall have lap seams that are tightly joined by galvanized rivets or bolts.

C For CSP 1600mm and larger and for CSPA 1880 x 1260mm, reinforced edges shall be supplemented with galvanized stiffener angles. Angles shall be attached by galvanized nuts and bolts.

D All surfaces shall be galvanized.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

END SECTION DETAILS CORRUGATED STEEL PIPE

Nov 2017 | Rev 2


ONTARIO STANDARDS MUNICIPAL–PROVINCIAL

OPSD 801.020

TABLE 1 – Step–Bevel for Circular Structural Plate Pipe						
Dia	*H* for bevels of		*V* for bevels of		*X* for bevels of	
	1.5H:1V	2H:1V	1.5H:1V	2H:1V	1.5H:1V	2H:1V
1500	1830	1830	1220	910	140	295
1660	1830	1830	1220	910	220	375
1810	1830	2440	1220	1220	295	295
1970	1830	2440	1220	1220	375	375
2120	1830	3050	1220	1520	450	300
2280	1830	3050	1220	1520	530	380
2430	3050	3050	2030	1520	200	455
2590	3050	3050	2030	1520	280	535
2740	3050	3660	2030	1830	355	455
3050	3050	3660	2030	1830	510	610
3360	3050	3660	2030	1830	665	765
3670	3050	3660	2030	1830	820	920
3990	3050	3660	2030	1830	980	1080
4300	3660	3660	2440	1830	930	1235
4610	3660	3660	2440	1830	1085	1390
4920	3660	6100	2440	3050	1240	935
5230	6100	6100	4070	3050	580	1090
5540	6100	6100	4070	3050	735	1245
5850	6100	7320	4070	3660	890	1095
6160	6100	7320	4070	3660	1045	1250
6470	6100	7320	4070	3660	1200	1405
6780	6100	7320	4070	3660	1355	1560
7090	6100	7320	4070	3660	1510	1715
7400	6100	7320	4070	3660	1665	1870
7710	6100	7320	4070	3660	1820	2025
8020	6100	7320	4070	3660	1975	2180


TABLE 2 – Partial Bevel and Step–Bevel for Pipe–Arch Structural Plate Pipe									
Span	Rise	*X*	*H* for bevels of			*V*	*Y* for bevels of		
			1.5H:1V	2H:1V	3H:1V		1.5H:1V	2H:1V	3H:1V
2060	1520	660	1290	1720	2580	860	—	—	—
2240	1630	660	1450	1940	2910	970	—	—	—
2440	1750	710	1560	2080	3050	1040	—	—	20
2590	1880	710	1750	2340	3050	1170	—	—	150
2690	2080	760	1980	2640	3050	1320	—	—	300
3100	1980	810	1750	2340	3050	1170	—	—	150
3400	2010	810	1800	2400	3050	1200	—	—	180
3730	2290	910	2070	2760	3050	1380	—	—	360
3890	2690	*1090	2400	3050	3660	1600	—	80	380
4370	2870	*1300	2360	3050	3660	1570	—	50	350
4720	3070	*1240	2750	3050	3660	1830	—	310	610
5050	3330	*1220	3050	3050	3660	2110	80	590	890
5490	3530	*1300	3050	3660	3660	2230	200	400	1010
5890	3710	*1370	3050	3660	3660	2340	310	510	1120
6250	3910	*1300	3050	3660	3660	2610	580	780	1390
7040	4060	1370	3050	3660	—	2690	660	860	—
7620	4240	1500	3050	3660	—	2740	710	910	—

* Denotes dimension to top of corner plate.




STEP–BEVEL

CIRCULAR STRUCTURAL PLATE PIPE



PARTIAL BEVEL



STEP–BEVEL

PIPE–ARCH STRUCTURAL PLATE PIPE

NOTES:

A Dimensions X, Y, V, and H are standardized by Corrugated Steel Pipe Institute.

B Dimensions for span and rise are nominal. Dimensions for bevel details are actual.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2017 | Rev 3

BEVEL DETAILS
CIRCULAR AND PIPE–ARCH
STRUCTURAL PLATE CORRUGATED STEEL PIPE

OPSD 801.030

STEEL END SECTION FOR ELLIPTICAL CONCRETE PIPE

Equiv. Dia	Ellipse Dimensions		Steel Minimum Thickness	Toe Plate Dimensions				∠ Dimensions	
	Span	Rise		A	H	W	Overall width	4H:1V Slope	6H:1V Slope
460	585	355	1.6	205	150	735	1145	405	610
610	760	485	1.6	205	150	915	1320	915	1370
685	865	560	2.0	305	230	1015	1625	1220	1830
760	965	610	2.0	305	230	1120	1725	1420	2135
840	1065	685	2.8	305	230	1220	1830	1725	2590
915	1145	740	2.8	405	305	1295	2110	1930	2895
1065	1345	865	2.8	405	305	1500	2310	2440	3660
1220	1525	965	2.8	405	305	1675	2490	2845	4265
1370	1730	1090	2.8	405	305	1880	2690	3355	5030
1525	1930	1220	2.8	405	305	2030	2845	3860	5790

STEEL END SECTION FOR CIRCULAR PIPE

Pipe Dia	Steel Minimum Thickness	Toe Plate Dimensions				∠ Dimensions	
		A	H	W	Overall width	4H:1V Slope	6H:1V Slope
300	1.6	200	150	450	850	n/a	700
400	1.6	200	150	550	950	800	1200
450	1.6	200	150	600	1000	1000	1500
500	1.6	200	150	650	1050	1200	1800
525	1.6	200	150	675	1075	1300	1950
600	1.6	200	150	750	1150	1600	2400
700	2.8	300	225	850	1450	1800	2700
750	2.8	300	225	900	1500	2000	3000
800	2.8	300	225	950	1550	2200	3300
900	2.8	300	225	1050	1650	2600	3900
1000	2.8	400	300	1150	1950	3000	4500
1050	2.8	400	300	1200	2000	3200	4800
1200	2.8	400	300	1350	2150	3800	5700
1350	2.8	400	300	1500	2300	4400	6600
1400	2.8	400	300	1550	2350	4600	6900

STEEL END SECTION FOR ARCHED STEEL PIPE

Equivalent Diameter	Ellipse Dimensions		Steel Minimum Thickness	Toe Plate Dimensions				∠ Dimensions	
	Span	Rise		A	H	W	Overall width	4H:1V Slope	6H:1V Slope
400–CSP	450	340	1.6	200	150	600	1000	560	840
450–Spiral Rib	500	390	1.6	200	150	650	1050	760	1140
500–CSP	560	420	1.6	200	150	710	1110	880	1320
525–Spiral Rib	580	465	1.6	200	150	730	1130	1060	1590
600–CSP	680	500	1.6	200	150	830	1230	1200	1800
600–Spiral Rib	660	530	1.6	200	150	810	1210	1320	1980
700–CSP	800	580	2.8	300	225	950	1550	1320	1980
750–Spiral Rib	830	660	2.8	300	225	980	1580	1640	2460
800–CSP	910	660	2.8	300	225	1060	1660	1640	2460
900–CSP	1030	740	2.8	300	225	1180	1780	1960	2940
900–Spiral Rib	1010	790	2.8	300	225	1160	1760	2160	3240
1000–CSP	1150	820	2.8	400	300	1300	2100	2280	3420
1050–Spiral Rib	1160	920	2.8	400	300	1310	2110	2680	4020
1200–CSP	1390	970	2.8	400	300	1540	2340	2880	4320
1200–Spiral Rib	1340	1050	2.8	400	300	1490	2290	3200	4800
1350–Spiral Rib	1485	1190	2.8	400	300	1635	2435	3760	5640
1400–CSP	1630	1120	2.8	400	300	1780	2580	3480	5220
1500–Spiral Rib	1670	1300	2.8	400	300	1820	2620	4200	6300
1600–CSP	1880	1260	2.8	400	300	2030	2830	4040	6060
1650–Spiral Rib	1815	1450	2.8	400	300	1965	2765	4800	7200
1800–CSP	2130	1400	2.8	400	300	2280	3080	4600	6900

NOTES:

A This OPSD shall be read in conjunction with OPSD 801.041, 801.042, and 801.043. Notes and tables shown on this standard apply to the noted standards.

B Safety slope end treatment attach to pipes up to 600mm with Type 1 or 3 connector. All other sizes attach with Type 2 or 4 connector.

C Safety bars shall be fabricated from Schedule 40 galvanized steel pipe. Safety bars shall be galvanized after fabrication.

D All surfaces shall be galvanized.

E Details of construction materials and workmanship not shown on this drawing shall be according to CSA G401.

F End sections shall have slotted holes for safety bar attachment.

G Cross drainage structures are perpendicular to the centreline of the road. Parallel drainage structures are parallel to centreline of the road.

H All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2017 | Rev 3


CULVERT AND SEWER
SAFETY SLOPE END TREATMENT
NOTES AND TABLES

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 801.040




PARALLEL DRAINAGE STRUCTURE




CROSS DRAINAGE STRUCTURE

CIRCULAR AND ARCHED CORRUGATED PIPES



PARALLEL DRAINAGE STRUCTURE



CROSS DRAINAGE STRUCTURE

CIRCULAR SMOOTH WALLED AND ELLIPTICAL PIPES

Concrete Pipe Shown


NOTES:

1 Longitudinal safety bar required only when span is greater than 750mm. When the open span of any cross drainage structure is less than 750mm, no longitudinal safety bars are required. Longitudinal bars shall be welded to the transverse bars to make a single piece structure.


A This OPSD shall be read in conjunction with OPSD 801.040, 801.042, and 801.043.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	3
CULVERT AND SEWER SAFETY SLOPE END TREATMENT ASSEMBLY DETAILS			
	OPSD 801.041		




SECTION A–A




TYPE 1–CONNECTOR DETAIL




TAPERED SLEEVE FOR ATTACHING STEEL END SECTIONS TO SMOOTH WALLED PIPE
Concrete Pipe Shown




SECTION B–B




TYPE 3–CONNECTOR DETAIL



TYPE 2–CONNECTOR DETAIL



SMOOTH TAPERED SLEEVE DETAIL



TYPE 4–CONNECTOR DETAIL

CIRCULAR AND ARCHED CORRUGATED PIPES

CIRCULAR SMOOTH WALLED AND ELLIPTICAL PIPES

NOTES:


A This OPSD shall be read in conjunction with OPSD 801.040, 801.041, and 801.043.

B All dimensions are in millimetres unless otherwise shown.


LEGEND:

D – Nominal pipe diameter

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	3
CULVERT AND SEWER SAFETY SLOPE END TREATMENT CONNECTION DETAILS			
			OPSD 801.042




SIDE ELEVATION FOR CROSS DRAINAGE STRUCTURE




FRONT VIEW


CIRCULAR SMOOTH WALLED PIPE



SIDE ELEVATION OF PARALLEL DRAINAGE STRUCTURE




DETAIL A



TRANSVERSE BARS LONGITUDINAL BAR

DETAIL OF SAFETY BARS



FRONT VIEW

ARCHED PIPE

NOTES:

1 Number of bars required will vary depending on the length of the end section. Bar No.1 shall be located 150mm above flow line.

A This OPSD shall be read in conjunction with OPSD 801.040, 801.041, and 801.042.

B Toe plate extensions shall be the same thickness and material as end section. Dimensions shall be overall width less 150mm by 200mm high.


C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2017 | Rev 3

CULVERT AND SEWER SAFETY SLOPE END TREATMENT INSTALLATION DETAILS

OPSD 801.043



LEGEND:

D – Inside diameter

NOTES:

1 Height of fill is measured from the finished surface to top of pipe.
2 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.
3 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.
4 Condition of excavation is symmetrical about centreline of pipe.

A Granular material placed in the haunch area shall be compacted prior to placing and compacting the remainder of the embedment material.

B Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.

C All dimensions are in metres unless otherwise shown.


CLEARANCE TABLE	
Pipe Inside Diameter mm	Clearance mm
900 or less	300
Over 900	500

ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2014 | Rev 3

FLEXIBLE PIPE EMBEDMENT AND BACKFILL EARTH EXCAVATION

OPSD 802.010



ORIGINAL ROCK < 1200mm ABOVE TRENCH BOTTOM

ORIGINAL ROCK ≥ 1200mm ABOVE TRENCH BOTTOM

NOTES:

1 Height of fill is measured from the finished surface to top of pipe.
2 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.
3 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.
4 Condition of excavation is symmetrical about centreline of pipe.
5 Embedment material shall be wrapped in non–woven geotextile when specified.

A Granular material placed in the haunch area shall be compacted prior to placing and compacting the remainder of the embedment material.
B Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.
C Fractured rock shall be treated as Type 1 soil.
D All dimensions are in metres unless otherwise shown.

LEGEND:

D – Inside diameter
* – Type 1 or 2 soil
** – Type 3 soil
*** – Type 4 soil


CLEARANCE TABLE	
Pipe Inside Diameter mm	Clearance mm
900 or less	300
Over 900	500

ONTARIO PROVINCIAL STANDARD DRAWING

FLEXIBLE PIPE EMBEDMENT AND BACKFILL ROCK EXCAVATION

Nov 2014 | Rev 3

OPSD 802.013



PIPE INVERT ABOVE ORIGINAL GROUND

PIPE INVERT AT OR BELOW ORIGINAL GROUND

PIPE EMBEDMENT WITH ROCK FILL UNDER AND OVER THE PIPE

LEGEND:

D – Inside diameter

NOTES:

1 Height of fill is measured from the finished surface to top of pipe.
2 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.
3 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.
4 Embedment material shall be wrapped in non–woven geotextile when specified.

CLEARANCE TABLE	
Pipe Inside Diameter mm	Clearance mm
900 or less	300
Over 900	500

A Granular material placed in the haunch area shall be compacted prior to placing and compacting the remainder of the embedment material.

B All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING


FLEXIBLE PIPE EMBEDMENT IN EMBANKMENT ORIGINAL GROUND: EARTH OR ROCK

Nov 2014 | Rev 3

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL ·

OPSD 802.014





LEGEND:

S – Span of pipe arch

NOTES:

1 Height of fill is measured from the finished surface to top of pipe. Height of fill over pipe shall be according to OPSD 805.020.

2 For width $0.75S$, granular material shall be uncompacted for its full depth and fine graded to shape of bottom of the pipe arch.

3 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.

4 Condition of excavation is symmetrical about centreline of pipe.

A Granular material placed in the haunch area, other than the area included in Note 2, shall be compacted prior to placing and compacting the remainder of the embedment material.

B Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.

C All dimensions are in metres unless otherwise shown.

CLEARANCE TABLE	
Pipe Span mm	Clearance mm
900 or less	300
Over 900	500


ONTARIO PROVINCIAL STANDARD DRAWING

FLEXIBLE PIPE ARCH EMBEDMENT AND BACKFILL EARTH EXCAVATION

Nov 2015 | Rev 3

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 802.020



ORIGINAL ROCK < 1200mm ABOVE TRENCH BOTTOM

ORIGINAL ROCK ≥ 1200mm ABOVE TRENCH BOTTOM

NOTES:

1 Height of fill is measured from the finished surface to top of pipe. Height of fill over pipe shall be according to OPSD 805.020.
2 For width 0.75*S*, granular material shall be uncompacted for its full depth and fine graded to shape of bottom of the pipe arch.
3 Pipe culvert frost treatment shall be according OPSD 803.030 and 803.031.
4 Condition of excavation is symmetrical about centreline of pipe.
5 Embedment material shall be wrapped in non–woven geotextile when specified.

A Granular material placed in the haunch area, other than the area included in Note 2, shall be compacted prior to placing and compacting the remainder of the embedment material.
B Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.
C Fractured rock shall be treated as Type 1 soil.
D All dimensions are in metres unless otherwise shown.

LEGEND:

S – Span of pipe arch
* – Type 1 or 2 soil
** – Type 3 soil
*** – Type 4 soil


CLEARANCE TABLE	
Pipe Span mm	Clearance mm
900 or less	300
Over 900	500

ONTARIO PROVINCIAL STANDARD DRAWING

FLEXIBLE PIPE ARCH EMBEDMENT AND BACKFILL ROCK EXCAVATION

Nov 2015 | Rev 3

OPSD 802.023



PIPE EMBEDMENT
WITH ROCK FILL UNDER AND OVER THE PIPE

LEGEND:

S – Span of pipe arch

NOTES:

1 Height of fill is measured from the finished surface to top of pipe. Height of fill over pipe shall be according to OPSD 805.020.

2 For width 0.75S, granular material shall be uncompacted for its full depth and fine graded to shape of bottom of the pipe arch.

3 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.

4 Embedment material shall be wrapped in non–woven geotextile when specified.

A Granular material placed in the haunch area, other than the area included in Note 2, shall be compacted prior to placing and compacting the remainder of the embedment material.

B All dimensions are in metres unless otherwise shown.

CLEARANCE TABLE	
Pipe Span mm	Clearance mm
900 or less	300
Over 900	500


ONTARIO PROVINCIAL STANDARD DRAWING

FLEXIBLE PIPE ARCH EMBEDMENT IN EMBANKMENT ORIGINAL GROUND: EARTH OR ROCK

Nov 2015 | Rev 3

ONTARIO STANDARDS – MUNICIPAL – PROVINCIAL

OPSD 802.024



CLASS B BEDDING

CLASS C BEDDING

NOTES:

1 Height of fill is measured from the finished surface to top of pipe.
2 The minimum bedding depth below the pipe shall be 0.15*D*. In no case shall this dimension be less than 150mm or greater than 300mm.
3 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.
4 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.
5 Condition of excavation is symmetrical about centreline of pipe.

A Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.

B All dimensions are in metres unless otherwise shown.

LEGEND:

D – Inside diameter
OD – Outside diameter

CLEARANCE TABLE	
Pipe Inside Diameter mm	Clearance mm
900 or less	300
Over 900	500


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2015 | Rev 3

RIGID PIPE BEDDING, COVER, AND BACKFILL TYPE 1 OR 2 SOIL – EARTH EXCAVATION

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL

OPSD 802.030



NOTES:

1 Height of fill is measured from the finished surface to top of pipe.
2 The minimum bedding depth below the pipe shall be 0.15*D*. In no case shall this dimension be less than 150mm or greater than 300mm.
3 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.
4 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.
5 Condition of excavation is symmetrical about centreline of pipe.
A Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.
B All dimensions are in metres unless otherwise shown.

LEGEND:

D – Inside diameter
OD – Outside diameter

CLEARANCE TABLE	
Pipe Inside Diameter mm	Clearance mm
900 or less	300
Over 900	500


ONTARIO PROVINCIAL STANDARD DRAWING

RIGID PIPE BEDDING, COVER, AND BACKFILL TYPE 3 SOIL – EARTH EXCAVATION


Nov 2015 | Rev 3

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL

OPSD 802.031



CLASS B BEDDING



CLASS C BEDDING

CLEARANCE TABLE	
Pipe Inside Diameter mm	Clearance mm
900 or less	300
Over 900	500

LEGEND:

D – Inside diameter

OD – Outside diameter

NOTES:

1 Height of fill is measured from the finished surface to top of pipe.

2 The minimum bedding depth below the pipe shall be 0.15*D*. In no case shall this dimension be less than 150mm or greater than 300mm.

3 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.


4 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.

5 Condition of excavation is symmetrical about centreline of pipe.

A Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.

B All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	3
RIGID PIPE BEDDING, COVER, AND BACKFILL TYPE 4 SOIL – EARTH EXCAVATION			
	OPSD 802.032		



NOTES:

1 Height of fill is measured from the finished surface to top of pipe.
2 The minimum bedding depth below the pipe shall be 0.25*D*. In no case shall this dimension be less than 150mm or greater than 300mm.
3 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.
4 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.
5 Condition of excavation is symmetrical about centreline of pipe.
6 Embedment material shall be wrapped in non–woven geotextile when specified.

A Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.
B Fractured rock shall be treated as Type 1 soil.
C All dimensions are in metres unless otherwise shown.

LEGEND:

D – Inside diameter
OD – Outside diameter
* – Type 1 or 2 soil
** – Type 3 soil
*** – Type 4 soil

CLEARANCE TABLE	
Pipe Inside Diameter mm	Clearance mm
900 or less	300
Over 900	500


ONTARIO PROVINCIAL STANDARD DRAWING


RIGID PIPE BEDDING, COVER, AND BACKFILL ROCK EXCAVATION

Nov 2015 | Rev 3

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL

OPSD 802.033





PIPE BEDDING AND COVER
WITH ROCK FILL UNDER AND OVER THE PIPE

LEGEND:

D – Inside diameter
OD – Outside diameter

NOTES:

1 Height of fill is measured from the finished surface to top of pipe.
2 The minimum bedding depth below the pipe shall be 0.15*D*, except on a rock foundation where the minimum bedding depth shall be 0.25*D*. In no case shall the minimum dimension be less than 150mm or greater than 300mm.
3 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.
4 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.
5 Condition of excavation is symmetrical about centreline of pipe.
6 Bedding and cover material shall be wrapped in non–woven geotextile when specified.

A All dimensions are in metres unless otherwise shown.

CLEARANCE TABLE	
Pipe Inside Diameter mm	Clearance mm
900 or less	300
Over 900	500


ONTARIO PROVINCIAL STANDARD DRAWING

RIGID PIPE BEDDING AND COVER IN EMBANKMENT ORIGINAL GROUND: EARTH OR ROCK

Nov 2015 | Rev 3

ONTARIO STANDARD MUNICIPAL–PROVINCIAL O P S

OPSD 802.034



NOTES:

1 Height of fill is measured from the finished surface to top of pipe.
2 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.
3 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.
4 Condition of excavation is symmetrical about centreline of pipe.


A Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.

B All dimensions are in metres unless otherwise shown.

LEGEND:

B_c = Outside horizontal span
B_r = Outside vertical rise

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	3
HORIZONTAL ELLIPTICAL RIGID PIPE BEDDING, COVER, AND BACKFILL TYPE 1 OR 2 SOIL – EARTH EXCAVATION			
	OPSD 802.050		



NOTES:

1 Height of fill is measured from the finished surface to top of pipe.
2 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.
3 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.
4 Condition of excavation is symmetrical about centreline of pipe.

A Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.

B All dimensions are in metres unless otherwise shown.

LEGEND:


B_c = Outside horizontal span
B_r = Outside vertical rise

ONTARIO PROVINCIAL STANDARD DRAWING


HORIZONTAL ELLIPTICAL RIGID PIPE BEDDING, COVER, AND BACKFILL TYPE 3 SOIL – EARTH EXCAVATION

Nov 2015 | Rev 3

OPSD 802.051



CLASS B BEDDING



CLASS C BEDDING

LEGEND:

B_c = Outside horizontal span

B_r = Outside vertical rise

NOTES:

1 Height of fill is measured from the finished surface to top of pipe.

2 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.

3 Pipe culvert frost treatment shal be according to OPSD 803.030 and 803.031.

4 Condition of excavation is symmetrical about centreline of pipe.

A Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.

B All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

HORIZONTAL ELLIPTICAL RIGID PIPE BEDDING, COVER, AND BACKFILL TYPE 4 SOIL – EARTH EXCAVATION

Nov 2015 | Rev 3

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL

OPSD 802.052



CLASS B BEDDING **CLASS C BEDDING**

NOTES:

1 Height of fill is measured from the finished surface to top of pipe.
2 The minimum bedding depth below the pipe shall be $0.25B_c$. In no case shall this dimension be less than 150mm or greater than 300mm.
3 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.
4 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.
5 Condition of excavation is symmetrical about centreline of pipe.
6 Embedment material shall be wrapped in non–woven geotextile when specified.

A Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.
B Fractured rock shall be treated as Type 1 soil.
C All dimensions are in metres unless otherwise shown.


LEGEND:


B_c = Outside horizontal span
B_r = Outside vertical rise
* – Type 1 or 2 soil
** – Type 3 soil
*** – Type 4 soil

ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2015 | Rev 3

HORIZONTAL ELLIPTICAL RIGID PIPE BEDDING, COVER, AND BACKFILL ROCK EXCAVATION

OPSD 802.053





PIPE BEDDING AND COVER WITH ROCK FILL UNDER AND OVER THE PIPE

LEGEND:

B_c = Outside horizontal span

B_r = Outside vertical rise

NOTES:

1 Height of fill is measured from the finished surface to top of pipe.

2 The pipe bed shall be compacted and shaped to receive the bottom of the pipe.

3 Pipe culvert frost treatment shall be according to OPSD 803.030 and 803.031.

4 Condition of excavation is symmetrical about centreline of pipe.

5 Bedding and cover material shall be wrapped in non–woven geotextile when specified.

A All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2015 | Rev 3


HORIZONTAL ELLIPTICAL RIGID PIPE BEDDING AND COVER IN EMBANKMENT ORIGINAL GROUND: EARTH OR ROCK

ONTARIO STANDARDS · MUNICIPAL–PROVINCIAL · O P S

OPSD 802.054



PLAN




SECTION A–A

NOTES:


1 Key trench plug into undisturbed trench soil into sides and bottom (minimum 300mm).
A Unshrinkable fill or impervious clay shall be used as trench plug material.
B Trench plug shall be located so that no pipe joints are within the plug material.
C All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	3
TRENCH PLUG			
	OPSD 802.095		

FROST PENETRATION LINE AT OR ABOVE TOP OF CULVERT




LONGITUDINAL SECTION




SECTION A–A

FROST PENETRATION LINE BELOW TOP OF CULVERT



LONGITUDINAL SECTION



SECTION B–B

LEGEND:

d = depth of roadbed granular
k = depth of frost treatment below profile grade
f = depth of frost penetration below profile grade

NOTES:

1 Condition of frost treatment symmetrical about centreline of culvert.


A Bedding, levelling, and cover material shall be granular as specified.

B The depth of roadbed granular shall be 600mm minimum.

C The maximum depth of frost treatment shall be bottom of box frame or top of footing.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	3
BACKFILL AND COVER FOR CONCRETE CULVERTS WITH SPANS LESS THAN OR EQUAL TO 3.0M			
	OPSD 803.010		



FROST TREATMENT
RIGID AND FLEXIBLE PIPE


NOTES:

1 Pipe embedment or bedding, cover, and backfill shall be according to:
   a) Flexible OPSD 802.010, 802.013, 802.014, 802.020, 802.023, and 802.024.
   b) Rigid – OPSD 802.030, 802.031, 802.032, 802.033, 802.034, 802.050, 802.051, 802.052, 802.053, and 802.054.
2 Frost tapers shall start at bedding grade.

LEGEND:

d –depth of roadbed granular
k –depth of frost treatment below profile grade
f –depth of frost penetration below profile grade

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	3
FROST TREATMENT – PIPE CULVERTS FROST PENETRATION LINE BELOW BEDDING GRADE			
	OPSD 803.030		



FROST TREATMENT
RIGID AND FLEXIBLE PIPE

NOTES:

1 Pipe embedment or bedding, cover, and backfill shall be according to:
   a) Flexible OPSD 802.010, 802.013, 802.014, 802.020, 802.023, and 802.024.
   b) Rigid – OPSD 802.030, 802.031, 802.032, 802.033, 802.034, 802.050, 802.051, 802.052, 802.053, and 802.054.

2 Condition of frost treatment symmetrical about centreline of pipe.


3 Frost tapers shall start at the intersection of the 1H:1V or 3H:1V slope and the frost penetration line.

A Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.


LEGEND:

d – depth of roadbed granular
k – depth of frost treatment below profile grade
f – depth of frost penetration below profile grade
* – Type 3 soil
** – Type 4 soil

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	4
FROST TREATMENT – PIPE CULVERTS FROST PENETRATION LINE BETWEEN TOP OF PIPE AND BEDDING GRADE			
	OPSD 803.031		



FRONT ELEVATION



SECTION A–A

LEGEND:

OD – Outside diameter of pipe

NOTES:

A This OPSD to be read in conjunction with OPSD 3940.150.


B If a steel grate is required, refer to OPSD 804.05.

C Class of concrete: 30MPa.


D Cover to reinforcing bars 70mm ± 20mm.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	2
CONCRETE HEADWALL FOR PIPE LESS THAN 900mm DIAMETER			
	OPSD 804.030		




PLAN




SECTION A–A

PIPE DIA	ENDWALL DIMENSIONS							
	A	B	C	D	E	F	G	H
600	1050	2400	2725	1400	300	75	1525	2350
675	1125	2400	2725	1475	300	75	1600	2425
750	1200	2400	2725	1550	300	75	1675	2500
825	1275	2400	2725	1625	300	75	1755	2575
900	1350	2400	2725	1700	300	75	1825	2650
975	1425	2400	2725	1775	375	150	1975	2725
1050	1500	3000	3400	1850	375	150	2050	3100
1200	1650	3000	3400	2000	375	150	2200	3250
1350	1800	3000	3400	2150	375	150	2350	3400
1500	1950	3000	3400	2300	375	150	2500	3550
1650	2100	3000	3400	2450	375	150	2650	3700
1800	2250	3000	3400	2600	375	150	2800	3850
2400	3000	3000	3400	3350	375	150	3550	4600



FRONT VIEW



SIDE VIEW

NOTES:

A This OPSD to be read in conjunction with OPSD 3940.150.

B Class of concrete: 30MPa.

C Cover to reinforcing bars: 75mm ±20mm.

D Granular backfill to be placed to 300mm min thickness on all sides.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2017 | Rev 1


CONCRETE HEADWALL

FOR SEWER OR CULVERT PIPE OUTLET

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 804.040









TABLE 1 – NUMBER OF RODS IN FRAME	
PIPE DIA	No of RODS
450	1
525	1
600	2
675	3
750	3
825	4
900	4
975	5
1050	6
1200	7


PIPE DIA up to 1200mm

TABLE 2 – NUMBER OF FIXED RODS IN UPPER SECTION	
PIPE DIA	No of RODS
1350	3
1500	4
1650	5
1800	6
1950	7
2100	8
2250	9
2400	10


PIPE DIA 1350 to 2400mm




BOLT–ON ASSEMBLY DETAIL



ASSEMBLY





CAST–IN HINGE STRAP ASSEMBLY DETAILS

NOTES:

1 Grates shall be secured by either a bolt and nut or a locking device as specified.

A Metal surfaces shall be either painted with 2 coats of self priming abrasion resistant immersion grade epoxy or hot dip galvanized as specified.

B Frame, hinge strap, mounting bracket, and steel rods shall be medium grade steel.

C All welding shall be according to CSA W59.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	3
GRATING FOR CONCRETE ENDWALL			
			OPSD 804.050

Pipe Type	Corrugation Profile	Diameter	Min. Height of Fill	Area m^2	Metal Thickness									
					Corrugated Steel Pipe					Structural Plate				
					1.6	2.0	2.8	3.5	4.2	3.0	4.0	5.0	6.0	7.0
					Maximum Height of Fill Over Pipe m									
Round Corrugated Steel Pipe (Note 1)	68 x 13mm	300	300	0.07	61.3	79.7								
		400	300	0.13	45.9	59.7								
		450	300	0.16	40.8	53.1								
		500	300	0.20	36.8	47.8	69.3							
		600	300	0.28	30.6	39.8	57.8							
		700	300	0.38	26.2	34.1	49.5							
		750	300	0.44	24.5	31.9	46.5							
		800	300	0.50	23.0	29.9	43.3							
		900	300	0.64	20.4	26.5	38.5	48.9						
		1000	300	0.79	18.4	23.9	34.7	44.0	53.6					
		1200	300	1.13		19.9	28.9	36.7	44.7					
		1400	300	1.54			23.8	30.3	37.0					
		1500	300	1.77			21.3	27.2	33.2					
		1600	300	2.01			19.1	24.4	29.8					
		1800	300	2.54				19.5	23.9					
		2000	350	3.14					18.9					
	125 x 25mm	1200	300	1.13		20.4	29.6	37.6	45.8					
		1400	300	1.54		17.5	25.4	32.2	39.2					
		1500	300	1.77		16.3	23.7	30.1	36.6					
		1600	300	2.01		15.3	22.2	28.2	34.3					
		1800	300	2.54		13.6	19.7	25.0	30.5					
		2000	350	3.14		12.2	17.7	22.5	27.5					
		2200	400	3.80		11.1	16.1	20.5	25.0					
		2400	400	4.52		10.0	14.8	18.8	22.9					
		2700	450	5.73			13.1	16.7	20.3					
		3000	500	7.07			11.3	14.4	17.5					
Round Structural Plate Corrugated Steel Pipe	152 x 51mm	1500	300	1.77						26.2	39.1	49.8	60.5	70.6
		1660	300	2.16						23.7	35.3	45.0	54.6	63.8
		1810	350	2.58						21.7	32.4	41.3	50.1	58.5
		1970	350	3.04						19.9	29.8	37.9	46.0	53.8
		2120	400	3.54						18.5	27.7	35.3	42.8	50.0
		2280	400	4.07						17.2	25.7	32.8	39.8	46.4
		2430	450	4.65						16.1	24.1	30.8	37.3	43.6
		2590	450	5.26						15.1	22.6	28.8	35.0	40.9
		2740	500	5.91						14.3	21.4	27.3	33.1	38.6

NOTES:

1 Refer to manufacturer for non–standard sizes. For non–standard sizes, use the next larger standard diameter for estimating maximum height of fill over pipe.

A The table based on backfill density of 2243 kg/m^3.


B This OPSD shall be read in conjunction with OPSD 802.010, 802.013, and 802.014.

C Sizes greater than 3000mm are available subject to design by Canadian Highway Bridge Design Code (CHBDC CSA 56).

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
HEIGHT OF FILL TABLE ROUND CORRUGATED STEEL PIPE AND STRUCTURAL PLATE CORRUGATED STEEL PIPE	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 805.010		

Corrugation Profile	Inside Span	Inside Rise	Area m^2	Equivalent Round	Minimum Height of Fill	Metal Thickness									
						Corrugated Steel Pipe					Structural Plate				
						1.6	2.0	2.8	3.5	4.2	3.0	4.0	5.0	6.0	7.0
						Maximum Height of Fill Over Pipe m Corner Bearing Pressure Limited to 200 kPa (Note 1)									
68 x 13 mm (Note 1)	560	420	0.19	500	300	4.1									
	680	500	0.27	600	300	4.2									
	800	580	0.37	700	300	4.1									
	910	660	0.48	800	300	4.1									
	1030	740	0.61	900	300	4.0									
	1150	820	0.74	1000	300		4.0								
	1390	970	1.06	1200	300		3.9								
	1630	1120	1.44	1400	300			3.9							
	1880	1260	1.87	1600	350				3.8						
	2130	1400	2.36	1800	400				3.7						
125 x 25 mm (Note 1)	1330	1030	1.09	1200	300			4.4							
	1550	1200	1.48	1400	300			4.4							
	1780	1360	1.93	1600	300			4.4							
	2010	1530	2.44	1800	350			4.3							
	2230	1700	2.97	2000	400			4.6							
	2500	1830	3.44	2200	450			4.5							
	2800	1950	4.27	2400	500			4.4							
152 x 51 mm (Note 2)	2060	1520	2.49		350						5.1				
	2240	1630	2.90		400						4.8				
	2440	1750	3.36		450						4.6				
	2590	1880	3.87		450						4.6				
	2690	2080	4.49		450						5.0				



NOTES:

1 For heights of fill approaching the above maximums for 200kPa corner bearing pressure, consideration should be given to round pipes since they reduce the load being applied to the foundation.

A The table based on backfill density of 2243 kg/m^3.


B This OPSD shall be read in conjunction with OPSD 802.020, 802.023, and 802.024.

C Sizes greater than 3000mm are available subject to design by Canadian Highway Bridge Design Code (CHBDC CSA S6).


D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev 3
HEIGHT OF FILL TABLE CORRUGATED STEEL PIPE–ARCH AND STRUCTURAL PLATE CORRUGATED STEEL PIPE–ARCH		OPSD 805.020

Diameter	Area m^2	Minimum Height of Fill	Metal Thickness		
			1.6	2.0	2.8
			Maximum Height of Fill Over Pipe m		
450	0.16	300	22.7	33.6	
525	0.22	300	19.4	28.8	50.6
600	0.28	300	17.0	25.2	44.3
750	0.44	300	13.6	20.2	35.4
900	0.64	300	11.3	16.8	29.5
1050	0.87	300	9.7	14.4	25.3
1200	1.13	300	8.5 (Notes 1 and 2)	12.6	22.1
1350	1.43	350	7.5 (Notes 1 and 2)	11.2	19.7
1500	1.77	400	6.8 (Notes 1 and 2)	10.1 (Notes 1 and 2)	17.7
1650	2.14	450		9.1 (Notes 1 and 2)	16.1
1800	2.54	450		8.4 (Notes 1 and 2)	14.7
2100	3.46	550			12.6 (Notes 1 and 2)
2400	4.52	600			11.0 (Notes 1 and 2)



SPIRAL RIB STEEL PIPE PROFILE
TYPE I



SPIRAL RIB STEEL PIPE PROFILE
TYPE II

NOTES:

1 Installation shall be in trench–like conditions as shown for Type 1 and 2 soil in OPSD 802.010 or as shown in OPSD 802.013, provided the rock trench has a minimum depth of 0.75 times the diameter of the pipe.

2 Compaction of embedment material shall be obtained by hand, walk behind equipment, or by saturation and vibration in order to limit the compaction effort while maintaining pipe shape.


A The table based on backfill density of 2243 kg/m^3.

B This OPSD shall be read in conjunction with OPSD 802.010, 802.013, and 802.014.


C Refer to manufacturer for non–standard sizes. For non–standard sizes, use the next larger standard diameter for estimating maximum height of fill over pipe.

D All dimensions are in millimetres unless otherwise shown.


Span	Rise	Equivalent Diameter	Area m^2	Minimum Height of Fill	Metal Thickness		
					1.6	2.0	2.8
					Maximum Height of Fill Over Pipe m Corner Bearing Pressure Limited to 200 kPa (Note 3)		
500	410	450	0.15	300	4.0		
580	490	525	0.21	300	5.2		
680	540	600	0.27	300	5.2		
830	660	750	0.43	300	5.2		
1010	790	900	0.62	300	4.4		
1160	920	1050	0.85	300	5.1		
1340	1050	1200	1.12	300		4.4	
1520	1200	1350	1.44	350		5.3 (Notes 1 and 2)	5.3
1670	1300	1500	1.79	400		5.1 (Notes 1 and 2)	5.1
1850	1400	1650	2.15	450		4.7 (Notes 1 and 2)	4.7



SPIRAL RIB STEEL PIPE PROFILE
TYPE I



SPIRAL RIB STEEL PIPE PROFILE
TYPE II



NOTES:

1 Installation shall be in trench–like conditions as shown for Type 1 and 2 soil in OPSD 802.020 or as shown in OPSD 802.023, provided the rock trench has a minimum depth of 0.75 times the diameter of the pipe.

2 Compaction of embedment material shall be obtained by hand, walk behind equipment, or by saturation and vibration in order to limit the compaction effort while maintaining pipe shape.

3 For heights of fill approaching the above maximums for 200kPa corner bearing pressure, consideration should be given to round pipes since they reduce the load being applied to the foundation.

A The table based on backfill density of 2243 kg/m^3.

B This OPSD shall be read in conjunction with OPSD 802.020, 802.023, and 802.024.

C Refer to manufacturer for non–standard sizes. For non–standard sizes, use the next larger standard diameter for estimating maximum height of fill over pipe.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2018 | Rev 3

HEIGHT OF FILL TABLE

SPIRAL RIB PIPE–ARCH

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • OPS

OPSD 805.040

PIPE DIA mm	TRENCH WIDTH	MAXIMUM HEIGHT OF FILL				MINIMUM HEIGHT OF FILL
		320 kPa		RSC 160		All Pipe Classes
		Granular A	Granular B (Type I and II)	Granular A	Granular B (Type I and II)	Granular B (Type I and II)
100	0.5	9.8	6.7	–	–	0.3
150	0.6	9.8	7.6	–	–	0.3
200	0.7	8.5	5.8	–	–	0.3
250	0.7	10.1	6.7	–	–	0.3
300	0.8	11.0	7.3	–	–	0.3
375	0.9	9.8	6.4	–	–	0.3
450	1.0	10.1	6.7	–	–	0.3
525	1.1	9.1	6.1	–	–	0.3
600	1.2	10.7	7.0	–	–	0.3
750	1.4	9.8	6.4	–	–	0.3
900	1.6	8.8	6.1	–	–	0.3
1050	1.8	–	–	6.1	4.3	0.3
1200	2.0	–	–	6.4	4.6	0.3
1500	2.4	–	–	6.4	4.3	0.6

NOTES:

A The table applies to dual wall corrugated polyethylene gravity sewer pipe according to CSA B182.6 and CSA B182.8.

B Pipe diameters 1050 to 1500mm are listed with a constant RSC 160 value for convenience. Minimum pipe stiffness values are listed in Table 3 of CSA B182.8.

C Trench width is based on Class I compacted material for Granular A and Class II compacted material to 95% of the maximum dry density for Granular B.

D The table based on backfill density of 2243 kg/m^3.

E The table presumes groundwater is at or below the springline of the pipe.

F Minimum height of fill over the pipe is measured from bottom of flexible pavement or top of rigid pavement.

G Maximum height of fill is measured from the finished surface to top of pipe.

H This OPSD shall be read in conjunction with OPSD 802.010, 802.013 and 802.014.

I For height of fill and/or pipe sizes greater than shown, or for other design conditions, the values shall be calculated from first principles.

J All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

HEIGHT OF FILL TABLE

DUAL WALL CORRUGATED POLYETHYLENE GRAVITY SEWER PIPE – 320 kPa and RSC 160

Nov 2018 | Rev 3

OPSD 806.020

PIPE NOMINAL SIZE	PIPE INSIDE DIAMETER	AREA	RSC 160			RSC 250		
			MINIMUM HEIGHT	GRANULAR 'A' MAXIMUM HEIGHT	GRANULAR 'B' MAXIMUM HEIGHT	MINIMUM HEIGHT	GRANULAR 'A' MAXIMUM HEIGHT	GRANULAR 'B' MAXIMUM HEIGHT
mm	mm	m^2	m	m	m	m	m	m
460	455	0.17	0.6	18.3	14.6	–	–	–
500	495	0.20	0.6	18.3	14.0	–	–	–
530	535	0.22	0.6	18.3	13.4	–	–	–
610	610	0.29	0.6	18.3	12.2	–	–	–
690	685	0.37	0.6	18.0	11.3	–	–	–
760	760	0.45	0.6	16.5	10.4	–	–	–
840	840	0.55	0.6	16.2	10.1	–	–	–
910	910	0.65	0.6	14.9	9.4	0.5	15.2	9.8
1020	1020	0.82	0.6	14.3	9.1	0.5	14.9	9.4
1070	1070	0.90	0.6	14.0	8.8	0.5	14.9	9.4
1220	1220	1.17	0.6	13.4	8.5	0.5	14.3	9.1
1370	1370	1.47	0.6	13.4	8.5	0.5	14.0	8.8
1520	1520	1.81	0.6	12.8	8.2	0.5	14.0	8.8
1680	1680	2.22	0.6	12.8	8.2	0.6	13.7	8.5
1830	1830	2.63	0.6	12.8	7.9	0.6	13.4	8.5
1980	1980	3.08	0.8	12.5	7.9	0.6	13.4	8.2
2130	2130	3.56	0.8	12.5	7.9	0.6	13.1	8.2
2290	2290	4.12	0.8	12.5	7.9	0.6	13.1	8.2
2440	2440	4.68	0.8	11.9	7.6	0.6	12.8	7.9
2590	2590	5.27	0.8	11.9	7.6	0.6	12.8	7.9
2740	2740	5.90	0.8	11.9	7.6	0.6	12.5	7.9
2900	2900	6.60	0.8	11.9	7.3	0.6	12.5	7.9

NOTES:

A The table applies to closed profile wall polyethylene pipe manufactured according to ASTM F894.
B The table presumes groundwater is at or below the springline of the pipe.
C The table based on backfill density of 2243 kg/m^3.
D Installation shall be in accordance with OPSD 802.010 requirements.
E Height of fill is measured from the finished surface to top of pipe.
F All dimensions are in meters unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

HEIGHT OF FILL TABLE

CLOSED PROFILE WALL POLYETHYLENE PIPE
RSC 160 AND RSC 250

Nov 2018 | Rev 3

ONTARIO STANDARDS • MUNICIPAL - PROVINCIAL •

OPSD 806.021

PIPE DIA mm	TRENCH WIDTH	MAXIMUM HEIGHT OF FILL				MINIMUM HEIGHT OF FILL
		RSC 100		RSC 160		All Pipe Classes
		Granular A	Granular B (Type I and II)	Granular A	Granular B (Type I and II)	Granular B (Type I and II)
300	0.8	9.1	6.1	–	–	0.3
375	0.9	9.8	6.7	–	–	0.3
450	1.0	9.5	6.4	–	–	0.3
600	1.2	–	–	7.3	5.2	0.3
750	1.4	–	–	7.3	5.2	0.3
900	1.6	–	–	6.7	4.6	0.3
1050	1.8	–	–	6.1	4.3	0.3
1200	2.0	–	–	6.4	4.6	0.3
1500	2.4	–	–	6.4	4.3	0.6

NOTES:

A The table applies to dual wall corrugated polyethylene gravity sewer pipe according to AASHTO M294 Type S.

B Trench width is based on Class I compacted material for Granular A and Class II compacted material to 95% of the maximum dry density for Granular B.

C The table based on backfill density of 2243 kg/m^3.

D The table presumes groundwater is at or below the springline of the pipe.

E Minimum height of fill over the pipe shall be measured from the bottom of flexible pavement or the top of rigid pavement.

F Maximum height of fill is measured from the finished surface to top of pipe.

G This OPSD shall be read in conjunction with OPSD 802.010, 802.013 and 802.014.

H For height of fill and/or pipe sizes greater than shown, or for other design conditions, the values shall be calculated from first principles.

I All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2018 | Rev 3

HEIGHT OF FILL TABLE
DUAL WALL CORRUGATED POLYETHYLENE GRAVITY SEWER PIPE RSC 100 AND RSC 160

ONTARIO STANDARDS • MUNICIPAL – PROVINCIALS •

OPSD 806.022

PIPE DIA mm	TRENCH WIDTH	MAXIMUM HEIGHT OF FILL		MINIMUM HEIGHT OF FILL
		320 kPa		320 kPa
		Granular A	Granular B (Type I and II)	Granular B (Type I and II)
300	0.8	10.4	7.3	0.3
375	0.9	10.7	7.3	0.3
450	1.0	11.3	7.6	0.3
525	1.1	11.9	7.9	0.3
600	1.2	9.5	6.7	0.3
750	1.4	7.9	5.5	0.3
900	1.6	7.6	5.5	0.3
1050	1.8	8.2	5.8	0.3
1200	2.0	8.5	5.8	0.3
1500	2.4	7.9	5.5	0.6

NOTES:

A The table applies to dual wall corrugated polypropylene gravity sewer pipe, 300 to 750mm, and triple wall corrugated polypropylene gravity sewer pipe, 750 to 1,500 mm according to CSA 8182.13.

B Trench width is based on Class I compacted material for Granular A and Class II compacted material to 95% of the maximum dry density for Granular B, Type I and Type II.

C The table based on backfill density of 2243 kg/m^3.

D The table presumes groundwater is at or below the springline of the pipe.

E Minimum height of fill over the pipe is measured from the bottom of flexible pavement or the top of rigid pavement.

F Maximum height of fill is measured from the finished surface to top of pipe.

G This OPSD shall be read in conjunction with OPSD 802.010, 802.013 and 802.014.

H For height of fill and/or pipe sizes greater than shown, or for other design conditions, values shall be be calculated from first principles.

I All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2018 | Rev 1

HEIGHT OF FILL TABLE
DUAL AND TRIPLE WALL CORRUGATED POLYPROPYLENE GRAVITY SEWER PIPE 320 kPa

OPSD 806.030

PIPE DIA mm	AREA m^2	TRENCH WIDTH	MAXIMUM HEIGHT OF FILL					
			210 kPa Stiffness PSM DR 41		320 kPa Stiffness PSM DR 35		625 kPa Stiffness PSM DR 28	
			Trench	Embankment	Trench	Embankment	Trench	Embankment
100	0.008	0.40	10.4	6.2	10.8	6.5	11.9	7.0
135	0.014	0.54	10.4	6.2	10.8	6.5	11.9	7.0
150	0.020	0.95	10.4	6.2	10.8	6.5	11.9	7.0
200	0.030	1.00	10.4	6.2	10.8	6.5	N/A	N/A
250	0.050	1.05	10.4	6.2	10.8	6.5	N/A	N/A
300	0.070	1.10	10.4	6.2	10.8	6.5	N/A	N/A
375	0.110	1.20	10.4	6.2 *	10.8	6.5 *	N/A	N/A
450	0.160	1.25	10.4	6.2 **	10.8	6.5 **	N/A	N/A
525	0.220	1.30	10.4 *	6.2 **	10.8 *	6.5 **	N/A	N/A
600	0.280	1.40	10.4 *	6.2 **	10.8 *	6.5 **	N/A	N/A
675	0.360	1.50	10.4 *	6.2 **	10.8 *	6.5 **	N/A	N/A
750	0.440	1.60	10.4 *	6.2 **	10.8 *	6.5 **	N/A	N/A
900	0.640	1.70	10.4 **	6.2 **	10.8 **	6.5 **	N/A	N/A

NOTES:

1 For installations in Type 4 soil, height of fill shall be calculated from first principles.

2 For installations in Type 3 soil, height of fill shall be calculated from first principles.

A Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.

B Minimum height of fill over top of pipe shall be 300mm or one pipe diameter, whichever is greater.

C The table based on backfill density of 2243 kg/m^3.

D This OPSD shall be read in conjunction with OPSD 802.010 and 802.013.

E Height of fill greater than 12.0m shall be calculated from first principles.

F All dimensions are in metres unless otherwise shown.

LEGEND:

* Note 1
** Note 1 and 2
N/A Not Available

ONTARIO PROVINCIAL STANDARD DRAWING

HEIGHT OF FILL TABLE

POLYVINYL CHLORIDE GRAVITY SEWER PIPE
210, 320, and 625kPa

Nov 2018 | Rev 4

OPSD 806.040

DR	MAXIMUM HEIGHT OF FILL	
	Embankment Condition	Trench Condition
51	6.0	10.0
41	6.2	10.4
32.5	6.6	11.1
26	7.4	12.5
25	7.6	12.8
21	8.9	15.1
18	10.8	18.4
14	17.0	29.3

LEGEND:

$$\text{DR} = \text{Dimension ratio} = \frac{\text{Average outside diameter of the pipe, mm}}{\text{Minimum wall thickness, mm}}$$

NOTES:

A For installation in Type 4 and Type 3 soil, or if E' < 6864kN/m^2, the height of fill shall be calculated from first principles.

B Soil types as defined in the Occupational Health and Safety Act and Regulations for Construction Projects.

C The transition width, width of trench above the pipe when trench condition transitions to embankment condition, shall be calculated from first principles.

D The maximum height of fill is dependent on the DR of the pipe, regardless of the diameter of the pipe.

E Minimum height of fill over top of pipe shall be 300mm or one pipe diameter, whichever is greater.

F This OPSD shall be read in conjunction with OPSD 802.010 and OPSD 802.013.

G All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	2
HEIGHT OF FILL TABLE POLYVINYL CHLORIDE PRESSURE PIPE FOR DIFFERENT DIMENSION RATIOS			
	OPSD 806.060		

PIPE DIA mm	BEDDING CLASS	CONFINED TRENCH				
		HEIGHT OF FILL 0.3 to 0.6m	MAXIMUM HEIGHT OF FILL FOR DEPTHS > 0.6m			
		PIPE CLASS	50-D	65-D	100-D	140-D
300	B	140-D	2.2	3.1	6.7	NL
	C	SD	1.6	2.4	4.3	10.2
375	B	140-D	2.3	3.4	8.3	NL
	C	140-D	1.7	2.5	4.9	15.5
450	B	100-D	2.5	3.6	9.5	NL
	C	140-D	1.8	2.7	5.3	22.6
525	B	100-D	2.6	3.9	10.4	NL
	C	100-D	1.9	2.8	5.6	30.7
600	B	65-D	2.7	4.0	10.8	NL
	C	100-D	2.0	2.9	5.9	30.3
675	B	50-D	2.8	4.1	11.0	NL
	C	65-D	2.0	2.9	6.0	24.6
750	B	50-D	2.8	4.2	10.8	NL
	C	65-D	2.0	3.0	6.1	19.8
825	B	50-D	2.9	4.3	10.7	NL
	C	50-D	2.1	3.0	6.2	17.7
900	B	50-D	2.7	3.7	6.6	12.5
	C	50-D	2.2	2.9	4.9	8.0
975	B	50-D	2.7	3.7	6.7	12.8
	C	50-D	2.2	2.9	4.9	8.2
1050	B	50-D	2.7	3.8	6.8	12.9
	C	50-D	2.3	2.9	5.0	8.3
1200	B	50-D	2.9	3.9	7.0	13.1
	C	50-D	2.4	3.0	5.1	8.4
1350	B	50-D	3.0	4.0	7.3	13.7
	C	50-D	2.5	3.2	5.3	8.8
1500	B	50-D	3.1	4.0	7.2	13.1
	C	50-D	2.6	3.2	5.3	8.7
1650	B	50-D	3.2	4.1	7.3	12.9
	C	50-D	2.6	3.3	5.3	8.6
1800	B	50-D	3.3	4.2	7.3	12.7
	C	50-D	2.7	3.4	5.3	8.6
1950	B	50-D	3.3	4.2	7.3	12.8
	C	50-D	2.7	3.4	5.4	8.7
2100	B	50-D	3.4	4.3	7.3	12.6
	C	50-D	2.7	3.5	5.4	8.6
2250	B	50-D	3.4	4.3	7.3	12.4
	C	50-D	2.8	3.5	5.4	8.6
2400	B	50-D	3.4	4.4	7.1	12.2
	C	50-D	2.3	3.5	5.4	8.5
2550	B	50-D	3.5	4.4	7.2	12.0
	C	50-D	2.8	3.6	5.4	8.4
2700	B	50-D	3.5	4.4	7.0	11.9
	C	50-D	2.8	3.6	5.5	8.3
3000	B	50-D	3.5	4.4	7.1	11.9
	C	50-D	2.8	3.6	5.5	8.3

LEGEND:

SD = Special Design
NL = No Limit

NOTES:

A Height of fill is measured from the finished surface to top of pipe.

B Minimum design height of fill over the top of pipe shall be greater than 600mm. Contact the concrete pipe supplier for special pipe designs 600mm or less.

C For pipe-to-structure connections, the recommended minimum height of fill over the top of pipe shall be 600mm. Refer to OPSS 401.07.10 for minimum height of fill for backfilling and use of heavy equipment.

D The excavation width is based on OPSD 802.030 and is the width of the excavation measured at the top of the pipe.

E Strength designations are pipe Class 50-D, 65-D, 100-D, and 140-D according to CSA A257.2.

F The table is based on backfill density of 2,243 kg/m^3, truck axle loads as per CHBDC Annex A3.4.1.

G For confined trench, the load factor used for the calculation of the variable bedding factor is: Class B bedding=1.9, and Class C bedding=1.5.

H For confined trench, Kμ'=0.165. This represents a sand and gravel soil material in the trench walls, similar to Granular A or Granular B Type II as per OPSS 1010.

I This Fill Height Table was established using assumed design parameters, and should be used for guideline purposes only. The user should verify site specific design requirements for the pipe design.

J Conditions other than those indicated shall be calculated from first principles.

K All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2018 | Rev 4

HEIGHT OF FILL TABLE

REINFORCED CONCRETE PIPE – CONFINED TRENCH
CLASS 50-D, 65-D, 100-D, and 140-D

ONTARIO STANDARDS • MUNICIPAL - PROVINCIAL •

OPSD 807.010

PIPE DIA mm	BEDDING CLASS	POSITIVE PROJECTING EMBANKMENT			
		MAXIMUM HEIGHT OF FILL FOR DEPTHS > 0.6m			
		50–D	65–D	100–D	140–D
300	B	2.2	3.1	4.9	6.9
	C	1.7	2.4	3.9	5.5
375	B	2.4	3.2	5.1	7.2
	C	1.8	2.5	4.1	5.9
450	B	2.5	3.3	5.3	7.4
	C	1.9	2.6	4.2	6.0
525	B	2.5	3.4	5.4	7.6
	C	1.9	2.7	4.3	6.2
600	B	2.6	3.5	5.5	7.7
	C	2.0	2.7	4.4	6.3
675	B	2.6	3.5	5.5	7.8
	C	2.0	2.8	4.5	6.3
750	B	2.6	3.6	5.6	7.9
	C	2.1	2.8	4.5	6.4
825	B	2.7	3.6	5.6	7.9
	C	2.1	2.8	4.6	6.5
900	B	2.7	3.6	5.7	8.0
	C	2.2	2.9	4.6	6.5
975	B	2.7	3.6	5.7	8.1
	C	2.2	2.9	4.6	6.5
1050	B	2.8	3.7	5.7	8.1
	C	2.3	2.9	4.6	6.6
1200	B	2.9	3.7	5.8	8.2
	C	2.4	3.0	4.7	6.3
1350	B	3.0	3.8	6.0	8.4
	C	2.5	3.1	4.8	6.8
1500	B	3.1	3.8	6.0	8.4
	C	2.6	3.2	4.8	6.8
1650	B	3.2	3.9	6.0	8.4
	C	2.6	3.3	4.8	6.8
1800	B	3.3	4.0	6.0	8.5
	C	2.7	3.4	4.9	6.9
1950	B	3.3	4.1	6.0	8.5
	C	2.7	3.5	4.9	6.9
2100	B	3.4	4.2	6.0	8.5
	C	2.8	3.5	5.0	6.9
2250	B	3.4	4.3	6.0	8.5
	C	2.8	3.6	5.1	6.9
2400	B	3.5	4.3	6.1	8.5
	C	2.8	3.6	5.2	6.9
2550	B	3.5	4.4	6.2	8.5
	C	2.8	3.6	5.2	6.9
2700	B	3.6	4.5	6.3	8.5
	C	2.9	3.7	5.3	6.9
3000	B	3.6	4.6	6.4	8.5
	C	2.8	3.7	5.4	7.1

NOTES:

A Height of fill is measured from the finished surface to top of pipe.

B Minimum design height of fill over the top of pipe shall be greater than 600mm. Contact the concrete pipe supplier for special pipe designs 600mm or less.

C For pipe–to–structure connections, the recommended minimum height of fill over the top of pipe shall be 600mm. Refer to OPSS 401.07.10 for minimum height of fill for backfilling and use of heavy equipment.

D The excavation width is based on OPSD 802.030 and is the width of the excavation measured at the top of the pipe.

E Strength designations are pipe Class 50–D, 65–D, 100–D, and 140–D according to CSA A257.2.

F The table is based on backfill density of 2,243 kg/m^3, truck axle loads as per CHBDC Annex A3.4.1.

G For positive projecting embankment, the load factor used for the calculation of the variable bedding factor is: Class B bedding=1.9, and Class C bedding=1.5.

H For positive projecting embankment K_μ=0.165, p=0.8, and r_{sd}=0.7. This represents a sand and gravel soil material as the embankment backfill, similar to Granular A or Granular B Type II as per OPSS 1010.

I This Fill Height Table was established using assumed design parameters, and should be used for guideline purposes only. The user should verify site specific design requirements for the pipe design.

J Conditions other than those indicated shall be calculated from first principles.

K All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2018 | Rev 4

HEIGHT OF FILL TABLE

REINFORCED CONCRETE PIPE – EMBANKMENT

CLASS 50–D, 65–D, 100–D, and 140–D

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 807.030

PIPE DIA mm	RISE x SPAN mm	BEDDING CLASS	POSITIVE PROJECTING EMBANKMENT MAXIMUM HEIGHT OF FILL FOR DEPTHS > 0.6m					CONFINED TRENCH MAXIMUM HEIGHT OF FILL FOR DEPTHS > 0.6m				
			HE–A (30–D)	HE–I (40–D)	HE–II (50–D)	HE–III (60–D)	HE–IV (100–D)	HE–A (30–D)	HE–I (40–D)	HE–II (50–D)	HE–III (60–D)	HE–IV (100–D)
900	730 x 1150	B	–	2.1	2.7	3.6	6.0	–	2.1	2.7	3.9	7.2
		C	–	1.8	2.1	3.0	4.8	–	1.8	2.1	3.0	5.1
1050	855 x 1345	B	–	2.1	2.7	3.9	6.0	–	2.1	2.7	3.9	7.5
		C	–	1.8	2.4	3.0	4.8	–	1.8	2.4	3.0	5.4
1200	975 x 1535	B	–	2.4	3.0	3.9	6.0	–	2.4	3.0	3.9	7.5
		C	–	1.8	2.4	3.0	4.8	–	1.8	2.4	3.0	5.4
1350	1095 x 1730	B	–	2.4	3.0	3.9	6.0	–	2.4	3.0	4.2	7.5
		C	–	1.8	2.4	3.0	4.8	–	1.8	2.4	3.3	5.4
1500	1220 x 1920	B	–	2.4	3.0	3.9	6.0	–	2.4	3.0	4.2	7.5
		C	–	1.8	2.4	3.3	4.8	–	1.8	2.4	3.3	5.4
1650	1340 x 2110	B	–	2.4	3.0	3.9	6.0	–	2.4	3.0	4.2	7.5
		C	–	1.8	2.4	3.3	4.8	–	1.8	2.4	3.3	5.4
1800	1465 x 2305	B	–	2.4	3.3	3.9	6.0	–	2.4	3.3	4.2	7.5
		C	–	1.8	2.4	3.3	4.8	–	1.8	2.4	3.3	5.4
1950	1585 x 2495	B	–	2.4	3.3	4.2	6.0	–	2.4	3.3	4.2	7.5
		C	–	1.8	2.4	3.3	5.1	–	1.8	2.4	3.3	5.4
2100	1705 x 2690	B	–	2.4	3.3	4.2	6.0	–	2.4	3.3	4.2	7.5
		C	–	1.8	2.7	3.3	5.1	–	1.8	2.7	3.3	5.4
2400	1950 x 3070	B	–	2.7	3.3	4.2	6.3	–	2.7	3.3	4.2	7.5
		C	–	1.8	2.7	3.3	5.1	–	1.8	2.7	3.3	5.4
2700	2195 x 3455	B	–	2.7	3.3	4.2	6.3	–	2.7	3.3	4.5	7.5
		C	–	1.8	2.7	3.6	5.4	–	1.8	2.7	3.3	5.7
3000	2440 x 3840	B	–	2.7	3.3	4.5	6.6	–	2.7	3.3	4.5	7.2
		C	–	1.8	2.7	3.6	5.4	–	1.8	2.7	3.3	5.4

NOTES:

A Height of fill is measured from the finished surface to top of pipe.

B Minimum design height of fill over the top of pipe shall be greater than 600mm. Contact the concrete pipe supplier for special pipe designs 600mm or less.

C For pipe–to–structure connections, the recommended minimum height of fill over the top of pipe shall be 600mm. Refer to OPSS 401.07.10 for minimum height of fill for backfilling and use of heavy equipment.

D This OPSD shall be read in conjunction with OPSD 802.050.

E The table is based on backfill density of 2,243 kg/m^3, truck axle loads as per CHBDC Annex A3.4.1.

F For the positive projecting embankment and confined trench, the load factor used for the calculation of the variable bedding factor is: Class B bedding=1.9, and Class C bedding=1.5.

G For confined trench, $K_\mu' = 0.165$. This represents a sand and gravel soil material in the trench walls, similar to Granular A or or Granular B Type II as per OPSS 1010.

H For positive projecting embankment $K_\mu = 0.165$, p=0.8, and $r_{sd} = 0.7$. This represents a sand and gravel soil material as the embankment backfill, similar to Granular A or Granular B Type II as per OPSS 1010.

I This Fill Height Table was established using assumed design parameters, and should be used for guideline purposes only. The user should verify specific design requirements for the pipe design.

J For fill heights greater than the maximum heights given in this table, contact a manufacturer of horizontal elliptical concrete pipe.

K Conditions other than those indicated shall be calculated from first principles.

L All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2018 | Rev 4


HEIGHT OF FILL TABLE

HORIZONTAL ELLIPTICAL CONCRETE PIPE


CLASS HE–A, HE–I, HE–II, HE–III, and HE–IV

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 807.050



PLAN



SECTION A–A

NOTES:


1 Where concrete bedding is used for the main sewer, the pipe subdrain shall be placed 150mm above the top of such bedding.

2 Subdrain pipe shall be cored into maintenance hole.


A Maintenance hole benching shall accommodate pipe subdrain, as required.


B All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	4
PERFORATED PIPE SUBDRAIN IN GRANULAR TRENCH MAIN STORM SEWER CONNECTION TO DRAINAGE STRUCTURE			
	OPSD 809.010		




PLAN
CUT OR FILL







PLAN
CUT OR FILL




SECTION A–A CUT



SECTION B–B CUT



SECTION A–A FILL



SECTION B–B FILL

TYPE A – WITHOUT GEOTEXTILE

TYPE B – WITH GEOTEXTILE

NOTES:

1 The thickness of the rip–rap layer shall be at least 1.5 times the rip–rap mean diameter.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GENERAL RIP–RAP LAYOUT FOR SEWER AND CULVERT OUTLETS

Nov 2018 | Rev 3

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 810.010




Ditch Longitudinal Section — Ditch Cross–Section

TWIN INLET–INTERMEDIATE

Ditch Longitudinal Section — Ditch Cross–Section

SINGLE INLET–SUMP




Ditch Longitudinal Section — Ditch Cross–Section

SINGLE INLET–INTERMEDIATE

Ditch Longitudinal Section — Ditch Cross–Section

SINGLE INLET–INTERMEDIATE



Ditch Longitudinal Section — Ditch Cross–Section

SINGLE INLET–END OF DITCH

NOTES:

1 The thickness of the rip–rap layer shall be at least 1.5 times the rip–rap mean diameter.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GENERAL RIP–RAP LAYOUT FOR DITCH INLETS

Nov 2018 | Rev 3

OPSD 810.020


PIPE		A1		A2		A3		A4		ℓ	H
Span	Rise	No	Length m	No	Length m	No	Length m	No	Length m	m	m
3730	2290	20	1.06	20	3.20	24	2.13	36	1.06	6.17	2.28
3890	2690	20	1.06	20	3.27	24	2.13	36	1.06	6.32	2.28
4370	2870	20	1.37	20	3.86	24	2.28	40	1.06	7.46	2.43
4720	3070	20	1.37	20	4.01	24	2.28	42	1.06	7.77	2.43
5050	3330	20	1.37	20	4.19	24	2.28	44	1.06	8.07	2.43
5490	3530	20	1.37	20	4.42	24	2.28	46	1.06	8.53	2.43
5890	3710	20	1.37	20	4.62	24	2.28	50	1.06	8.91	2.43
6250	3910	20	1.37	20	4.80	24	2.28	52	1.06	9.29	2.43

PIPE	C1		C2		C3		C4		ℓ	H
Dia	No	Length m	No	Length m	No	Length m	No	Length m	m	m
3000	16	1.37	28	3.28	24	1.98	32	1.37	6.10	2.13
3050	16	1.37	28	3.35	24	1.98	34	1.37	6.25	2.13
3300	16	1.37	28	3.43	24	2.13	36	1.37	6.40	2.29
3360	16	1.37	28	3.51	24	2.13	38	1.37	6.55	2.29
3600	20	1.37	28	3.58	24	2.29	40	1.37	6.71	2.44
3670	20	1.37	28	3.73	24	2.44	44	1.37	7.01	2.59
3990	20	1.37	28	3.89	24	2.59	48	1.37	7.32	2.74
4300	20	1.37	28	4.04	24	2.74	52	1.37	7.62	2.90
4610	24	1.37	28	4.19	24	2.90	56	1.37	7.93	3.05
4920	24	1.37	28	4.34	24	3.05	60	1.37	8.23	3.20
5230	28	1.37	28	4.50	24	3.20	64	1.37	8.53	3.35




SECTION A–A

ELEVATION PIPE ARCH



SECTION B–B

ELEVATION CIRCULAR CSP



BOLT DETAIL SIDE VIEW

NOTES:

A Class of concrete: 30MPa.

B Cover to reinforcing bars: 100mm.

C EF denotes each face.

D Number of bars shown is for one wall.

E All bars shall be 15M.


F All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2017 | Rev 1

CUT OFF WALL FOR STRUCTURAL PLATE PIPE ARCH AND CIRCULAR CSP


OPSD 812.010




TYPE A



TYPE A–2



TYPE A–3



TYPE A–1
ASYMMETRIC SECTION

NOTES:

1 For slipforming procedure, a 1H:20V batter is acceptable.

2 Hot mix not required when concrete fill is placed to the top of the concrete barriers.


3 Embedment shall be 75mm into pavement at least 3m on both sides of barrier.

4 Height may vary from 825 to 1425mm in an asymmetric cross section.


5 Width may vary from 57.5 to 117.5mm in an asymmetric cross section.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2021	Rev	2
GUIDE RAIL SYSTEM, CONCRETE BARRIER CAST–IN–PLACE, TYPE A INSTALLATION			
	OPSD 911.130		



TYPE C



TYPE C–1
ASYMMETRIC SECTION

NOTES:

1 For slipforming procedure, a 1H:20V batter is acceptable.


2 Embedment shall be 75mm into pavement at least 3m wide on both sides of barrier.

A System configuration equivalent to AASHTO MASH TL–3.


B OPSD 911.136 Type M–2 barrier shall be placed adjacent to bridge piers.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2021	Rev	2
GUIDE RAIL SYSTEM, CONCRETE BARRIER CAST–IN–PLACE, TYPE C INSTALLATION			
	OPSD 911.131		




TYPE TW



TYPE TW–2



TYPE TW–3




TYPE TW–1
ASYMMETRIC SECTION


NOTES:

1 For slipforming procedure, a 1H:20V batter is acceptable.
2 Hot mix not required when concrete fill is placed to the top of the concrete barriers.
3 Embedment shall be 75mm into pavement at least 3m wide on both sides of barrier.
4 Height may vary from 1050 to 1650mm in an asymmetric cross section.
5 Width may vary from 80 to 140mm in an asymmetric cross section.
A System configuration equivalent to AASHTO MASH TL–5.
B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2021	Rev	2
GUIDE RAIL SYSTEM, CONCRETE BARRIER CAST–IN–PLACE, TALL WALL INSTALLATION			
	OPSD 911.132		



ELEVATION



DOWEL CONNECTION DETAIL

NOTES:

1 Barrier panel length shall not exceed 6m.


A This OPSD shall be read in conjunction with OPSD 911.130, 911.131, 911.132, or 911.136.

B All dowels shall be hot dip galvanized according to ASTM A123.


C Cover on reinforcement shall be 70mm ±20mm at all joints.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2021	Rev 2	ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S
GUIDE RAIL SYSTEM, CONCRETE BARRIER INSTALLATION – MEDIAN CONCRETE BARRIER TO STRUCTURE	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 911.134		



CUT SECTION




FILL SECTION

NOTES:


1 For slipforming procedure, a 1H:20V batter is acceptable.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	0
GUIDE RAIL SYSTEM, CONCRETE ROADSIDE BARRIER CAST–IN–PLACE OR SLIPFORMED INSTALLATION			
	OPSD 911.135		




TYPE M



TYPE M–2



TYPE M–3



TYPE M–1
ASYMMETRIC SECTION

NOTES:

1 For slipforming procedure, a 1H:20V batter is acceptable.

2 Hot mix not required when concrete fill is placed to the top of the concrete barriers.

3 Embedment shall be minimum 75mm into pavement at least 3m wide on both sides of barrier.


4 Height may vary from 825 to 1425mm in an asymmetric cross section.

5 Width may vary from 57.5 to 117.5mm in an asymmetric cross section.


A System configuration equivalent to AASHTO MASH TL–3.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2021	Rev	0
GUIDE RAIL SYSTEM, CONCRETE BARRIER CAST–IN–PLACE, TYPE M INSTALLATION			
	OPSD 911.136		



DETAIL A




FEMALE END ELEVATION
See Installation Detail B




ELEVATION


PLAN




MALE END ELEVATION
See Installation Detail B



DETAIL B



CONNECTION ASSEMBLY DETAIL, Note 3



SECTION A–A

NOTES:

1 The exposed flange shall be trimmed symmetrically about centreline to a width of 70mm.

2 Embedment shall be 75mm into adjacent pavement, 2.6m minimum width, both sides of barrier.

3 The connection assembly shall be hot dip galvanized after fabrication according to ASTM A123.

A Reinforcing and stirrups shall be 10M, Grade 400W, deformed steel bars. Concrete cover shall be 50mm minimum.

B All concrete edges shall have 15 x 45° chamfer.

C Welds shall be according to CSA W59 and CSA W186.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER PRECAST I–LOCK CONNECTION, TYPE TW INSTALLATION – PERMANENT


Nov 2021 | Rev 2

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S


OPSD 911.143




ELEVATION




END ELEVATION





SECTION A–A






PLAN





BARRIER TO BARRIER CONNECTION



DETAIL

Type J Connection

REINFORCING STEEL BARS						
BAR	SIZE	GRADE	TYPE	LENGTH	SHAPE	NO. REQ'D
R1	15M	400W	Deformed	3200	3000, 100	3
R2	15M	400W	Deformed	814	610, 102, 102	6
R3	10M	400W	Deformed	1080	480, 300	2
W1	152X152 MW18.7XMW18.7 (456X3810)					

NOTES:

1 Temporary concrete barriers manufactured prior to September 2009 with one 600mm long x 100mm high opening are acceptable.

A Minimum horizontal radius shall be 31m.

B The system depicted here is a proprietary product.

C System configuration meets NCHRP Report 350 TL–3.

D Concrete cover shall be 50mm minimum.

E All concrete edges shall have 15 x 45° chamfers.

F Welds shall be according to CSA W59.

G All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE J CONNECTION, 4m LENGTH INSTALLATION – TEMPORARY


Nov 2021 | Rev 1

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 911.150




ELEVATION




PLAN





END ELEVATION




SECTION A–A








BARRIER TO BARRIER CONNECTION





DETAIL
Type J Connection

REINFORCING STEEL BARS						
BAR	SIZE	GRADE	TYPE	LENGTH	SHAPE	NO. REQ'D
R1	15M	400W	Deformed	5045	4845, 100	3
R2	15M	400W	Deformed	814	610, 102, 102	6
R3	10M	400W	Deformed	1080	480, 300	2
R4	10M	400W	Deformed	1650	786, 253, R42	8
R5	10M	400W	Deformed	750	750	2
R6	20M	400W	Deformed	5825	5825	4

NOTES:

A Minimum horizontal radius shall be 47m.

B The system depicted here is a proprietary product.

C System configuration meets NCHRP Report 350 TL–3.

D Concrete cover shall be 50mm minimum.

E All concrete edges shall have 15 x 45° chamfers.

F Welds shall be according to CSA W59.

G All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2021 | Rev 1


GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE J CONNECTION, 6m LENGTH INSTALLATION – TEMPORARY

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 911.151




ELEVATION



SECTION A–A



PLAN



SECTION B–B

NOTES:

A This OPSD shall be read in conjunction with OPSD 911.161.


B System configuration meets AASHTO MASH TL–3.

C All concrete edges shall have 15 x 45° chamfers.


D Welding of reinforcement bars shall be according to CSA W186.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	1
GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE M CONNECTION INSTALLATION – TEMPORARY 1			
	OPSD 911.160		




PLAN




ELEVATION

CONNECTION DETAIL




PLAN




ELEVATION

CONNECTION PIN




PLAN

HOOP BAR ASSEMBLY




ELEVATION

STIRRUPS



PLAN



ELEVATION

LOOP BAR ASSEMBLY

REINFORCING STEEL BARS						
BAR	SIZE	GRADE	TYPE	LENGTH	SHAPE	NO. REQ'D
H1	15M	400W	Deformed	3708	3708	5
L1, Note 1 and 2	20M	400W Note 1	Deformed	2570	405 857	2
L2, Note 1 and 2	20M	400W Note 1	Deformed	2310	305 838	2
L3, Note 1 and 2	20M	400W Note 1	Deformed	2600	405 875	2
L4	20M	400W	Deformed	889	203 406	6
V1	15M	400W	Deformed	1791		12

NOTES:

1 Minimum tensile elongation of test specimen shall be greater than 14%.
2 Imperial size 3/4 inch diameter Grade 60 ASTM A706 smooth reinforcing steel bars are acceptable.
3 Slack shall be removed from joint after pin installation. Minimum horizontal radius shall be 26m.

A Welding of connection pin and plate shall be according to CSA W59.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE M CONNECTION INSTALLATION–TEMPORARY 2


Nov 2013 | Rev 0

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · STANDARD


OPSD 911.161



ELEVATION



SECTION A–A



STEEL PIN ASSEMBLY

NOTES:

1 Maximum 38mm diameter holes may be drilled through asphalt pavement for pins. Holes shall be drilled after barriers positioned.

2 When the level area between the back of the barrier and the upper edge of an excavation is less then one metre, use of this standard requires the Owner to have a signed and sealed memorandum from an Engineer for each installation used during construction according to Ontario Regulation 213/91.

3 Steel pins may be installed through drilled holes in concrete pavement, concrete approach slabs, or composite pavement. Maximum diameter of drilled holes are 41mm.

A This OPSD shall be read in conjunction with OPSD 911.160 and 911.170.

B System configuration meets NCHRP Report 350 TL–3.

C Welds shall be according to CSA W59.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE M CONNECTION

INSTALLATION – TEMPORARY RESTRAINED SYSTEM PINNED TO ASPHALT PAVEMENT


Nov 2021 | Rev | 1

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S


OPSD 911.162




END VIEW



ELEVATION



PLAN



ELEVATION

SIDE VIEW

STEEL TIE–DOWN STRAP

NOTES:

1 This OPSD shall not be used when asphalt layer over concrete exists.

2 This OPSD shall not be used on bridge superstructures that contain post tensioned tendons within the concrete deck or bridge superstructures with longitudinally prestressed, transversally post tensioned, solid or voided concrete slab units.

3 Anchors shall be installed according to manufacturer's specifications by an installer certified by the manufacturer's direct representative.

4 Minimum concrete strength shall be 27MPa.

5 When the level area between the back of the barrier and the upper edge of an excavation is less then one metre, use of this standard requires the Owner to have a signed and sealed memorandum from an Engineer for each installation used during construction according to Ontario Regulation 213/91.

A This OPSD shall be read in conjunction with OPSD 911.160 and 911.171.

B System configuration meets NCHRP Report 350 TL–3.

C Welds shall be according to CSA W59.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE M CONNECTION INSTALLATION – TEMPORARY RESTRAINT SYSTEM STRAPPED TO CONCRETE


Nov 2021 | Rev 1


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S

OPSD 911.163









STEEL TIE-DOWN STRAP

NOTES:

1 This OPSD shall not be used on bridge superstructures that contain post tensioned tendons within the concrete deck or bridge superstructures with longitudinally prestressed, transversally post tensioned, solid or voided concrete slab units.

2 Anchors shall be installed according to manufacturer's specifications by an installer certified by the manufacturer's direct representative. The 1-1/4" diameter holes for anchors shall be diamond core drilled.

3 Minimum concrete strength shall be 27MPa.

4 When the level area between the back of the barrier and the upper edge of an excavation is less then one metre, use of this standard requires the Owner to have a signed and sealed memorandum from an Engineer for each installation used during construction according to Ontario Regulation 213/91.

A This OPSD shall be read in conjunction with OPSD 911.160 and 911.171.

B System configuration is equivalent to OPSD 911.163, which meets NCHRP Report 350 TL-3.

C Barriers shall be pulled tight during installation to remove slack.

D Welds shall be according to CSA W59.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE M CONNECTION

INSTALLATION – TEMPORARY RESTRAINT SYSTEM STRAPPED TO CONCRETE WITH ASPHALT SURFACE


Nov 2021 | Rev 1

ONTARIO STANDARDS · MUNICIPAL - PROVINCIAL · O P S

OPSD 911.164



ELEVATION



SECTION A–A

NOTES:

1 This OPSD shall not be used when asphalt layer over concrete exists.

2 This OPSD shall not be used on bridge superstructures that contain post tensioned tendons within the concrete deck or bridge superstructures with longitudinally prestressed, transversally post tensioned, solid or voided concrete slab units.

3 Minimum concrete strength shall be 27MPa.

4 When the level area between the back of the barrier and the upper edge of an excavation is less then one metre, use of this standard requires the Owner to have a signed and sealed memorandum from an Engineer for each installation used during construction according to Ontario Regulation 213/91.

A This OPSD shall be read in conjuction with OPSD 911.160 and 911.172.

B System configuration meets NCHRP Report 350 TL–3.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE M CONNECTION INSTALLATION – TEMPORARY RESTRAINT SYSTEM BOLTED THROUGH CONCRETE

Nov 2021 | Rev 1


ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 911.167



ELEVATION

TABLE 1	
Maximum asphalt thickness	Steel tube diameter
76	73 OD 41 ID
100	83 OD 51 ID
150	95 OD 64 ID



SECTION A–A

NOTES:

1 Cold drawn over mandrel steel tube. See Table 1 for minimum tube size based on maximum asphalt thickness.

2 This OPSD shall not be used on bridge superstructures that contain post tensioned tendons within the concrete deck or bridge superstructures with longitudinally prestressed, transversally post tensioned, solid or voided concrete slab units.

3 Minimum concrete strength shall be 27MPa.

4 When the level area between the back of the barrier and the upper edge of an excavation is less then one metre, use of this standard requires the Owner to have a signed and sealed memorandum from an Engineer for each installation used during construction according to Ontario Regulation 213/91.

A This OPSD shall be read in conjunction with OPSD 911.160 and 911.172.

B System configuration is equivalent to OPSD 911.167, which meets NCHRP Report 350 TL–3.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE M CONNECTION

INSTALLATION – TEMPORARY RESTRAINT SYSTEM BOLTED THROUGH CONCRETE WITH ASPHALT SURFACE


Nov 2021 | Rev 1

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 911.168



PLAN



ELEVATION

NOTES:

1 Type M temporary concrete barrier shown. Transition to another connection type shall be completed according to OPSD 911.340.

2 When the level area between the back of the barrier and the upper edge of an excavation is less than one metre, use of this standard requires the Owner to have a signed and sealed memorandum from an Engineer for each installation used during construction according to Ontario Regulation 213/91.

A This OPSD shall be read in conjunction with OPSD 911.160 and 911.162.

B System configuration meets NCHRP Report 350 TL–3.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE M CONNECTION INSTALLATION – TEMPORARY RESTRAINT SYSTEM TRANSITION TO PINNED TCB


Nov 2021 | Rev 2

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL ·

OPSD 911.170



PLAN



ELEVATION

NOTES:

1 Type M temporary concrete barrier shown. Transition to another connection type shall be completed according to OPSD 911.340.

2 When the level area between the back of the barrier and the upper edge of an excavation is less then one metre, use of this standard requires the Owner to have a signed and sealed memorandum from an Engineer for each installation used during construction according to Ontario Regulation 213/91.

A This OPSD shall be read in conjunction with OPSD 911.160, 911.163, and 911.164.

B System configuration meets NCHRP Report 350 TL–3.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE M CONNECTION
INSTALLATION – TEMPORARY RESTRAINT SYSTEM TRANSITION TO STRAPPED TCB


Nov 2021 | Rev 2

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 911.171



PLAN



ELEVATION

NOTES:

1 It is acceptable to omit one anchor bolt within a single barrier if a conflict exists between an anchor location and an expansion joint or deck drain.
2 When the connection of adjacent barrier units does not line up with the expansion joint, a barrier unit crossing the expansion joint shall be anchored with a combination of bolts on the bridge deck and pins on the approach slab.
3 When steel pin assemblies are to be installed within the limits of the approach slab, drill maximum 41mm diameter holes through the asphalt and concrete approach slab. Holes shall be drilled after the barriers are positioned.
4 Distance measured from end of bridge deck to mid span of thrie beam rail.
5 Type M temporary concrete barrier shown. Transition to another connection type shall be completed according to OPSD 911.340.
6 When the level area between the back of the barrier and the upper edge of an excavation is less than one metre, use of this standard requires the Owner to have a signed and sealed memorandum from an Engineer for each installation used during construction according to Ontario Regulation 213/91.

A This OPSD shall be read in conjunction with OPSD 911.160, 911.162, 911.167, 911.168, and 911.174.
B System configuration meets NCHRP Report 350, TL–3.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE M CONNECTION INSTALLATION – TEMPORARY RESTRAINT SYSTEM TRANSITION TO BOLTED TCB


Nov 2021 | Rev 2

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 911.172



PLAN



ELEVATION

NOTES:

1 Type M temporary concrete barrier shown. Transition to another connection type shall be completed according to OPSD 911.340.

2 When the level area between the back of the barrier and the upper edge of an excavation is less then one metre, use of this standard requires the Owner to have a signed and sealed memorandum from an Engineer for each installation used during construction according to Ontario Regulation 213/91.

3 When steel pin assemblies are to be installed within the limits of the approach slab, drill maximum 41mm diameter holes through asphalt and concrete approach slab. Holes shall be drilled after the barriers are positioned.

A This OPSD shall be read in conjunction with OPSD 911.160 and 911.162.

B System configuration meets NCHRP Report 350 TL–3.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE M CONNECTION
INSTALLATION – TEMPORARY RESTRAINT SYSTEM TRANSITION TO PERMANENT CONCRETE BARRIER

Nov 2021 | Rev 2


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 911.173




PLAN

Traffic flow



ELEVATION



SPLICE BOLT AND NUT
DETAIL A

NOTES:

1 Alternative Hilti HIT HY200 with 22mm diameter HAS–E rods or equivalent, 95mm minimum embedment.
2 Exposed bolt or threaded rod end saw–cut flush with face of nut.
3 Steel connection pin not required with permanent concrete barrier.
A This OPSD shall be read in conjunction with OPSD 911.160.
B System configuration meets NCHRP Report 350 TL–3.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE M CONNECTION COMPONENT – THRIE BEAM TRANSITION


Nov 2021 | Rev 2

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS


OPSD 911.174




DETAIL A




SECTION A–A




SECTION B–B



ELEVATION



REINFORCING STEEL BARS					
BAR	SIZE	GRADE	TYPE	LENGTH	NO. REQ'D
R1	15M	400W	Deformed	3898	3
R2	20M	400W	Deformed	610	4
R3	20M	400W	Deformed	915	3



ELEVATION

PLAN

STEEL DETAILS

NOTES:

1 Type T connections with 610mm long T–Lok connections manufactured before March 2010 may be used.

A Minimum horizontal radius shall be 26m.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–3.

D Concrete cover shall be 50mm minimum.

E All concrete edges shall have 15 x 45° chamfers.

F Welds shall be according to CSA W59.

G All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE T CONNECTION, 4.0m LENGTH INSTALLATION – TEMPORARY


Nov 2021 | Rev 1

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS

OPSD 911.180




DETAIL A




ELEVATION

PLAN





SECTION A–A



SECTION B–B

REINFORCING STEEL BARS					
BAR	SIZE	GRADE	TYPE	LENGTH	NO. REQ'D
R1	15M	400W	Deformed	5898	3
R2	20M	400W	Deformed	610	4
R3	20M	400W	Deformed	915	3





ELEVATION

PLAN

STEEL DETAILS

NOTES:

1 Type T connections with 610mm long T–Lok connections manufactured before March 2010 may be used.

A Minimum horizontal radius shall be 39m.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–3.

D Concrete cover shall be 50mm minimum.

E All concrete edges shall have 15 x 45° chamfers.

F Welds shall be according to CSA W59.

G All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE T CONNECTION, 6.0m LENGTH INSTALLATION – TEMPORARY


Nov 2021 | Rev 1

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS


OPSD 911.181




ELEVATION



SECTION A–A



PLAN



BARRIER SHAPE

NOTES:

1 Minimum 38mm cover to longitudinal bars shall be provided above the opening.

A This OPSD shall be read in conjunction with OPSD 911.191 and 911.192.

B Minimum horizontal radius shall be 122m.

C System configuration meets AASHTO MASH TL–3.

D All concrete edges shall have 15 x 45° chamfer.

E Welds shall be according to CSA W59 and CSA W186.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE X CONNECTION, 9.1m LENGTH INSTALLATION – TEMPORARY


Nov 2021	Rev	0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS


OPSD 911.190




END JOINT RECESSED LEAVE OUTS DETAIL



CONNECTION ROD DETAIL



STEEL CONNECTOR PLATE DETAILS



CONNECTION DETAIL






PLATE WASHER DETAIL




CONNECTION ASSEMBLY




D1

DEFORMED ANCHOR BAR DETAIL



SCHEDULE 40 PIPE



STEEL CONNECTOR PLATE DETAIL

NOTES:

1 The connection hardware shall not extend beyond the concrete face of the barrier at the leave–outs.

A Welds shall be according to CSA W59 and CSA W186.

B Steel reinforcement shall be Grade 400W according to CAN/CSA G30.18 with a minimum yield strength of 420 MPa.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE X CONNECTION COMPONENTS


Nov 2021 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S

OPSD 911.191




V1



STIRRUPS

V3



V2

REINFORCING STEEL BARS										
					OPSD 911.193		OPSD 911.198		OPSD 911.190	
					LENGTH = 3.048m		LENGTH = 6.096m		LENGTH = 9.144m	
BAR	SIZE	Grade Note 1	TYPE	SHAPE	BAR LENGTH (mm)	NUMBER REQUIRED	BAR LENGTH (mm)	NUMBER REQUIRED	BAR LENGTH (mm)	NUMBER REQUIRED
V1	15M	400W	DEFORMED		1524	17	1524	29	1524	37
V2	15M	400W	DEFORMED		1270	2	1270	2	1270	2
V3	15M	400W	DEFORMED		635	19	635	20	635	20
D1	20M	400W	DEFORMED		1135	8	1135	8	1135	8
H1	15M	400W	DEFORMED		N/A	N/A	9040	6	9040	6
H2	15M	400W	DEFORMED		N/A	N/A	9040	2	9040	2
H3	15M	400W	DEFORMED		2994	6	N/A	N/A	N/A	N/A
H4	15M	400W	DEFORMED		2994	2	N/A	N/A	N/A	N/A

NOTES:

1 Steel reinforcement shall be Grade 400W according to CAN/CSA G30.18 with a minimum yield strength of 420MPa.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE X CONNECTION – REINFORCEMENT COMPONENTS

Nov 2021 | Rev 0


OPSD 911.192




ELEVATION



PLAN



SECTION A–A



BARRIER SHAPE

NOTES:

1 Minimum 38mm cover to longitudinal bars shall be provided above the opening.

A This OPSD shall be read in conjunction with OPSD 911.191 and 911.192.

B Minimum horizontal radius shall be 40m.

C System configuration meets AASHTO MASH TL–3.

D All concrete edges shall have 15 x 45° chamfer.

E Welds shall be according to CSA W59 and CSA W186.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE X CONNECTION, 3.048m LENGTH INSTALLATION – TEMPORARY


Nov 2021 | Rev 0

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPS


OPSD 911.193




PLAN




SECTION A–A




SECTION B–B



ELEVATION



RIGHT SIDE



PROFILE

NOTES:

A Barrier shall only be used with OPSD 911.331 and shall not be used as a stand alone system.

B This OPSD shall be read in conjunction with OPSD 911.191 and 911.197.

C All concrete edges shall have 15 x 45° chamfer.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE X CONNECTION, 4.0m LENGTH INSTALLATION – TEMPORARY


Nov 2021 | Rev | 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S


OPSD 911.194



ELEVATION



SECTION A–A
EXISTING ASPHALT
OR CONCRETE



SECTION A–A
NEW ASPHALT

NOTES:

1 When level area between the back of the barrier and the upper edge of an excavation is less than one metre, use of this OPSD requires the Owner to have a signed and sealed memorandum from an Engineer for each installation used during construction according to Ontario Regulation 213/91.

A System configuration meets AASHTO MASH TL–3.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE X CONNECTION INSTALLATION – TEMPORARY

Nov 2021 | Rev 0

OPSD 911.195



PLAN



ELEVATION

NOTES:

1 Temporary concrete barrier as specified or transition to energy attenuator according to OPSD 911.232 or 911.233.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE X CONNECTION INSTALLATION – TEMPORARY REDUCED DEFLECTION TRANSITION TO TCB


Nov 2021	Rev	0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 911.196




V3



V3A



V4



MK2002

REINFORCING STEEL BARS							
BAR	SIZE	Grade Note 1	TYPE	SHAPE	LENGTH	NUMBER REQUIRED OPSD 911.194	NUMBER REQUIRED OPSD 911.199
V3	15M	400W	DEFORMED		1560	16	9
V3A	15M	400W	DEFORMED		1560	2	2
V4	15M	400W	DEFORMED		1610	4	2
D1	20M	400W	DEFORMED		1135	8	8
H1	15M	400W	DEFORMED		3900	7	7
MK 2002	15M	400W	DEFORMED		860	6	5

NOTES:

1 Steel reinforcement shall be Grade 400W according to CAN/CSA G30.18 with a minimum yield strength of 420 MPa.

A All dimensions in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER
TYPE X CONNECTION, 4.0m LENGTH
REINFORCING STEEL


Nov 2021 | Rev 0

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · O P S


OPSD 911.197




ELEVATION



PLAN



SECTION A–A



BARRIER SHAPE

NOTES:

1 Minimum 38mm cover to longitudinal bars shall be provided above the opening.

A This OPSD shall be read in conjunction with OPSD 911.191 and 911.192.

B Minimum horizontal radius shall be 40m.

C System configuration meets AASHTO MASH TL–3.

D All concrete edges shall have 15 x 45° chamfer.

E Welds shall be according to CSA W59 and CSA W186.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE X CONNECTION, 6.1m LENGTH INSTALLATION – TEMPORARY


Nov 2021 | Rev 0

ONTARIO STANDARD • MUNICIPAL – PROVINCIAL •


OPSD 911.198




PLAN




PROFILE



A B ELEVATION



SECTION A–A



SECTION B–B

NOTES:

A Barrier shall only be used with OPSD 911.331.

B This OPSD shall be read in conjunction with OPSD 911.191 and 911.197.

C All concrete edges shall have 15 x 45° chamfer.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE X CONNECTION, 4.0m LENGTH, CLIPPED INSTALLATION – TEMPORARY


Nov 2021 | Rev | 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 911.199



ELEVATION



SECTION A–A
EXISTING ASPHALT
OR CONCRETE



SECTION A–A
NEW ASPHALT

NOTES:

1 When the level area between the back of the barrier and the upper edge of an excavation is less than one metre, use of this OPSD requires the Owner to have a signed and sealed memorandum from an Engineer for each installation used during construction according to Ontario Regulation 213/91.

2 Use of this OPSD requires traffic to be in a single lane controlled by temporary traffic signals resting in red and the regulatory posted speed limit at the installation to be less than 70km/h.

A System configuration meets AASHTO MASH TL–2.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TYPE X CONNECTION INSTALLATION – TEMPORARY – LOW SPEED


Nov 2021 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 911.200




PLAN



SIDE ELEVATION

SECTION A–A



SECTION B–B

NOTES:

1 Where minimum clearance cannot be obtained, an approved end treatment or energy attenuator shall be installed.

2 Embedment shall be 75mm into adjacent pavement.

A This OPSD shall be read in conjunction with OPSD 911.130, 911.131, and 911.132.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER MEDIAN END TREATMENT INSTALLATION

Apr 2021 | Rev 2

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 911.230



NOTES:

1 Energy attenuator–temporary reduced exposure (EAT–RE), shall be placed on a paved surface according to the manufacturer's recommendations and Contract Documents.

2 Offset to EAT–RE from edge of travelled way shall not be less than 1.0m.

3 At locations where existing concrete barrier or steel beam guide rail is present behind the EAT–RE, the existing barrier shall extend a minimum of 16m beyond the impact end of the EAT–RE.

4 When the EAT–RE is placed parallel to existing barrier, lateral offset shall be ≤0.3m or >3.0m.

5 Length of transition governed by temporary concrete barrier (TCB) flare rate. Maximum length of each TCB unit within transition is 4m.

6 Minimum 1.0m offset from back of TCB to edge of excavation or edge of structure or back of roadway protection (support) system, unless otherwise specified.

A Roadside installation shown. For median application, use a mirror image.

B All dimensions are in millimetres unless otherwise shown.


Maximum TCB Flare Rate	
Posted Speed km/h	X:1
≥ 70	10
< 70	6

ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, TEMPORARY CONCRETE BARRIER AND ENERGY ATTENUATOR – TEMPORARY, REDUCED EXPOSURE INSTALLATION – TEMPORARY

Nov 2021 | Rev 2

OPSD 911.232



NOTES:

1 Energy attenuator–temporary reduced exposure (EAT–RE), shall be placed on a paved surface according to the manufacturer's recommendations and contract documents.

2 Offset to EAT–RE from edge of travelled way shall not be less than 1.0m.

3 At locations where existing concrete barrier or steel beam guide rail is present behind the EAT–RE, the existing barrier shall extend a minimum of 16m beyond the impact end of the EAT–RE.

4 When EAT–RE placed adjacent to existing barrier, lateral clearance shall be ≤0.3m or ≥ 3.0m; otherwise, a traversable object–free zone shall be provided

5 Length of transition governed by Temporary Concrete Barrier (TCB) flare rate. Maximum length of each TCB unit within transition are 4m.

6 Minimum 1.0m offset from back of TCB to edge of excavation or edge of structure or back of roadway protection (support) system, unless otherwise specified.

A Configuration to be used only with ABSORB–M.

B Roadside installation shown. For median application, use a mirror image.

C All dimensions are in millimetres unless otherwise shown.

Max TCB Flare Rate	
Posted Speed km/h	X:1
≥ 70	10
< 70	6


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, TEMPORARY CONCRETE BARRIER AND ENERGY ATTENUATOR – TEMPORARY, REDUCED EXPOSURE, ANCHORED BARRIER INSTALLATION – TEMPORARY


Nov 2021 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS

OPSD 911.236



PLAN



ELEVATION

NOTES:


1 Connect barrier cap to Type X barrier using threaded rod through cup washer 1 on traffic side and cup washer 2 on barrier side.

A This OPSD shows left shoulder installation. The temporary transition barrier shall be inverted for right shoulder installation.

B System configuration meets AASHTO MASH TL–3.

C This OPSD shall be read in conjunction with OPSD 911.335, 911.336, 911.337, 911.338, 911.339, 911.341, and 911.342.

D All dimensions are in millimetres unless otherwise shown.



DETAIL A


PROPRIETARY JACK SCREW AND BALL JOINT WOBBLE PLATE

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, CONCRETE BARRIER TEMPORARY TRANSITION BARRIER INSTALLATION

Nov 2020 | Rev 0

OPSD 911.331



REAR SIDE ELEVATION



POST 1 | POSTS 2, 3, 4 | POST 5

STIFFENERS


HORIZONTAL STIFFENER RIBS

NOTES:


1 Top three stiffener ribs shall be tapered from full cross section to 6.4mm thick wall welded to traffic side plate over upstream 1752mm. Bottom stiffener rib shall be transitioned in the same manner over 2182mm.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev	0
GUIDE RAIL SYSTEM, CONCRETE BARRIER TEMPORARY TRANSITION BARRIER RIBS AND STIFFENER POSTS – COMPONENTS			
	OPSD 911.335		




STIFFENER POST 1
PLAN




SPLICE PLATES




STIFFENER POST 1
PLAN



STIFFENER POSTS 3 AND 4
REAR HOLE DETAIL



STIFFENER POST 2
PLAN



STEEL TRANSITION PLATE

NOTES:

1 Spacer shall be attached to stiffener plate 2 using 16mm bolts through side holes.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2020 | Rev 0


GUIDE RAIL SYSTEM, CONCRETE BARRIER TEMPORARY TRANSITION BARRIER STIFFENER POST DETAILS – COMPONENTS

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S


OPSD 911.336




TAIL PIECE ELEVATION




TAIL PIECE
CROSS SECTION



TRANSITION
UPSTREAM DETAILS



TAIL PIECE
CONNECTION PLAN VIEW



STIFFENER RIBS
UPSTREAM TERMINATION

NOTES:

A Steel plates shall be 6mm thick.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER
TEMPORARY TRANSITION BARRIER
TAIL PIECE DETAILS – COMPONENTS


Nov 2020 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL ·


OPSD 911.337




WELDS TO STIFFENER POST 5 AND RIBS




DOWNSTREAM ELEVATION




PLAN VIEW



DETAIL A



REAR SIDE ELEVATION



TRAFFIC SIDE ELEVATION

NOTES:

A Steel plates shall be 6mm thick.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TEMPORARY TRANSITION BARRIER END CAP DETAILS – COMPONENTS

Nov 2020 | Rev 0

OPSD 911.338



ISOMETRIC VIEW




PLATE 1




PLATE 2




PLATE 3




PLATE 4

NOTES:

A Steel plates shall be 6mm thick.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, CONCRETE BARRIER TEMPORARY TRANSITION BARRIER CUP WASHER 1 – COMPONENT

Nov 2020 | Rev 0


OPSD 911.339




PLAN



WOODEN SPACER BLOCK
DETAIL A




ELEVATION



SECTION A–A


NOTES:

1 Top and bottom of wooden spacer block cut shall match profile of adjacent temporary concrete barriers.
2 Alternative Hilti HIT HY200 with 22mm diameter HAS–E rods or equivalent, 95mm minimum embedment.
3 Exposed bolt or threaded rod end saw–cut flush with face of nut. Flame cutting is not permitted.
A Minimum length of 32m of temporary concrete barrier on both sides of transition.
B All dimensions are in millimetres unless otherwise shown.




SPLICE BOLT AND NUT
DETAIL B


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev	1
GUIDE RAIL SYSTEM, CONCRETE BARRIER TEMPORARY CONCRETE BARRIER TRANSITION INSTALLATION – TEMPORARY			
			OPSD 911.340




UPSTREAM CONNECTION



SECTION A–A



SECTION B–B




STEEL PIN ASSEMBLY
FOR ASPHALT PAVEMENT

NOTES:

1 Hex socket bolts shall use Hilti HY–200 epoxy anchoring system or equivalent epoxy adhesive anchoring system.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev	0
GUIDE RAIL SYSTEM, CONCRETE BARRIER TEMPORARY TRANSITION BARRIER CONNECTION TO PERMANENT BARRIER – COMPONENT			
	OPSD 911.341		



ISOMETRIC VIEW




PLATE 1




PLATE 2





PLATE 3


NOTES:

A Steel plates shall be 6mm thick.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev	0
GUIDE RAIL SYSTEM, CONCRETE BARRIER TEMPORARY TRANSITION BARRIER CUP WASHER 2 – COMPONENT			
	OPSD 911.342		



PLAN



DETAIL B



DETAIL A

NOTES:

1 Shoulder surface may be granular or pavement.

2 Temporary concrete barriers (A) through (E) shall be Type J, M, or T with maximum unit lengths of 4m and may be installed on granular or paved surface. Type M TCB depicted.

3 When SBGR posts are installed within paved areas, pavement shall be removed according to Detail B.

4 See OPSD 911.354 and 911.355 for steel brackets and wooden offset blocks (1) through (4).

A Right shoulder installation shown. For left shoulder installation on divided highway, installation shall be inverted with a SBGR left side transition connection.

B System configuration meets AASHTO MASH TL–3.

C All dimensions are in metres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER STEEL BEAM GUIDE RAIL TO TEMPORARY CONCRETE BARRIER INSTALLATION – TEMPORARY

Nov 2020 | Rev 0


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 911.350



ELEVATION

PROFILE



PLAN

NOTES:

1 Nuts shall be according to ASTM A563DH.

A Component shall be hot dip galvanized after fabrication according to ASTM A123.

B Components (e2) through (e12) detailed on OPSD 911.352.

C Assembled component for right shoulder connector plate installation depicted. For left shoulder installations on divided highways, assembled component details shall be mirrored.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER
STEEL BEAM GUIDE RAIL TO TEMPORARY CONCRETE BARRIER
CONNECTOR PLATE – COMPONENT


Nov 2020 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 911.351




Part e2




Part e6




Part e3




Part e7




Part e8




Part e9




Part e4




Part e10



Part e11



Part e12



Part e5

NOTES:

A All vertical and horizontal gussets shall be 6.35mm thick ASTM A36 steel.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER
STEEL BEAM GUIDE RAIL TO TEMPORARY CONCRETE BARRIER
CONNECTOR GUSSETS – COMPONENTS


Nov 2020 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • OPS

OPSD 911.352



PLAN



ELEVATION

NOTES:

A Connector plates shall be 6.35mm thick ASTM A36 steel.
B Face plate details for right shoulder installations depicted. For left shoulder installations on divided highways, details shall be mirrored.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER
STEEL BEAM GUIDE RAIL TO
TEMPORARY CONCRETE BARRIER
CONNECTOR PLATE FACE PLATE – COMPONENT


Nov 2020 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 911.353



PROFILE



ELEVATION



PLAN


OFFSET BLOCK BRACKET 1 THROUGH 4

NOTES:

A Offset block brackets shall be 6.35mm thick ASTM A36 steel, hot dip galvanized after fabrication according to ASTM A123.


B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev	0
GUIDE RAIL SYSTEM, CONCRETE BARRIER STEEL BEAM GUIDE RAIL TO TEMPORARY CONCRETE BARRIER STEEL BRACKETS – COMPONENTS			
	OPSD 911.354		





WOODEN OFFSET BLOCKS 1 THROUGH 4

ELEVATION









WOODEN OFFSET BLOCK 1 WOODEN OFFSET BLOCK 2 WOODEN OFFSET BLOCK 3 WOODEN OFFSET BLOCK 4

PLAN

NOTES:


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2020 | Rev 0

GUIDE RAIL SYSTEM, CONCRETE BARRIER
STEEL BEAM GUIDE RAIL TO TEMPORARY CONCRETE BARRIER
WOODEN OFFSET BLOCKS – COMPONENTS

OPSD 911.355



PLAN



ELEVATION

NOTES:

1 Type M TCB units depicted from OPSD 911.350. Other types of TCB that meet AASHTO MASH TL–3 or NCHRP Report 350 TL–3 are acceptable when each unit is more than 3.8m long.

2 One bolt on each side of bracket shall be installed through upper or lower hole in bracket (two per bracket).

3 All bolts shall be according to ASTM A325.

4 All nuts shall be according to ASTM A563DH.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER
STEEL BEAM GUIDE RAIL TO TEMPORARY CONCRETE BARRIER
TEMPORARY TRANSITION CONNECTION


Nov 2020 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL ·

OPSD 911.357



PLAN



ELEVATION

TABLE 1	
Flare	
POSTED SPEED km/h	X
100	32
90	30
80	26
70	24
60	21
50	18

NOTES:

1 Transition length governed by flare rate and width of barrier at bridge pier according to Table 1 or as specified.

2 Length governed by bridge pier configuration. Concrete barrier and expansion joint details as specified.

3 Transition shall be one piece construction. No portion of the transition shall be slipformed.

A This OPSD shall be read in conjunction with OPSD 911.130, 911.131, 911.132, and 911.136.


B All dimensions are shown in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, CONCRETE BARRIER PERMANENT TRANSITION INSTALLATION AT BRIDGE PIERS

Apr 2021 | Rev 2


OPSD 911.380



SECTION A–A




PLAN




ELEVATION

NOTES:
A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2021	Rev	3
GUIDE RAIL SYSTEM, CONCRETE BARRIER PERMANENT TRANSITION INSTALLATION ROADSIDE CONCRETE BARRIER TO STRUCTURE			
	OPSD 911.381		




DOWEL CONNECTION WITH EXPANSION JOINT
TYPE I



DOWEL CONNECTION WITHOUT EXPANSION JOINT
TYPE II



DOWEL CONNECTION DETAIL
TYPE I



DOWEL CONNECTION DETAIL
TYPE II

NOTES:


1 Dowel shall be placed along centreline of transition section.

A This OPSD shall be read in conjunction with OPSD 911.381.


B All dowels shall be hot dip galvanized according to ASTM A123.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	1
GUIDE RAIL SYSTEM, CONCRETE BARRIER DOWEL CONNECTION DETAIL			
	OPSD 911.382		



PLAN



ELEVATION

TABLE 1	
Flare	
POSTED SPEED km/h	X
100	32
90	30
80	26
70	24
60	21
50	18

NOTES:

1 Transition length governed by flare rate and width of footing according to Table 1 or as specified.

2 Length governed by lighting pole or sign support footing. Concrete barrier and expansion joint details as specified.

3 Transition shall be one piece construction. No portion of the transition shall be slipformed.

A This OPSD shall be read in conjunction with OPSD 911.130, 911.131, 911.132, and 911.136.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, CONCRETE BARRIER PERMANENT TRANSITION INSTALLATION AT LIGHTING POLE AND SIGN SUPPORT FOOTINGS

Apr 2021 | Rev 1

OPSD 911.383




PLAN
TYPE A



PLAN
TYPE B

Dimension	Posted Speed (km/h)	
	< 70	≥ 70
L1	20m	32m
L2	12m	16m
X1	0.15–0.3m	0.15–0.3m
X2	0.8m	1.5m
X3	0.4m	0.6m



PLAN
TYPE C

NOTES:

A Roadside installation shown. For median application, use a mirror image.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER TEMPORARY – LEAVING END TREATMENT INSTALLATION – DIVIDED HIGHWAY


Nov 2015 | Rev 1

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL ·

OPSD 911.430



SIDE ELEVATION



FRONT ELEVATION

NOTES:

A The system depicted here is a proprietary product.
B System configuration meets NCHRP Report 350 TL–3.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CONCRETE BARRIER QUICKCHANGE MOVEABLE BARRIER INSTALLATION – TEMPORARY


Nov 2021 | Rev | 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 911.610



FRONT ELEVATION




ENLARGED SECTION A–A



SPLICE BOLT AND NUT

SPLICE BOLT LENGTH	
LOCATION	LENGTH
At posts	32
At structure anchor	38



ARRANGEMENT AT POST
WOODEN POST SHOWN

NOTES:

1 Base metal thickness of rail shall be 2.67mm nominal and 2.44mm minimum.

2 Holes only in rail.


A All dimensions subject to manufacturing tolerances unless otherwise indicated.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2016 | Rev 3

GUIDE RAIL SYSTEM, STEEL BEAM
RAIL
COMPONENT


OPSD 912.101






SPLICE BOLT AND NUT

SPLICE BOLT LENGTH	
LOCATION	LENGTH
At posts	32
At structures	64





NOTES:

1 Base metal thickness of channel shall be 4.0mm nominal and 3.8mm minimum.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, STEEL BEAM CHANNEL COMPONENT

Nov 2016 | Rev 2


OPSD 912.102



KING OFFSET BLOCK
NOTE 1



MONDO OFFSET BLOCK
NOTE 2



P–BLOCK
NOTE 3

NOTES:


1 The component depicted is proprietary to Trinity Industries, Inc.

2 The component depicted is proprietary to Mondo Polymer Technologies.


3 The component depicted is proprietary to R.G. Steel Corp.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	4
GUIDE RAIL SYSTEM, STEEL BEAM PLASTIC OFFSET BLOCKS COMPONENT			
	OPSD 912.103		



ROUTED WOODEN OFFSET BLOCK




POST DETAIL

NOTES:


1 Imperial size steel sections W6x9 and W6x8.5 are acceptable.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev 3	ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL ·
GUIDE RAIL SYSTEM, STEEL BEAM STEEL POST WITH WOODEN OFFSET BLOCK COMPONENT			OPSD 912.104



PLAN




SECTION A–A

FOR SQUARE WOODEN POST FOR STEEL BEAM GUIDE RAIL


NOTES:

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	2
GUIDE RAIL SYSTEM, STEEL BEAM BASE PLATE COMPONENT			
	OPSD 912.105		




ROUTED WOODEN OFFSET BLOCK (SHOWN)
OR
PLASTIC OFFSET BLOCK
ACCORDING TO OPSD 912.103




POST DETAIL

NOTES:
1 Imperial size steel sections W6x9 or W6x8.5 are acceptable.
A Welds shall be according to CSA W59.
B Steel post and base plate shall be hot dip galvanized after manufacturing.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM TYPE M20 STEEL POST WITH OFFSET BLOCK AND BASE PLATE COMPONENT			
	OPSD 912.109		



FRONT ELEVATION




ENLARGED SECTION A–A
Note 1



SPLICE BOLT AND NUT
Note 2

TABLE 1	
MOUNTING BOLT LENGTH	
SBGR Type	Length mm
M20 Wood Post	460
M20 Steel Post	250
M30 Wood Post	560
M30 Steel Post	360



MOUNTING BOLT, WASHER, AND NUT

NOTES:

1 Base metal thickness of rail shall be 2.67mm nominal and 2.44mm minimum.

2 Splice bolt length shall be 38mm when connecting nested (double) rails.

A All dimensions subject to manufacturing tolerances unless otherwise indicated.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, STEEL BEAM TYPE M RAIL – 476mm HOLE SPACING COMPONENT


Nov 2016 | Rev 0

ONTARIO STANDARDS MUNICIPAL–PROVINCIAL

OPSD 912.123



ENLARGED SECTION A–A
NOTE 1



FRONT ELEVATION

NOTES:

1 Base metal thickness of rail shall be 2.67mm nominal and 2.44mm minimum.

A All dimensions subject to manufacturing tolerances unless otherwise indicated.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


Apr 2016 | Rev | 0

GUIDE RAIL SYSTEM, STEEL BEAM


TYPE M TRANSITION RAIL

COMPONENT


OPSD 912.124



FRONT ELEVATION




ENLARGED SECTION A–A
NOTE 1



SPLICE BOLT AND NUT
NOTE 2

TABLE 1	
MOUNTING BOLT LENGTH	
SBGR Type	Length mm
M20 Wood Post	460
M20 Steel Post	250
M30 Wood Post	560
M30 Steel Post	360



MOUNTING BOLT, WASHER, AND NUT

NOTES:

1 Base metal thickness of rail shall be 2.67mm nominal and 2.44mm minimum.

2 Splice bolt length shall be 38mm when connecting nested (double) rails.

A All dimensions subject to manufacturing tolerances unless otherwise indicated.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


Apr 2016 | Rev 0

GUIDE RAIL SYSTEM, STEEL BEAM


TYPE M RAIL

COMPONENT

OPSD 912.125



ROUTED WOODEN OFFSET BLOCK




POST DETAIL


NOTES:

1 Imperial size steel sections W6x9 or W6x8.5 are acceptable.
2 Post length shall be 2134mm when specified and when 2134mm long shall be stamped with a 50mm high number "7" in centre of web 50mm below top of post.
A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM STEEL POST FOR THRIE BEAM RAIL WITH 30cm OFFSET BLOCK COMPONENT			
	OPSD 912.126		



ROUTED WOODEN OFFSET BLOCK (SHOWN)
OR
PLASTIC OFFSET BLOCK
ACCORDING TO OPSD 912.103



POST DETAIL


NOTES:

1 Imperial size steel sections W6x9 or W6x8.5 are acceptable.


2 Post length shall be 2438mm when specified and when 2438mm long shall be stamped with a 50mm high number "8" in centre of web 50mm below top of post.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2016	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM **M20 STEEL POST WITH OFFSET BLOCK** COMPONENT			
	OPSD 912.127		



ROUTED WOODEN OFFSET BLOCK (SHOWN)
OR
PLASTIC OFFSET BLOCK
ACCORDING TO OPSD 912.129



POST DETAIL


NOTES:

1 Imperial size steel sections W6x9 or W6x8.5 are acceptable.


2 Post length shall be 2438mm when specified and when 2438mm long shall be stamped with a 50mm high number "8" in center of web 50mm below top of post.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM TYPE M30 STEEL POST WITH OFFSET BLOCK COMPONENT			
	OPSD 912.128		




PLAN



ISOMETRIC



ELEVATION




SECTION

NOTES:

A The component depicted is proprietary to Monroeville Industrial Molding.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM 30cm POLYMER OFFSET BLOCK – P–BLOCK COMPONENT	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 912.129		




PLAN


POST BOLT		
	Post Bolt Size and Type	Washer @ Nut
(A)	16x250 BH	Plate
(B)	16x100 CaB	Plate



PLAN




ELEVATION




SIDE VIEW

SINGLE RAIL



ELEVATION



SIDE VIEW

SINGLE RAIL WITH CHANNEL

NOTES:

1 Washer shall not be installed at front face of rail. One bolt located at centre of steel beam guide rail.

A This OPSD to be read in conjunction with OPSD 912.101, 912.102, 912.103, and 912.104.

B Steel beam guide rail mounting heights shall be as specified.


C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, STEEL BEAM STEEL POST WITH OFFSET BLOCK ASSEMBLY INSTALLATION – SINGLE RAIL


Nov 2016 | Rev 3

OPSD 912.130




NEW POST BOLTS		
	Post Bolt Size and Type	Washer @ Nut
Ⓐ	16x250 BH	Plate
Ⓑ	16x100 CaB	Plate






EXISTING SINGLE RAIL WITH STEEL OFFSET BLOCK



ADJUSTED SINGLE RAIL WITH NEW WOODEN OR PLASTIC OFFSET BLOCK



NOTES:

1 Washer shall not be installed at front face of rail. Type Ⓐ bolt located at centre of steel beam guide rail.

2 Steel beam guide rail mounting heights shall be as specified.

3 One new hole shall be punched as required to attach new offset block. Punching of second new hole is acceptable. New holes shall be treated according to ASTM A780. New holes shall not be flame cut.

A This OPSD shall be read in conjunction with OPSD 912.103 and 912.104.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, STEEL BEAM STEEL POST WITH STEEL OFFSET BLOCK ASSEMBLY ADJUSTMENT – SINGLE RAIL

Nov 2016 | Rev 1


ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS

OPSD 912.135




PLAN

	NEW POST BOLT AND HOLE	
	Hole Dia	Post Bolt Size and Type
Ⓐ	18	16x460 BH
Ⓑ	18	16x310 CaB




PLAN



ELEVATION SIDE VIEW

EXISTING SINGLE RAIL



ELEVATION SIDE VIEW

ADJUSTED SINGLE RAIL

NOTES:

1 Washer shall not be installed at front face of rail. Type Ⓐ bolt located at centre of steel beam guide rail.

2 Steel beam guide rail mounting heights shall be as specified.

3 The top of the offset block shall not extend beyond the top of the existing post.

4 One new hole shall be drilled as required to attach rail and new offset blocks. At locations where channel exists, an additional hole shall be drilled as required. Holes shall be treated with two applications of 2% copper naphthenate wood preservative.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, STEEL BEAM WOODEN POST ASSEMBLY ADJUSTMENT – SINGLE RAIL


Nov 2016 | Rev 1

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL


OPSD 912.145



PLAN



ELEVATION



SECTION A–A

NOTES:


1 Slope shall be flatter when specified.

2 Mounting height to top of steel beam shall be measured vertically at face of rail.

A System configuration meets AASHTO MASH TL–3.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM TYPE M20 INSTALLATION			
	OPSD 912.185		




PLAN

Traffic Flow



ELEVATION



SECTION A–A

NOTES:

1 Slope shall be flatter when specified.
2 Mounting height to top of steel beam rail shall be measured vertically at face of rail.
3 Offset from edge of shoulder to traffic side face of post shall be 280mm.
A System configuration meets AASHTO MASH TL–3.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, STEEL BEAM TYPE M20 – ADJACENT TO 2H:1V SLOPE INSTALLATION – RAIL AT SHOULDER


Nov 2016 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S


OPSD 912.186



PLAN



ELEVATION




SECTION A-A


NOTES:

1 Slope shall be flatter when specified.
2 Mounting height to top of steel beam rail shall be measured vertically at the edge of pavement.
A System configuration meets AASHTO MASH TL-3.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	1
GUIDE RAIL SYSTEM, STEEL BEAM TYPE M30-ADJACENT TO CONCRETE CURB INSTALLATION			
	OPSD 912.188		



PLAN



ELEVATION



SECTION A–A

NOTES:

1 Slope shall be flatter when specified.

2 Mounting height to top of steel beam rail shall be measured vertically at the edge of pavement.


3 Wider sidewalk when specified.

4 2.1m minimum when 1.8m wide sidewalk specified, 2.3m when 2.0m wide sidewalk specified.


A System configuration meets AASHTO MASH TL–2.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM TYPE M30 – ADJACENT TO SIDEWALK INSTALLATION			
	OPSD 912.189		




DETAIL A




DETAIL C




PLAN



DETAIL B




PLAN



ELEVATION SIDE VIEW

DETAIL D



ELEVATION

NOTES:

1 Steel bearing plate shall be secured against rotation using nails into post.

2 When channel specified, channel shall be terminated at post ③.

3 Minimum weight of post shall be 4.46kg/m.

4 Post and mounting hardware shall be hot dip galvanized according to CSA G164.

A Steel beam guide rail mounting heights shall be as specified.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2010 | Rev 1


GUIDE RAIL SYSTEM, STEEL BEAM

LEAVING END TREATMENT


INSTALLATION

ONTARIO STANDARD MUNICIPAL – PROVINCIAL


OPSD 912.235



PLAN



ELEVATION



POSTS (1) TO (6)

NOTES:

1 Type M rail, mounting hardware, and splice hardware shall be according to OPSD 912.125.

2 Wooden offset block dressed dimensions shall be 140mm wide x 360mm long x 305mm deep.

3 Wooden posts dressed dimensions shall be 140mm wide x 1829mm long x 184mm deep.

4 Mounting height to top of steel beam rail shall be measured vertically at face of rail.

5 Drive 16D double head nail through post and offset block.

6 The centre of the top hole shall be in line with the ground surface.

7 Slope shall be flatter when specified.

8 Type M SBGR includes Type M20 and Type M30. The minimum length of Type M SBGR to be installed upstream and downstream of the long span treatment shall be 19.05m.

9 Distance from face of rail to inside face of culvert headwall shall not be less than 900mm.

10 Obstacles shall not protrude more than 50mm above the finished grade.

A System configuration meets AASHTO MASH TL-3.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, STEEL BEAM TYPE M – 7.62m LONG SPAN TREATMENT INSTALLATION


Nov 2016 | Rev 0

ONTARIO STANDARDS MUNICIPAL-PROVINCIAL


OPSD 912.245



PLAN



ELEVATION



POSTS (1) TO (6)

NOTES:

1 Type M rail, mounting hardware, and splice hardware shall be according to OPSD 912.125.

2 Wooden offset block dressed dimensions shall be 140mm wide x 360mm long x 305mm deep.

3 Wooden posts dressed dimensions shall be 140mm wide x 1829mm long x 184mm deep.

4 Mounting height to top of steel beam rail shall be measured vertically at face of rail.

5 Drive 16D double head nail through post and offset block.

6 The centre of the top hole shall be in line with the ground surface.

7 Slope shall be flatter when specified.

8 Type M SBGR includes Type M20 and Type M30. The minimum length of Type M SBGR to be installed upstream and downstream of the long span treatment shall be 19.05m.


9 Distance from face of rail to inside face of culvert headwall shall not be less than 900mm.


10 Obstacles shall not protrude more than 50mm above the finished grade.

A System configuration meets AASHTO MASH TL-3.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM TYPE M – 5.715m LONG SPAN TREATMENT INSTALLATION			
	OPSD 912.246		





SECTION A–A

NOTES:

1 Mounting height to top of steel beam rail shall be measured vertically at face of rail.
2 Slope shall be flatter when specified.
3 Type M SBGR includes Type M20 and Type M30. The minimum length of Type M SBGR to be installed upstream and downstream of the long span treatment shall be 19.05m.
4 Obstacles shall not protrude more than 50mm above the finished grade.
5 Four 22mm ($\frac{7}{8}$") diameter A193 B7 Super HAS all threaded anchor rods 216mm ($8\frac{1}{2}$") long with washer and nut installed with Hilti RE500 V3 or equivalent epoxy. Holes for anchors shall be 25mm (1") diameter diamond core drilled.
A For precast culverts with distribution slab according to OPSD 3920.110, threaded rods shall be embedded 150mm into top of precast box culvert.
B For precast culverts with distribution slab according to OPSD 3920.110 waterproofing shall not be installed under or within 50mm of base plates.
C System configuration meets AASHTO MASH TL–3.
D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, STEEL BEAM TYPE M – BASE PLATED FOR SHALLOW BOX CULVERTS INSTALLATION


Nov 2019 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS


OPSD 912.249




SECTION A–A




PLAN




SHELF ANGLE BRACKET DETAIL



SECTION B–B



ELEVATION



SECTION C–C

NOTES:

1 Mounting height to top of steel beam shall be measured vertically at face of rail.

2 Rail is not bolted to post (1) and is supported by shelf angle bracket that is bolted to post (1).

A Splice and mounting hardware shall be according to OPSD 912.125.

B This OPSD shall be read in conjunction with OPSD 912.256 and 912.257.

C All dimensions subject to manufacturing tolerances unless otherwise shown.

D System configuration meets AASHTO MASH TL–3.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, STEEL BEAM TYPE M20 AND M30 LEAVING END TREATMENT INSTALLATION


Nov 2018 | Rev 1


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 912.255




STEEL BEAM GUIDE RAIL







ROUNDED TERMINAL




ENLARGED SECTION A–A
Note 1



CHANNEL STRUT



STEEL BEAM GUIDE RAIL
CABLE ATTACHMENT



SECTION B–B


NOTES:

1 Base metal thickness of rail shall be 2.67mm nominal and 2.44mm minimum.


A All dimensions subject to manufacturing tolerances unless otherwise shown.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	1
GUIDE RAIL SYSTEM, STEEL BEAM TYPE M20 AND M30 LEAVING END TREATMENT RAIL COMPONENTS			
	OPSD 912.256		



DETAIL A
(STRUTS NOT SHOWN FOR CLARITY)




STEEL BEARING PLATE DETAIL




ONE PIECE CABLE END **TWO PIECE CABLE END**

CABLE ASSEMBLY




FRONT VIEW **SIDE VIEW**

BREAKAWAY WOODEN POST



FRONT VIEW **SIDE VIEW**

POST ANCHOR TUBE
HSS 203.2x152.4x4.78
1829mm long




SNOW PLOW MARKER AND POST

NOTES:

1 Minimum weight of post shall be 4.46 kg/m.
2 Post and mounting hardware shall be hot dip galvanized after fabrication according to ASTM A 123.
3 Steel bearing plate shall be secured against rotation using nails into post.
A All dimensions subject to manufacturing tolerances unless otherwise shown.
B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM TYPE M20 AND M30 LEAVING END TREATMENT POST COMPONENTS			
			OPSD 912.257



ELEVATION

NOTES:

1 Type M SBGR includes Type M20 and Type M30.

A Mounting height to top of steel beam shall be measured vertically at face of rail.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, STEEL BEAM TRANSITION FROM TYPE M TO EXISTING STEEL BEAM GUIDE RAIL – INSTALLATION

Nov 2020 | Rev 0

OPSD 912.313



ELEVATION

NOTES:


1 Type M SBGR includes Type M20 and Type M30.

2 When transitioning to existing SBGR with channel, the height of the channel shall be adjusted and terminated over a length of 7.62m.

A Mounting height to top of steel beam measured vertically at face of rail.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2017	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM TRANSITION FROM TYPE M TO EXISTING STEEL BEAM GUIDE RAIL INSTALLATION			
	OPSD 912.314		



ELEVATION

NOTES:

1 Type M SBGR includes Type M20 and Type M30.

A Mounting height to top of steel beam shall be measured vertically at face of rail.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, STEEL BEAM TRANSITION FROM TYPE M TO STEEL BEAM GUIDE RAIL WITH CHANNEL FOR STRUCTURE CONNECTION–INSTALLATION


Nov 2016	Rev	0

ONTARIO STANDARDS · MUNICIPAL–PROVINCIAL · O P S


OPSD 912.315



PLAN



ELEVATION



SECTION A–A

NOTES:

1 Type M SBGR includes Type M20 and Type M30.
2 Mounting height to top of steel beam shall be measured vertically at face of rail.
3 When rigid obstacle extends beyond centre 3.81m length of rail, additional 3.81m lengths of rail with posts spaced at 476mm c/c shall be provided between 7.62m long transitions.
4 Post spacing at 476mm c/c.
5 Post spacing at 952mm c/c.
6 Slope shall be flatter when specified.

A Mounting height to top of steel beam rail shall be measured vertically at face of rail.
B System configuration meets AASHTO MASH TL–3.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2016 | Rev 0


GUIDE RAIL SYSTEM, STEEL BEAM TYPE M – REDUCED DEFLECTION TREATMENT INSTALLATION

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S


OPSD 912.316



PLAN



ELEVATION



SECTION A–A

NOTES:

1 Additional holes may be field drilled.

2 Flare rate of temporary transition rail and first precast concrete barrier unit shall be 16:1 or flatter.

3 Two anchorage back up rails only.

4 Where temporary transition rail cannot be connected at post it shall be connected to existing guide rail between posts using 6–M22 A230 bolts.

5 20mm dia removable anchor bolts each with an ultimate pullout value of 100kN in 30MPa concrete.

A For Steel Beam Guide Rail detail to be read in conjunction with OPSD–912.130, 912.140, or 912.141.

B When transitioning from a curb section onto a lower surface the temporary concrete barrier shall be supported to attain a grade of 10% or flatter.


C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2002 | Rev 1


GUIDE RAIL SYSTEM, STEEL BEAM
TEMPORARY TRANSITION INSTALLATION–RAIL METHOD
SINGLE STEEL BEAM TO TEMPORARY CONCRETE BARRIER

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL


OPSD – 912.330



PLAN



ELEVATION



SECTION A–A

NOTES:


1 22mm dia A490 bolts or equivalent strength threaded bar in 25mm dia holes.

A For Steel Beam Guide Rail detail to be read in conjunction with OPSD–912.130, 912.140, or 912.141.


B When transitioning from a curb section onto a lower surface the temporary concrete barrier shall be supported to attain a grade of 10% or flatter.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2002	Rev	1
GUIDE RAIL SYSTEM, STEEL BEAM TEMPORARY TRANSITION INSTALLATION SINGLE STEEL BEAM TO TEMPORARY CONCRETE BARRIER			
	OPSD – 912.331		



ELEVATION



PLAN

NOTES:

A Steel beam guide rail mounting heights shall be as specified.

B This OPSD to be read in conjunction with OPSD 912.141.


C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, STEEL BEAM PERMANENT TRANSITION INSTALLATION CHANNEL TERMINATION MEDIAN

Nov 2008 | Rev 1


OPSD 912.380




ANCHORAGE BACKUP RAIL




ANCHORAGE FRONT RAIL




STEEL BEARING PLATE DETAIL



CHANNEL



SECTION A–A



SECTION B–B

NOTES:

1 End sections shall be welded with 2.5mm fillets and standard guide rail element materials shall be used.

2 Channel with swaged end shall be used at structure approach and non–swaged end section shall be used at structure exit.

A All welds shall be according to CSA W59, low hydrogen classification, and ground smooth.

B This OPSD to be read in conjunction with OPSD 912.101 and 912.102.


C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2010 | Rev 1

GUIDE RAIL SYSTEM, STEEL BEAM STRUCTURE CONNECTION COMPONENT – RAIL AND CHANNEL


OPSD 912.401



PLAN



ELEVATION




SECTION A–A

NOTES:


A Base metal thickness of rail shall be 3.43mm nominal and 3.18mm minimum.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev 0
GUIDE RAIL SYSTEM, STEEL BEAM TERMINAL CONNECTOR COMPONENT		
		OPSD 912.402




LEAVING END APPROACH END ELEVATION




EXISTING CONCRETE BARRIER



EMBEDDED ANCHORAGE NEW CONCRETE BARRIER





BOLT THROUGH ANCHORAGE DETAIL

NOTES:

1 Horizontal and vertical transitions apply to structure approach and leaving end curb with gutter termination.
2 Channel post bolt at offset blocks to be 510mm long. End of bolts to be saw cut, flush with face of nut.
3 When channel is to be discontinued, a 7.62m termination shall commence at the third beam element joint beyond the end of approach slab.
4 Steel beam guide rail and channel to be field drilled to suit. Coat holes and bolt heads with approved zinc rich paint.
5 Wooden or steel posts as specified.
6 If curb or sidewalk in front of the barrier wall is 300mm or greater in width, the mounting height shall be measured vertically to the top of the concrete surface.


A This OPSD to be read in conjunction with OPSD 912.130, 912.140, 912.401, and 912.530.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2010 | Rev 3

GUIDE RAIL SYSTEM, STEEL BEAM STRUCTURE CONNECTION


OPSD 912.430



PLAN



ELEVATION




SECTION A–A


Notes:

1 Two thrie beam rails, one set inside the other.
2 Two steel beam rails, one set inside the other.
3 Toe nail top of offset block with two 16d galvanized nails, one on each side of post web and bend over post flange.
4 Structure connection for 3 tube railing on curb (MTO Structural Standard Drawing SS110–38).
5 Gutter outlets not permitted within 12m of structure.
A System configuration meets AASHTO MASH TL–3.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM STRUCTURE CONNECTION – 3 TUBE RAILING INSTALLATION			
	OPSD 912.450		



PLAN



ELEVATION




SECTION A–A


Notes:

1 Two thrie beam rails, one set inside the other.
2 Two steel beam rails, one set inside the other.
3 Toe nail top of offset block with two 16d galvanized nails, one on each side of post web and bend over post flange.
4 Structure connection for 4 tube combination traffic/bicycle railing on curb (MTO Structural Standard Drawing SS110–35, shown).
5 Gutter outlets not permitted within 12m of structure.
A System configuration meets AASHTO MASH TL–3.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM STRUCTURE CONNECTION – 4 TUBE RAILING INSTALLATION			
			OPSD 912.451



PLAN



ELEVATION



SECTION A–A

Notes:

1 Two thrie beam rails, one set inside the other.
2 Two steel beam rails, one set inside the other.
3 Toe nail top of offset block with two 16d galvanized nails, one on each side of post web and bend over post flange.
4 Structure connection for 4 tube railing on sidewalk (MTO Structural Standard Drawing SS110–47).
5 Gutter outlets not permitted within 12m of structure.
A System configuration meets AASHTO MASH TL–3.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, STEEL BEAM STRUCTURE CONNECTION – 4 TUBE RAILING WITH SIDEWALK, INSTALLATION


Nov 2019 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 912.452



PLAN



ELEVATION



CONCRETE TRANSITION WALL

NOTES:

1 Two SBGR elements one set inside the other for the first 5.21m length of guide rail on traffic approach to wingwall side only.

2 Two 150mm ID 8x230mm long steel spacer tubes, schedule 40 galvanized pipe connected only to SGBR and channel.

3 Six 25mm dia holes cast–in–place or drilled to receive 6–M22 x 310mm long A490 bolts.


4 Vertical transition required for connection to tall wall barrier or bridge wingwalls greater than 825mm high.

A Steel beam guide rail mounting heights shall be as specified.


B This OPSD to be read in conjunction with OPSD 912.130 and 912.140.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2008	Rev	2
GUIDE RAIL SYSTEM, STEEL BEAM PERMANENT CONNECTION INSTALLATION SINGLE STEEL BEAM TO CONCRETE BARRIER			
			OPSD 912.480



PLAN



ELEVATION



CONCRETE TRANSITION WALL

NOTES:

1 Two SBGR elements one set inside the other for the first 5.21m length of guide rail on traffic approach to wingwall side only.

2 Six 25mm dia holes cast–in–place or drilled to receive 6–M22 x 650mm long A490 bolts.


3 Vertical transition required for connection to tall wall barrier or bridge wingwalls greater than 825mm high.

A Steel beam guide rail mounting heights shall be as specified.


B This OPSD to be read in conjunction with OPSD 912.141.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2008	Rev	2
GUIDE RAIL SYSTEM, STEEL BEAM PERMANENT CONNECTION INSTALLATION DOUBLE STEEL BEAM TO CONCRETE BARRIER	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
		OPSD 912.481	




ROAD SHOULDER NARROWER THAN BRIDGE CLEARANCE PLUS CURB



ROAD SHOULDER SAME WIDTH AS BRIDGE CLEARANCE PLUS CURB



ROAD SHOULDER WIDER THAN BRIDGE CLEARANCE PLUS CURB



FOR SKEWED STRUCTURE:


The pavement taper is to end on a line at right angles to ℄ of highway, length of taper shall be measured from bridge corner that allows greatest length of tapered section.

NOTES:


1 Tangent to structure shall be one standard rail length +855mm long minimum. If approach slab is more than one standard beam element +855mm beyond wing wall, then tangent section shall be taken to end of approach slab.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	2
GUIDE RAIL SYSTEM, STEEL BEAM STRUCTURE APPROACH TREATMENT INSTALLATION – RURAL HIGHWAY			
	OPSD 912.530		




FRONT ELEVATION
Thrie Beam Rail – 3.81m Span



SPLICE BOLT AND NUT



FRONT ELEVATION
Thrie Beam Rail – 1.905m Span



ENLARGED SECTION A–A


NOTES:

1 Splice bolt length shall be 38mm when connecting nested (double) rails.

A Thrie beam rail elements shall be according to AASHTO M180 Type 2 and Class A. Base metal thickness of rail shall be 2.67mm nominal and 2.44mm minimum.

B All dimensions are in millmetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	0
GUIDE RAIL SYSTEM, STEEL BEAM THRIE BEAM RAIL – 476mm HOLE SPACING COMPONENT			
	OPSD 912.625		



NOTES:

A Transition rail elements shall be according to AASHTO M180 Type 2 and Class B. Base metal thickness of rail shall be 3.43mm nominal and 3.18mm minimum.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, STEEL BEAM
ASYMMETRIC TRANSITION RAIL COMPONENT

Nov 2019 | Rev 0


OPSD 912.630




TURN BUCKLE ASSEMBLY – TOP VIEW




END FITTING – SIDE VIEW




SECTION A–A




SECTION B–B




SECTION C–C




SPLICER – TOP VIEW




SPLICER – SIDE VIEW



WEDGE



PRESSED FERRULE AND CABLE FITTING



END VIEW

NOTES:

1 Uncompressed ferrule: length 90mm, diameter 30mm.
Compressed ferrule: length 100mm min, diameter 25mm min.

2 As an option, a square or hex nut may be welded to a 3/4"–10UNC–2A threaded bar.

A Dimensions of ferrous castings to have tolerance of ±0.7mm.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2008 | Rev 1

GUIDE RAIL SYSTEM, CABLE COMPONENT – CABLE FITTINGS


OPSD 913.101




EXISTING CABLE GUIDE RAIL




ADJUSTED CABLE GUIDE RAIL




CLAMP DETAIL



EXISTING POST DETAIL



ADJUSTED POST DETAIL



TURNBUCKLE DETAIL

NOTES:

1 Reflectorized strips as specified.

2 Ends of cable strands shall protrude past the end of the wedge 10mm.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, CABLE ADJUSTMENT – SHOULDER


Nov 2013	Rev	0

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPSS


OPSD 913.135



PLAN



ELEVATION



SECTION A–A

NOTES:

1 Height from ground to top of post shall be measured at face of post.
2 Slope shall be flatter when specified.
3 Top of steel anchor shall project 25 to 75mm above top of shoulder.
4 The longitudinal slope of the steel bottom plate shall match the gradient of the roadway.

A Delineation shall be according to OPSD 984.206 and OPSD 984.207.
B Bottom cable shall be hooked to posts ⑥, ⑦, ⑧, ⑨, and ⑩.
C Middle cable shall be hooked to posts ⑦, ⑧, ⑨, and ⑩.
D Top cable shall be hooked to posts ⑨, and ⑩.
E The system depicted here is a proprietary product.
F System configuration meets NCHRP Report 350 TL–3.
G All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, HIGH TENSION CABLE SAFENCE TERMINAL, 3–CABLE SLOPE INSTALLATION


Apr 2018 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • OPS

OPSD 913.220




PLAN



ELEVATION

NOTES:

1 Height from ground to top of post shall be measured at face of post.
2 Slope shall be flatter when specified.
3 Top of steel anchor shall project 25 to 75mm above top of shoulder.
4 Posts ① through ⑧ shall be installed in a straight line and posts ⑨ through ⑫ on a 400m radii. Measurements are from edge of shoulder to face of cable.
5 The longitudinal slope of the steel bottom plate shall match the gradient of the roadway.
A Delineation shall be according to OPSD 984.206 and OPSD 984.207.
B Bottom cable shall be hooked to posts ⑥, ⑦, ⑧, ⑨, and ⑩.
C Middle cable shall be hooked to posts ⑦, ⑧, ⑨, and ⑩.
D Top cable shall be hooked to posts ⑨, and ⑩.
E The system depicted here is a proprietary product.
F System configuration meets NCHRP Report 350 TL–3.
G All dimensions are in millimetres unless otherwise shown.




SECTION A–A

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, HIGH TENSION CABLE SAFENCE TERMINAL, 3–CABLE SHOULDER INSTALLATION

Apr 2018 | Rev 0

OPSD 913.221



ELEVATION




PLAN


NOTES:

A The components depicted here are proprietary.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2018	Rev	0
GUIDE RAIL SYSTEM, HIGH TENSION CABLE SAFENCE TERMINAL, 3–CABLE TERMINAL POSTS – COMPONENT	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 913.222		



ELEVATION



FRONT ELEVATION




PLAN


NOTES:

A The components depicted here are proprietary.
B Steel components hot dip galvanized according to ASTM A123.
C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2018	Rev	0
GUIDE RAIL SYSTEM, HIGH TENSION CABLE SAFENCE TERMINAL STEEL ANCHOR ASSEMBLY – COMPONENT	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 913.226		



PLAN



ELEVATION

TABLE 1	
CABLE TEMPERATURE (°C)	CABLE TENSION (kN)
−40	31.4
−30	28.4
−20	25.5
−10	22.5
0	19.6
+10	16.7
+20	13.7
+30	10.8
+40	7.8

NOTES:

1 Each end of the installation shall be anchored by a high tension cable guide rail terminal according to OPSD 913.221.

2 Line posts and grading shall be according to OPSD 913.253.

A Tension in 19mm diameter cables shall be according to Table 1.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–3.


D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


GUIDE RAIL SYSTEM, HIGH TENSION CABLE SAFENCE, 3–CABLE SHOULDER INSTALLATION

Apr 2018 | Rev 0

OPSD 913.250



PLAN



ELEVATION

TABLE 1	
CABLE TEMPERATURE (°C)	CABLE TENSION (kN)
−40	31.4
−30	28.4
−20	25.5
−10	22.5
0	19.6
+10	16.7
+20	13.7
+30	10.8
+40	7.8

NOTES:

1 Each end of the installation shall be anchored by a high tension cable guide rail terminal according to OPSD 913.220.

2 Line posts and grading shall be according to OPSD 913.252.

A Tension in 19mm diameter cables shall be according to Table 1.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–3.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, HIGH TENSION CABLE SAFENCE, 3–CABLE SLOPE INSTALLATION

Apr 2018 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 913.251




NOTES:

1 Desirable 3H:1V or flatter slope. Minimum 2H:1V slope when specified.
2 Cable hook shall be inserted into hole with rubber grommet.
3 Face of post shall not be offset more than 200mm beyond the rounding breakpoint.

A The components depicted here are proprietary.
B ASTM A1011 Grade 60 steel post hot dip galvanized according to ASTM F1043.
C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2018	Rev	0
GUIDE RAIL SYSTEM, HIGH TENSION CABLE SAFENCE, 3–CABLE SLOPE INSTALLATION LINE POST COMPONENT			
	OPSD 913.252		



NOTES:

1 Desirable 3H:1V or flatter slope. Minimum 2H:1V slope when specified.


2 Cable hook shall be inserted into hole with rubber grommet.


A The components depicted here are proprietary.

B ASTM A1011 Grade 60 steel post hot dip galvanized according to ASTM F1043.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2018	Rev	0
GUIDE RAIL SYSTEM, HIGH TENSION CABLE SAFENCE, 3–CABLE SHOULDER INSTALLATION LINE POST COMPONENT			
	OPSD 913.253		





SECTION A–A

Table 1, Note 3	
Y	X
< 300mm	1.5m
300 to 500mm	1.0m

NOTES:

1 Reduced line post spacing shall be provided at locations specified. Reduced line post spacing width, X, shall be according to Table 1. Reduced line post spacing to continue to first full length line post on both sides of the buried obstacle.

2 Line post shall be cut to the length specified. The damaged galvanized coating at the cut end shall be repaired according to ASTM A 780.

3 A single line post with cutting length of 100 to 700 mm will not require a line post spacing reduction if surrounded by a minimum of five uncut line posts with standard length on each side.

4 For installations where obstacle projects from side slope, distance from face of cables to exposed obstacle shall be greater than 2.1m.

5 Minimum clearance for installations over concrete box culverts.

6 Minimum clearance for installations over circular culverts.

A All dimensions are in millimetres unless otherwise shown.

Legend

Y1 – Standard line post length, OPSD 913.252 or OPSD 913.253
Y2 – Cut line post length, Note 2
Y – Cutting length (Y1–Y2)


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, HIGH TENSION CABLE SAFENCE, 3–CABLE BURIED OBSTACLE TREATMENT INSTALLATION


Apr 2018 | Rev 0

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL


OPSD 913.255



PLAN



SECTION A–A



SECTION B–B

NOTES:

1 When concrete barrier is used around piers, a 1.0m wide paved area is required in front of barrier.

2 Length varies depending on the length of energy attenuator plus the length of barrier transition required to accommodate the width of hazard.

3 Traffic barriers as specified.

4 Delineators shall be installed at 1.5m intervals at the leaving end of the energy attenuator.

A Delineation shall be according to OPSD 984.101.


B Drainage as required.

C All dimensions are in millimetres unless otherwise shown.

LEGEND:

X = distance from edge of driving lane to ℄ of energy attenuator

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	2
ENERGY ATTENUATOR, GENERAL INSTALLATION–GRANULAR APPROACH PAD, MEDIAN			
			OPSD 921.101



NOTES:

1 Top of anchor bolt shall not project above concrete pad surface by more than 40mm.

A Delineation shall be according to OPSD 984.204.

B The system depicted here is a proprietary product.

C The system shall be anchored to concrete pad and rear cable anchor block detailed in OPSD 922.133.

D Right side installation is shown. Left side installation is inverse of that shown.

E System configuration meets NCHRP Report 350 TL–3.

F This OPSD shall be read in conjunction with OPSD 202.033.

G All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADTREND SYSTEM INSTALLATION – CONCRETE BARRIER

Nov 2011 | Rev 2

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPSD

OPSD 922.131



NOTES:

1 Top of anchor block shall match embankment slope.

A All reinforcing shall be 15M reinforcing steel bars.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADTREND SYSTEM INSTALLATION – CONCRETE PAD AND REAR CABLE ANCHOR BLOCK


Nov 2011 | Rev 2

OPSD 922.133



PLAN

Traffic flow



ELEVATION

NOTES:

1 This OPSD shows right shoulder installation. The MSRT shall be inverted for left shoulder installation.

2 Guide rail panels shall not be attached to posts 2 to 7.

3 Rails shall be installed in a straight line between post 1 and rail splice between posts 11 and 12. Offset from edge of shoulder to face of post 1 is 1.22m.

4 Type M SBGR includes type M20 and Type M30.

5 This OPSD shows right shoulder approach end installation with rail element splices lapped in direction of traffic. For leaving end installations, rail element splices shall be lapped in direction of traffic.

A Delineation shall be according to OPSD 984.201 and 984.202.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL-3.

D This OPSD shall be read in conjunction with OPSD 202.037 and 202.038.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, END TERMINAL STEEL BEAM TERMINAL MASH SLOTTED RAIL TERMINAL SYSTEM INSTALLATION

Apr 2018 | Rev 1

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL

OPSD 922.150



NOTES:

1 This OPSD shows right shoulder installation. The MASH SoftStop Terminal shall be inverted for left shoulder installation.

2 The system length shall be installed in a straight line at a 50:1 flare rate or parallel to roadway when specified.

3 Type M SBGR includes Type M20 and Type M30.

4 This OPSD shows right shoulder approach end installation with rail element splices lapped in direction of traffic. For leaving end installations, rail elements splices shall be lapped in direction of traffic.

A Delineation shall be according to OPSD 984.201 and 984.202.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–3.

D This OPSD shall be read in conjunction with OPSD 202.031 or 202.032 as specified.

E All dimensions are in millimetres unless otherwise shown.


Table 1	
Steel Yielding Terminal Post	
Post	Length (m)
1	1.46
2	1.83

ONTARIO PROVINCIAL STANDARD DRAWING


ENERGY ATTENUATOR, END TREATMENT STEEL BEAM ENERGY ATTENUATING TERMINAL MASH SOFTSTOP TERMINAL SYSTEM INSTALLATION

Nov 2022 | Rev 2

OPSD 922.165



PLAN



ELEVATION

NOTES:

1 This OPSD shows right shoulder installation. The Max–Tension Terminal shall be inverted for left shoulder installation.
2 The system length shall be installed in a straight line at a 50:1 flare rate, or parallel to roadway when specified.
3 Type M SBGR includes Type M20 and Type M30.
4 This OPSD shows right shoulder approach installation with rail element splices lapped in direction of traffic. For leaving end installations, rail elements shall be lapped in direction opposite of traffic.

A Delineation shall be according to OPSD 984.201 and 984.202.
B The system depicted here is a proprietary product.
C This OPSD shall be read in conjunction with OPSD 202.031 or 202.032 as specified.
D System configuration meets AASHTO MASH TL–3.
E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, END TREATMENT STEEL BEAM ENERGY ATTENUATING TERMINAL MASH MAX–TENSION TERMINAL SYSTEM INSTALLATION

Nov 2018 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 922.171



NOTES:

1 This OPSD shows right shoulder installation. The MSKT shall be inverted for left shoulder installation.
2 The system length shall be installed in a straight line at a 50:1 flare rate or parallel to roadway when specified
3 Type M SBGR includes Type M20 and Type M30.
4 Imperial size steel sections referenced.
5 This OPSD shows right shoulder approach end installation with rail element splices lapped in direction of traffic. For leaving end installation, rail element splices shall be lapped in direction of traffic.
A Delineation shall be according to OPSD 984.201 and 984.202.
B The system depicted here is a proprietary product.
C System configuration meets AASHTO MASH TL–3.
D This OPSD shall be read in conjunction with OPSD 202.031 or 202.032 as specified.
E All dimensions are in millimetres unless otherwise shown.

Table 1		
Hinged Steel End Posts, Note 4		
Post	1	2
Lower	W6x15 1.8m long	W6x9 1.8m long


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, END TREATMENT STEEL BEAM ENERGY ATTENUATING TERMINAL MASH SEQUENTIAL KINKING TERMINAL SYSTEM – INSTALLATION

Nov 2018 | Rev 1


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S

OPSD 922.186




PLAN

CONCRETE PAD FOR TL-3 SYSTEM CONFIGURATION



PLAN

CONCRETE PAD FOR TL-2 SYSTEM CONFIGURATION



SECTION A-A

NOTES:

A All reinforcing shall be 15M reinforcing steel bars.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2011 | Rev 3

ENERGY ATTENUATOR, CRASH CUSHION NARROW SYSTEMS COMPONENT – REINFORCED CONCRETE PAD

OPSD 923.001



DETAIL
STEEL ANCHOR PLATE OPTIONS


NOTES:

1 Modified temporary concrete barrier shall be anchored to the pavement using six steel anchor plates according to system manufacturer's specifications.

2 Steel anchor plate depicted here is a proprietary product.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	2
ENERGY ATTENUATOR, CRASH CUSHION COMPONENT–ANCHOR ASSEMBLY			
	OPSD 923.002		




PLAN

CONCRETE PAD FOR TL-3 SYSTEM CONFIGURATION



PLAN



SECTION A-A


CONCRETE PAD FOR TL-2 SYSTEM CONFIGURATION

NOTES:

A All reinforcing shall be 15M deformed reinforcing steel bars.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	1
ENERGY ATTENUATOR, CRASH CUSHION WIDE SYSTEMS COMPONENT – REINFORCED CONCRETE PAD			
	OPSD 923.004		




PLAN

CONCRETE PAD FOR TL–3 SYSTEM CONFIGURATION



PLAN

CONCRETE PAD FOR TL–2 SYSTEM CONFIGURATION



SECTION A–A

NOTES:

A All reinforcing shall be 15M deformed reinforcing steel bars.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION EXTRA WIDE SYSTEMS COMPONENT – REINFORCED CONCRETE PAD

Nov 2021 | Rev 1


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 923.005



PLAN

CONCRETE PAD FOR TL–3 SYSTEM CONFIGURATION



SECTION A–A

NOTES:

A All reinforcing shall be 15M deformed reinforcing steel bars.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2021 | Rev 1

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD SUPER WIDE SYSTEM COMPONENT – REINFORCED CONCRETE PAD


OPSD 923.006



PLAN VIEW



ELEVATION VIEW



SECTION A–A

NOTES:

A All reinforcing steel bar shall be 15M unless otherwise shown.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD M10 WIDE SYSTEM, COMPONENT REINFORCED CONCRETE PAD

Nov 2021 | Rev 0

OPSD 923.007



PLAN VIEW



ELEVATION VIEW

SECTION A–A

NOTES:

A All reinforcing steel bar shall be 15M unless otherwise shown.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION HERCULES SYSTEM, COMPONENT REINFORCED CONCRETE PAD

Nov 2021 | Rev 0


OPSD 923.008



PLAN


CONCRETE PAD FOR TL–3 SYSTEM CONFIGURATION

Traffic flow



PLAN

CONCRETE PAD FOR TL–2 SYSTEM CONFIGURATION



SECTION A–A

NOTES:

A All reinforcing steel bar shall be 15M unless otherwise shown.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


ENERGY ATTENUATOR, CRASH CUSHION NARROW SYSTEMS

COMPONENT–REINFORCED PRECAST CONCRETE PAD FOR PERMANENT INSTALLATION


Apr 2022 | Rev | 1

ONTARIO STANDARD • MUNICIPAL – PROVINCIAL •


OPSD 923.010



PLAN



INSTALLATION




SECTION A–A

NOTES:

A All reinforcing steel bar shall be 15M unless otherwise shown.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2022	Rev	1
ENERGY ATTENUATOR, CRASH CUSHION COMPONENT–REINFORCED PRECAST CONCRETE PAD FOR MODIFIED TEMPORARY CONCRETE BARRIER			
	OPSD 923.011		



NOTES:

1 The system shall be anchored to a concrete pad as detailed in OPSD 923.007. Anchors shall be according to the manufacturer's specifications.

2 Maximum width of object shall be 1658mm for the first 762mm behind the rear fender panels.

A Delineation shall be according to OPSD 984.204.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–3.

D All dimensions are in millimeters unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD M10 WIDE SYSTEM INSTALLATION – PERMANENT UNIDIRECTIONAL


Nov 2021 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 923.141



PLAN



ELEVATION

NOTES:

1 The system shall be anchored to concrete pad detailed in OPSD 923.004.
2 Maximum width of object shall be 1658mm for the first 762mm behind the rear fender panels.

A Delineation shall be according to OPSD 984.204.
B The system depicted here is a proprietary product.
C System configuration meets NCHRP Report 350 test level.
D All dimensions are in millimetres unless otherwise shown.

TABLE 1

SYSTEM CONFIGURATION	PLASTIC NOSE		STEEL NOSE	
	TL–2	TL–3	TL–2	TL–3
TYPE I CARTRIDGES FRONT REQ'D	3	4	3	3
TYPE II CARTRIDGES REAR REQ'D	1	3	1	3
SYSTEM LENGTH	4000	6740	4000	5780
NOMINAL SYSTEM WIDTH	1755	1755	1755	1755


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD WIDE SYSTEM INSTALLATION – PERMANENT BIDIRECTIONAL


Nov 2011 | Rev 0

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · O P S

OPSD 923.187



PLAN



ELEVATION

NOTES:

1 When system is placed on a concrete pad, the pad shall be according to OPSD 923.005.
2 Adjacent temporary concrete barriers shall be modified and anchored according to OPSD 923.002.
3 Maximum width of object shall be 2200mm for the first 762mm behind the rear fender panels.

A Delineation shall be according to OPSD 984.203.
B The system depicted here is a proprietary product.
C System configuration meets NCHRP Report 350 test level.
D All dimensions are in millimetres unless otherwise shown.

TABLE 1

SYSTEM CONFIGURATION	PLASTIC NOSE		STEEL NOSE	
	TL–2	TL–3	TL–2	TL–3
TYPE I CARTRIDGES FRONT REQ'D	3	4	3	3
TYPE II CARTRIDGES REAR REQ'D	1	3	1	3
SYSTEM LENGTH	4000	6740	4000	5780
NOMINAL SYSTEM WIDTH	2285	2285	2285	2285


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD EXTRA WIDE SYSTEM INSTALLATION – TEMPORARY UNIDIRECTIONAL

Nov 2011 | Rev 0

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · O P S

OPSD 923.188



NOTES:

1 When system is placed on a concrete pad, the pad shall be according to OPSD 923.005.
2 Adjacent temporary concrete barrier units shall be modified and anchored according to OPSD 923.002.
3 Maximum width of object shall be 2200mm for the first 762mm behind the rear fender panels.

A Delineation shall be according to OPSD 984.203.
B The system depicted here is a proprietary product.
C System configuration meets NCHRP Report 350 test level.
D All dimensions are in millimetres unless otherwise shown.

TABLE 1

SYSTEM CONFIGURATION	PLASTIC NOSE		STEEL NOSE	
	TL–2	TL–3	TL–2	TL–3
TYPE I CARTRIDGES FRONT REQ'D	3	4	3	3
TYPE II CARTRIDGES REAR REQ'D	1	3	1	3
SYSTEM LENGTH	4000	6740	4000	5780
NOMINAL SYSTEM WIDTH	2285	2285	2285	2285


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD EXTRA WIDE SYSTEM INSTALLATION – TEMPORARY BIDIRECTIONAL


Nov 2011 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS

OPSD 923.189



PLAN



ELEVATION

NOTES:

1 The system shall be anchored to concrete pad detailed in OPSD 923.005.
2 Maximum width of object shall be 2200mm for the first 762mm behind the rear fender panels.

A Delineation shall be according to OPSD 984.204.
B The system depicted here is a proprietary product.
C System configuration meets NCHRP Report 350 test level.
D All dimensions are in millimetres unless otherwise shown.

TABLE 1

SYSTEM CONFIGURATION	PLASTIC NOSE		STEEL NOSE	
	TL–2	TL–3	TL–2	TL–3
TYPE I CARTRIDGES FRONT REQ'D	3	4	3	3
TYPE II CARTRIDGES REAR REQ'D	1	3	1	3
SYSTEM LENGTH	4000	6740	4000	5780
NOMINAL SYSTEM WIDTH	2285	2285	2285	2285


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD EXTRA WIDE SYSTEM INSTALLATION – PERMANENT UNIDIRECTIONAL


Nov 2011 | Rev 0

ONTARIO STANDARD MUNICIPAL – PROVINCIAL

OPSD 923.190



PLAN



ELEVATION

NOTES:

1 The system shall be anchored to concrete pad detailed in OPSD 923.005.
2 Maximum width of object shall be 2200mm for the first 762mm behind the rear fender panels.

A Delineation shall be according to OPSD 984.204.
B The system depicted here is a proprietary product.
C System configuration meets NCHRP Report 350 test level.
D All dimensions are in millimetres unless otherwise shown.

TABLE 1

SYSTEM CONFIGURATION	PLASTIC NOSE		STEEL NOSE	
	TL–2	TL–3	TL–2	TL–3
TYPE I CARTRIDGES FRONT REQ'D	3	4	3	3
TYPE II CARTRIDGES REAR REQ'D	1	3	1	3
SYSTEM LENGTH	4000	6740	4000	5780
NOMINAL SYSTEM WIDTH	2285	2285	2285	2285


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD EXTRA WIDE SYSTEM INSTALLATION – PERMANENT BIDIRECTIONAL

Nov 2011 | Rev 0

ONTARIO STANDARD MUNICIPAL – PROVINCIAL

OPSD 923.191



NOTES:

1 When system is placed on a concrete pad, the pad shall be according to OPSD 923.006.
2 Adjacent temporary concrete barrier units shall be modified and anchored according to OPSD 923.002.
3 Maximum width of object shall be 3200mm immediately behind the system. The sides of the objects shall taper rearward at a maximum 10° angle. Rear fender panels shall be able to slide rearward 762mm minimum.

A Delineation shall be according to OPSD 984.203.
B The system depicted here is a proprietary product.
C System configuration meets NCHRP Report 350 test level.
D All dimensions are in millimetres unless otherwise shown.

TABLE 1	
SYSTEM CONFIGURATION	TL–3
TYPE I CARTRIDGES FRONT REQ'D	4
TYPE II CARTRIDGES REAR REQ'D	3
SYSTEM LENGTH	6740
NOMINAL SYSTEM WIDTH	3200


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD SUPER WIDE SYSTEM INSTALLATION – TEMPORARY UNIDIRECTIONAL

Nov 2015 | Rev 0

ONTARIO STANDARDS · MUNICIPAL–PROVINCIAL · O P S

OPSD 923.192



NOTES:

1 When system is placed on a concrete pad, the pad shall be according to OPSD 923.006.
2 Adjacent temporary concrete barrier units shall be modified and anchored according to OPSD 923.002.
3 Maximum width of object shall be 3200mm immediately behind the system. The sides of the objects shall taper rearward at a maximum 10° angle. Rear fender panels shall be able to slide rearward 762mm minimum.

A Delineation shall be according to OPSD 984.203.
B The system depicted here is a proprietary product.
C System configuration meets NCHRP Report 350 test level.
D All dimensions are in millimetres unless otherwise shown.

TABLE 1	
SYSTEM CONFIGURATION	TL–3
TYPE I CARTRIDGES FRONT REQ'D	4
TYPE II CARTRIDGES REAR REQ'D	3
SYSTEM LENGTH	6740
NOMINAL SYSTEM WIDTH	3200


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD SUPER WIDE SYSTEM INSTALLATION – TEMPORARY BIDIRECTIONAL

Nov 2015 | Rev 0

ONTARIO STANDARDS MUNICIPAL–PROVINCIAL

OPSD 923.193



NOTES:

1 The system shall be anchored to concrete pad detailed in OPSD 923.006.

2 Maximum width of object shall be 3200mm immediately behind the system. The sides of the objects shall taper rearward at a maximum 10° angle. Rear fender panels shall be able to slide rearward 762mm minimum.

A Delineation shall be according to OPSD 984.204.

B The system depicted here is a proprietary product.

C System configuration meets NCHRP Report 350 test level.

D All dimensions are in millimetres unless otherwise shown.

TABLE 1	
SYSTEM CONFIGURATION	TL–3
TYPE I CARTRIDGES FRONT REQ'D	4
TYPE II CARTRIDGES REAR REQ'D	3
SYSTEM LENGTH	6740
NOMINAL SYSTEM WIDTH	3200


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD SUPER WIDE SYSTEM INSTALLATION – PERMANENT UNIDIRECTIONAL

Nov 2015 | Rev | 0

ONTARIO STANDARDS MUNICIPAL–PROVINCIAL

OPSD 923.194



NOTES:

1 The system shall be anchored to concrete pad detailed in OPSD 923.006.
2 Maximum width of object shall be 3200mm immediately behind the system. The sides of the objects shall taper rearward at a maximum 10° angle. Rear fender panels shall be able to slide rearward 762mm minimum.

A Delineation shall be according to OPSD 984.204.
B The system depicted here is a proprietary product.
C System configuration meets NCHRP Report 350 test level.
D All dimensions are in millimetres unless otherwise shown.

TABLE 1	
SYSTEM CONFIGURATION	TL–3
TYPE I CARTRIDGES FRONT REQ'D	4
TYPE II CARTRIDGES REAR REQ'D	3
SYSTEM LENGTH	6740
NOMINAL SYSTEM WIDTH	3200


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD SUPER WIDE SYSTEM INSTALLATION – PERMANENT BIDIRECTIONAL

Nov 2015 | Rev | 0


ONTARIO STANDARDS MUNICIPAL–PROVINCIAL

OPSD 923.195




PLAN

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
M10 TYPE I CARTRIDGES FRONT REQUIRED	3	4
M10 TYPE II CARTRIDGES REAR REQUIRED	1	3
SYSTEM LENGTH	3960	6710



ELEVATION



SECTION A–A

NOTES:

1 When system is placed on a concrete pad, the pad shall be according to OPSD 923.001.

2 Anchors shall be according to the manufacturer's specifications.

3 Adjacent temporary concrete barrier unit shall be modified and anchored according to OPSD 923.002.

A Delineation shall be according to OPSD 984.203.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–2 or TL–3 (Table 1).

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD M10 SYSTEM INSTALLATION – TEMPORARY UNIDIRECTIONAL


Nov 2021 | Rev 0

ONTARIO STANDARDS • MUNICIPAL–PROVINCIAL •

OPSD 923.196




PLAN



ELEVATION

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
M10 TYPE I CARTRIDGES FRONT REQUIRED	3	4
M10 TYPE II CARTRIDGES REAR REQUIRED	1	3
SYSTEM LENGTH	3960	6710



SECTION A–A

NOTES:

1 When system is placed on a concrete pad, the pad shall be according to OPSD 923.001.

2 Anchors shall be according to the manufacturer's specifications.

3 Adjacent temporary concrete barrier unit shall be modified and anchored according to OPSD 923.002.

A Delineation shall be according to OPSD 984.203.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–2 or TL–3 (Table 1).

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD M10 SYSTEM INSTALLATION – TEMPORARY BIDIRECTIONAL

Nov 2021 | Rev 0


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 923.197




PLAN

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
M10 TYPE I CARTRIDGES FRONT REQUIRED	3	4
M10 TYPE II CARTRIDGES REAR REQUIRED	1	3
SYSTEM LENGTH	3960	6710



ELEVATION



SECTION A–A

NOTES:

1 The system shall be anchored to a concrete pad as detailed in OPSD 923.001.

2 Anchors shall be according to the manufacturer's specifications.

A Delineation shall be according to OPSD 984.204.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–2 or TL–3 (Table 1).

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD M10 SYSTEM INSTALLATION – PERMANENT UNIDIRECTIONAL

Nov 2021 | Rev 0


ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL ·

OPSD 923.198




PLAN

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
M10 TYPE I CARTRIDGES FRONT REQUIRED	3	4
M10 TYPE II CARTRIDGES REAR REQUIRED	1	3
SYSTEM LENGTH	3960	6710



ELEVATION



SECTION A–A

NOTES:

1 The system shall be anchored to a concrete pad as detailed in OPSD 923.001.
2 Anchors shall be according to the manufacturer's specifications.
A Delineation shall be according to OPSD 984.204.
B The system depicted here is a proprietary product.
C System configuration meets AASHTO MASH TL–2 or TL–3 (Table 1).
D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION QUADGUARD M10 SYSTEM INSTALLATION – PERMANENT BIDIRECTIONAL

Nov 2021 | Rev 0


ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL ·

OPSD 923.199




STEEL CYLINDERS: A,B,C STEEL CYLINDERS: D,E,F,G


TOP VIEWS



SECTION A–A




SECTION B–B




SIDE VIEW **TOP VIEW**

LID SUPPORT ANGLE DETAIL



LIFTING DEVICE DETAIL



STEEL CYLINDERS: A,B,C STEEL CYLINDERS: D,E,F,G

ISOMETRIC VIEWS

NOTE:

A No internal reinforcing in cylinder types H to N.


B All dimensions are in millimetres unless otherwise shown.

STEEL CYLINDERS			
CYLINDERS	OD	HEIGHT	WALL THICKNESS
A,B,C	1220	1218	6.4
D,E	1220	1218	7.9
F,G,H I,J,K,N	1220	1218	4.8
L,M	914	1218	4.2


ONTARIO PROVINCIAL STANDARD DRAWING | Nov 2013 | Rev 2

ENERGY ATTENUATOR, CRASH CUSHION CONNECTICUT IMPACT ATTENUATION SYSTEM COMPONENT – STEEL CYLINDER


OPSD 923.201




CYLINDERS–914mm DIA




CYLINDERS–1220mm DIA




SIDE VIEW




TOP VIEW



DETAIL A



DETAIL B



DETAIL C

POLYETHYLENE LID

NOTES:

1 For 914mm cylinder lid, cut along trim line as shown.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


ENERGY ATTENUATOR, CRASH CUSHION CONNECTICUT IMPACT ATTENUATION SYSTEM COMPONENT – POLYETHYLENE LID

Nov 2013 | Rev 2

OPSD 923.202



SIDE VIEW



FRONT VIEW

LEGEND:

BF – Back Face

FF – Front Face

NOTES:

1 Bars D and F shall extend a minimum of 300mm below grade.

A All reinforcing steel bar splices shall have a minimum overlap of 300mm.

B All reinforcing steel bars shall be size 15M. All right angle bends shall have a minimum radius of 80mm.

C All reinforcing steel bars shall have 70mm minimum cover.

D All dimensions are in millimetres unless otherwise shown.

REINFORCEMENT OF CONCRETE BACKWALL			
BAR	LENGTH	SHAPE	NO. REQ'D
A	1820	1070, 375	8
B	3400	450, 1475	8
C	2670	2670	2
D	700	700	8
E	500	250, 250	4
F	1450	1450	8


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION CONNECTICUT IMPACT ATTENUATION SYSTEM COMPONENT – CONCRETE BACKWALL


Nov 2013 | Rev 2

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS


OPSD 923.204




PLAN




DETAIL C



ELEVATION




SECTION A–A




DETAIL A



STEEL RAIL DETAIL



DETAIL B



SECTION B–B

NOTES:

1 Stud shall extend beyond nut by not more than 10mm.

2 Bolt head shall be flush or below top of rail.

A Delineation shall be according to OPSD 984.205.

B System configuration meets NCHRP Report 350 TL–3.

C For SBGR connection to concrete backwall refer to OPSD 923.245.

D This OPSD shall be read in conjunction with OPSD 923.201, 923.202, and 923.204.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION CONNECTICUT IMPACT ATTENUATION SYSTEM INSTALLATION


Nov 2013 | Rev 2

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPS


OPSD 923.242



PLAN



SBGR CONNECTION DETAIL



MEDIAN

NOTES:

1 Where additional SBGR panels are required, post spacing shall be 950mm as shown.

2 Six 3/4" diameter ISO 898–1 Class 5.8 threaded rods with washer and nut into Hilti Hit–RE 500 adhesive anchoring system with a minimum 125mm embedment depth. Nuts shall not be torqued until epoxy has cured. Anchoring system shall be installed according to the manufacturer's specifications by an installer trained by the manufacturer's direct representative.

3 For shorter installations, concrete barrier shall be used between the concrete backwalls.

4 Cross slopes shall be 6% or flatter.

A This OPSD shall be read in conjunction with OPSD 921.101 and 923.242.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION CONNECTICUT IMPACT ATTENUATION SYSTEM INSTALLATION – LONG MEDIAN HAZARD


Nov 2021 | Rev 2

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 923.244



PLAN



SBGR CONNECTION DETAIL



MEDIAN

NOTES:

1 Where additional SBGR panels are required, post spacing shall be 950mm as shown.

2 Six 3/4" diameter ISO 898–1 Class 5.8 threaded rods with washer and nut into Hilti Hit–RE 500 adhesive anchoring system with a minimum 125mm embedment depth. Nuts shall not be torqued until epoxy has cured. Anchoring system shall be installed according to the manufacturer's specifications by an installer trained by the manufacturer's direct representative.

3 For shorter installations, concrete barrier shall be used between the concrete backwalls.

4 Cross slopes shall be 6% or flatter.

A This OPSD shall be read in conjunction with OPSD 921.101 and 923.242.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION CONNECTICUT IMPACT ATTENUATION SYSTEM INSTALLATION – SHORT MEDIAN HAZARD


Nov 2021 | Rev 3

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL ·

OPSD 923.245



PLAN



ELEVATION

NOTES:

1 When system is placed on a concrete pad, the pad shall be according to OPSD 923.004.
2 Adjacent temporary concrete barriers shall be modified and anchored according to OPSD 923.002.
3 Maximum width of object shall be 1658mm for the first 762mm behind the rear fender panels.

A Delineation shall be according to OPSD 984.203.
B The system depicted here is a proprietary product.
C System configuration meets NCHRP Report 350 test level.
D All dimensions are in millimetres unless otherwise shown.

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
TYPE A CARTRIDGES FRONT REQ'D	1	3
TYPE B CARTRIDGES REAR REQ'D	3	5
SYSTEM LENGTH	4722	8084
NOMINAL SYSTEM WIDTH	1520	1520


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION TAU–II WIDE SYSTEM INSTALLATION – TEMPORARY UNIDIRECTIONAL


Nov 2011 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS

OPSD 923.384



PLAN



ELEVATION

NOTES:

1 When system is placed on a concrete pad, the pad shall be according to OPSD 923.004.
2 Adjacent temporary concrete barrier units shall be modified and anchored according to OPSD 923.002.
3 Maximum width of object shall be 1658mm for the first 762mm behind the rear fender panels.
4 Removable 20mm dia anchor bolts, each with an ultimate pullout strength of 100kN in 30MPa concrete.

A Delineation shall be according to OPSD 984.203.
B The system depicted here is a proprietary product.
C System configuration meets NCHRP Report 350 test level.
D All dimensions are in millimetres unless otherwise shown.

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
TYPE A CARTRIDGES FRONT REQ'D	1	3
TYPE B CARTRIDGES REAR REQ'D	3	5
SYSTEM LENGTH	4722	8084
NOMINAL SYSTEM WIDTH	1520	1520


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION TAU–II WIDE SYSTEM INSTALLATION – TEMPORARY BIDIRECTIONAL


Nov 2011 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS

OPSD 923.385



PLAN



ELEVATION

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
TYPE A CARTRIDGES FRONT REQ'D	1	3
TYPE B CARTRIDGES REAR REQ'D	3	5
SYSTEM LENGTH	4722	8084
NOMINAL SYSTEM WIDTH	1520	1520

NOTES:

1 The system shall be anchored to concrete pad detailed in OPSD 923.004.
2 Maximum width of object shall be 1658mm for the first 762mm behind the rear fender panels.

A Delineation shall be according to OPSD 984.204.
B The system depicted here is a proprietary product.
C System configuration meets NCHRP Report 350 test level.
D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION TAU–II WIDE SYSTEM INSTALLATION – PERMANENT UNIDIRECTIONAL


Nov 2011 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS

OPSD 923.386



PLAN



ELEVATION

NOTES:

1 The system shall be anchored to concrete pad detailed in OPSD 923.004.
2 Maximum width of object shall be 1658mm for the first 762mm behind the rear fender panels.
3 Removable 20mm dia anchor bolts, each with an ultimate pullout strength of 100kN in 30MPa concrete.

A Delineation shall be according to OPSD 984.204.
B The system depicted here is a proprietary product.
C System configuration meets NCHRP Report 350 test level.
D All dimensions are in millimetres unless otherwise shown.

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
TYPE A CARTRIDGES FRONT REQ'D	1	3
TYPE B CARTRIDGES REAR REQ'D	3	5
SYSTEM LENGTH	4722	8084
NOMINAL SYSTEM WIDTH	1520	1520


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION TAU–II WIDE SYSTEM INSTALLATION – PERMANENT BIDIRECTIONAL


Nov 2011 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS

OPSD 923.387



PLAN




ELEVATION

NOTES:


1 2 Type A and 4 Type B cartridges.
2 When system is placed on a concrete pad, the pad shall be according to OPSD 923.005.
3 Adjacent temporary concrete barriers shall be modified and anchored according to OPSD 923.002.
4 Maximum width of object shall be 2200mm for the first 762mm behind the rear fender panels.

A Delineation shall be according to OPSD 984.203.
B Nominal system width is 2290mm.
C The system depicted here is a proprietary product.
D System configuration meets NCHRP Report 350 test level.
E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2011	Rev	0
ENERGY ATTENUATOR, CRASH CUSHION TAU-II EXTRA WIDE SYSTEM – TL-2 INSTALLATION – TEMPORARY UNIDIRECTIONAL			
	OPSD 923.388		



PLAN




ELEVATION

NOTES:


1 2 Type A and 4 Type B cartridges.
2 When the system is placed on a concrete pad, the pad shall be according to OPSD 923.005.
3 Adjacent temporary concrete barrier units shall be modified and anchored according to OPSD 923.002.
4 Maximum width of object shall be 2200mm for the first 762mm behind the rear fender panels.
5 Removable 20mm dia anchor bolts, each with an ultimate pullout strength of 100kN in 30MPa concrete.

A Nominal system width is 2290mm.
B Delineation shall be according to OPSD 984.203.
C The system depicted here is a proprietary product.
D System configuration meets NCHRP Report 350 test level.
E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2011	Rev	0
ENERGY ATTENUATOR, CRASH CUSHION TAU–II EXTRA WIDE SYSTEM – TL–2 INSTALLATION – TEMPORARY BIDIRECTIONAL			
	OPSD 923.389		



PLAN



ELEVATION

NOTES:

1 5 Type A and 6 Type B cartridges.
2 When system is placed on a concrete pad, the pad shall be according to OPSD 923.005.
3 Adjacent temporary concrete barrier units shall be modified and anchored according to OPSD 923.002.
4 Maximum object width shall be 2200mm for the first 762mm behind the rear fender panels.

A Delineation shall be according to OPSD 984.203.
B Nominal system width is 2290mm.
C The system depicted here is a proprietary product.
D System configuration meets NCHRP Report 350 test level.
E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION TAU–II EXTRA WIDE SYSTEM – TL–3 INSTALLATION – TEMPORARY UNIDIRECTIONAL

Nov 2011 | Rev 0

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · O P S

OPSD 923.390



NOTES:

1 5 Type A and 6 Type B cartridges.
2 When the system is placed on a concrete pad, the pad shall be according to OPSD 923.005.
3 Adjacent temporary concrete barrier units shall be modified and anchored according to OPSD 923.002.
4 Maximum object width shall be 2200mm for the first 762mm behind the rear fender panels.
5 Removable 20mm dia anchor bolts, each with an ultimate pullout strength of 100kN in 30MPa concrete.

A Nominal system width is 2290mm.
B Delineation shall be according to OPSD 984.203.
C The system depicted here is a proprietary product.
D System configuration meets NCHRP Report 350 test level.
E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION TAU–II EXTRA WIDE SYSTEM – TL–3 INSTALLATION – TEMPORARY BIDIRECTIONAL


Nov 2011 | Rev 0

ONTARIO STANDARD MUNICIPAL – PROVINCIAL

OPSD 923.391



PLAN




ELEVATION

NOTES:


1 The system shall be anchored to concrete pad detailed in OPSD 923.005.
2 2 Type A and 4 Type B cartridges.
3 Maximum width of object shall be 2200mm for the first 762mm behind the rear fender panels.

A Delineation shall be according to OPSD 984.204.
B Nominal system width is 2290mm.
C The system depicted here is a proprietary product.
D System configuration meets NCHRP Report 350 test level.
E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2011	Rev	0
ENERGY ATTENUATOR, CRASH CUSHION TAU-II EXTRA WIDE SYSTEM - TL-2 INSTALLATION - PERMANENT UNIDIRECTIONAL			
	OPSD 923.392		



PLAN




ELEVATION

NOTES:


1 The system shall be anchored to concrete pad detailed in OPSD 923.005.
2 2 Type A and 4 Type B cartridges.
3 Maximum width of object shall be 2200mm for the first 762mm behind the rear fender panels.
4 Removable 20mm dia anchor bolts, each with an ultimate pullout strength of 100kN in 30MPa concrete.

A Nominal system width is 2290mm.
B Delineation shall be according to OPSD 984.204.
C The system depicted here is a proprietary product.
D System configuration meets NCHRP Report 350 test level.
E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2011	Rev	0
ENERGY ATTENUATOR, CRASH CUSHION TAU–II EXTRA WIDE SYSTEM – TL–2 INSTALLATION – PERMANENT BIDIRECTIONAL			
	OPSD 923.393		



PLAN



ELEVATION

NOTES:

1 The system shall be anchored to concrete pad detailed in OPSD 923.005.
2 5 Type A and 6 Type B cartridges.
3 Maximum width of object shall be 2200mm for the first 762mm behind the rear fender panels.

A Delineation shall be according to OPSD 984.204.
B Nominal system width is 2290mm.
C The system depicted here is a proprietary product.
D System configuration meets NCHRP Report 350 test level.
E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION TAU–II EXTRA WIDE SYSTEM – TL–3 INSTALLATION – PERMANENT UNIDIRECTIONAL

Nov 2011 | Rev 0

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPS

OPSD 923.394



NOTES:

1 The system shall be anchored to concrete pad detailed in OPSD 923.005.
2 5 Type A and 6 Type B cartridges.
3 Maximum width of object shall be 2200mm for the first 762mm behind the rear fender panels.
4 Removable 20mm dia anchor bolts, each with an ultimate pullout strength of 100kN in 30MPa concrete.

A Nominal system width is 2290mm.
B Delineation shall be according to OPSD 984.204.
C The system depicted here is a proprietary product.
D System configuration meets NCHRP Report 350 test level.
E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION TAU–II EXTRA WIDE SYSTEM – TL–3 INSTALLATION – PERMANENT BIDIRECTIONAL

Nov 2011 | Rev 0


ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS

OPSD 923.395




PLAN

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
NUMBER OF CARTRIDGES REQUIRED	4	7
SYSTEM LENGTH	4334	6934



ELEVATION



SECTION A–A

NOTES:

1 Braces for asphalt shall be used when system is placed on asphalt over granular. When system is placed on a concrete pad, the pad shall be according to OPSD 923.001.

2 Adjacent temporary concrete barrier unit shall be anchored according to OPSD 923.002. Barrier bevelling is not required.

3 Anchors shall be according to the manufacturer's specifications.

A Delineation shall be according to OPSD 984.203.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–2 or TL–3 (Table 1).

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION TAU–M SYSTEM INSTALLATION – TEMPORARY UNIDIRECTIONAL

Nov 2021 | Rev 0


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 923.396




PLAN

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
NUMBER OF CARTRIDGES REQUIRED	4	7
SYSTEM LENGTH	4334	6934



ELEVATION



SECTION A–A

NOTES:

1 Braces for asphalt shall be used when system is placed on asphalt over granular. When system is placed on a concrete pad, the pad shall be according to OPSD 923.001.

2 Adjacent temporary concrete barrier unit shall be anchored according to OPSD 923.002. Barrier bevelling is not required.

3 Anchors shall be according to the manufacturer's specifications.

4 Threaded rods anchored to barrier as per manufacturer's instructions.

A Delineation shall be according to OPSD 984.203.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–2 or TL–3 (Table 1).

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION TAU–M SYSTEM INSTALLATION – TEMPORARY BIDIRECTIONAL

Nov 2021 | Rev 0


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 923.397




PLAN

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
NUMBER OF CARTRIDGES REQUIRED	4	7
SYSTEM LENGTH	4334	6934



ELEVATION



SECTION A–A

NOTES:

1 The system shall be anchored to a concrete pad as detailed in OPSD 923.001. Braces for asphalt shall be used when system is placed on asphalt over granular.
2 Anchors shall be according to the manufacturer's specifications.
A Delineation shall be according to OPSD 984.204.
B The system depicted here is a proprietary product.
C System configuration meets AASHTO MASH TL–2 or TL–3 (Table 1).
D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION TAU–M SYSTEM INSTALLATION – PERMANENT UNIDIRECTIONAL

Nov 2021 | Rev 0


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 923.398




PLAN

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
NUMBER OF CARTRIDGES REQUIRED	4	7
SYSTEM LENGTH	4334	6934



ELEVATION



SECTION A–A

NOTES:

1 The system shall be anchored to a concrete pad as detailed in OPSD 923.001. Braces for asphalt shall be used when system is placed on asphalt over granular.
2 Anchors shall be according to the manufacturer's specifications.
3 Threaded rods anchored to barrier as per manufacturer's instructions.
A Delineation shall be according to OPSD 984.204.
B The system depicted here is a proprietary product.
C System configuration meets AASHTO MASH TL–2 or TL–3 (Table 1).
D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION TAU–M SYSTEM INSTALLATION – PERMANENT BIDIRECTIONAL


Nov 2021 | Rev 0

ONTARIO STANDARDS • MUNICIPAL–PROVINCIAL •


OPSD 923.399




PLAN



ELEVATION



FRONT VIEW



SECTION A–A

NOTES:

1 When system is placed on a concrete pad, the pad shall be according to OPSD 923.001.

2 Adjacent temporary concrete barrier shall be modified and anchored according to OPSD 923.002.

3 Measured at toe of safety shape barrier.

A Delineation shall be according to OPSD 984.203.

B The system depicted here is a proprietary product.

C System configuration meets NCHRP Report 350 and AASHTO MASH.

D All dimensions are in millimetres unless otherwise shown.

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
SYSTEM LENGTH	4118	6556
SIDE PANELS PER SIDE	2	5
SYSTEM WIDTH	879	951


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION SMART SYSTEM INSTALLATION–TEMPORARY UNIDIRECTIONAL


Nov 2017 | Rev 1

ONTARIO STANDARDS · MUNICIPAL–PROVINCIAL · O P S


OPSD 923.480




PLAN



ELEVATION



FRONT VIEW



SECTION A–A

NOTES:

1 When system is placed on a concrete pad, the pad shall be according to OPSD 923.001.

2 Adjacent temporary concrete barrier shall be modified and anchored according to OPSD 923.002.

3 Measured at toe of safety shape barrier.

A Delineation shall be according to OPSD 984.203.

B The system depicted here is a proprietary product.

C System configuration meets NCHRP Report 350 and AASHTO MASH.

D All dimensions are in millimetres unless otherwise shown.

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
SYSTEM LENGTH	4118	6556
SIDE PANELS PER SIDE	2	5
SYSTEM WIDTH	879	951


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION SMART SYSTEM INSTALLATION–TEMPORARY BIDIRECTIONAL


Nov 2017 | Rev 1

ONTARIO STANDARDS · MUNICIPAL–PROVINCIAL · O P S


OPSD 923.481




PLAN



ELEVATION



FRONT VIEW



SECTION A–A

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
SYSTEM LENGTH	4118	6556
SIDE PANELS PER SIDE	2	5
SYSTEM WIDTH	879	951

NOTES:

1 Measured at toe of safety shape barrier.

A Delineation shall be according to OPSD 984.204.

B The system depicted here is a proprietary product.

C System configuration meets NCHRP Report 350 and AASHTO MASH.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION SMART SYSTEM INSTALLATION–PERMANENT UNIDIRECTIONAL


Nov 2017 | Rev 1

ONTARIO STANDARDS MUNICIPAL–PROVINCIAL


OPSD 923.482




PLAN



ELEVATION



FRONT VIEW



SECTION A–A

TABLE 1		
SYSTEM CONFIGURATION	TL–2	TL–3
SYSTEM LENGTH	4118	6556
SIDE PANELS PER SIDE	2	5
SYSTEM WIDTH	879	951

NOTES:

1 Measured at toe of safety shape barrier.

A Delineation shall be according to OPSD 984.204.

B The system depicted here is a proprietary product.

C System configuration meets NCHRP Report 350 and AASHTO MASH.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION SMART SYSTEM INSTALLATION–PERMANENT BIDIRECTIONAL


Nov 2017 | Rev 1

ONTARIO STANDARDS MUNICIPAL–PROVINCIAL

OPSD 923.483



PLAN



ELEVATION

SECTION A–A

NOTES:

1 The system shall be anchored to a concrete pad as detailed in OPSD 923.008.

2 Anchors shall be according to the manufacturer's specifications.

3 Adjacent temporary concrete barrier unit shall be modified and anchored according to OPSD 923.002.

A Delineation shall be according to OPSD 984.203.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–3.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION HERCULES SYSTEM INSTALLATION – TEMPORARY UNIDIRECTIONAL AND BIDIRECTIONAL


Nov 2021 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S

OPSD 923.501



PLAN



ELEVATION

SECTION A–A

NOTES:

1 The system shall be anchored to a concrete pad as detailed in OPSD 923.008.

2 Anchors shall be according to the manufacturer's specifications.

A Delineation shall be according to OPSD 984.203.

B The system depicted here is a proprietary product.

C System configuration meets AASHTO MASH TL–3.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION HERCULES SYSTEM INSTALLATION – PERMANENT UNIDIRECTIONAL AND BIDIRECTIONAL

Nov 2021 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S

OPSD 923.502



NOTES:

1 Measured from traffic face side of rail.

A Delineation shall be according to OPSD 984.204.

B The system depicted here is a proprietary product.

C System configuration meets NCHRP Report 350 TL–3.

D This OPSD shall be read in conjuction with OPSD 923.531 and 202.033.

E Sections A–A and B–B shown on OPSD 923.531.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION BOX BEAM BURSTING ENERGY ABSORBING TERMINAL INSTALLATION – LAYOUT


Nov 2011 | Rev 1

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPS


OPSD 923.530




IMPACT HEAD DETAIL AND POST (1)




POSTS (2)(3)(4)(5)(6)



POSTS (7)(8)



SECTION A–A



SECTION B–B

NOTES:


1 Mounting height measured vertically to top of box beam rails.

A This OPSD shall be read in conjunction with OPSD 923.530.


B The system depicted here is a proprietary product.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2011	Rev	1
ENERGY ATTENUATOR, CRASH CUSHION BOX BEAM BURSTING ENERGY ABSORBING TERMINAL INSTALLATION – IMPACT HEAD AND POST			
			OPSD 923.531




PLAN




ELEVATION

TABLE A	
System Configuration	TL–3
Elements	8
Configuration	A–B–A–B–A–B–A–B
System Length	8280



TYPE A ELEMENT



TYPE B ELEMENT

NOTES:

1 When placed adjacent to concrete barrier, steel beam guide rail, or box beam guide rail; clearance shall be ≤ 0.3m or ≥ 3.0m, otherwise minimum 6.0m wide traversable object free zone shall extend from end assembly for 30.0m minimum or longer when specified.

2 First 16m of movable temporary concrete shall be placed tangential to ABSORB 350 system.

A The system depicted here is a proprietary product.

B System configuration meets NCHRP Report 350 TL–3.

C All elements except the first element adjacent to end assembly shall be filled with water. When temperature is predicted to fall below freezing, antifreeze agents according to manufacturer recommendations shall be used.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION ABSORB 350 SYSTEM MOVABLE TEMPORARY CONCRETE BARRIER INSTALLATION

Nov 2021 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 924.130






TABLE A		
System Configuration	TL–2	TL–3
Elements	5	9
Configuration	A–B–A–B–A	A–B–A–B–A–B–A–B–A
System Length	4740	9379

ELEVATION



TYPE A ELEMENT



TYPE B ELEMENT

NOTES:

1 When placed adjacent to concrete barrier or steel beam guide rail, clearance shall be ≤ 0.3m or ≥ 3.0m, otherwise minimum 6.0m wide traversable object free zone shall extend from end assembly for 22.0m minimum.

2 First 16m of TCB shall be placed tangential to ABSORB 350 system.

3 Taper and strap adapters shall be according to manufacturer's specifications for temporary concrete barrier type used.

A Delineation shall be according to OPSD 984.203.

B System configuration meets NCHRP Report 350 test level.

C The system depicted here is a proprietary product.

D All elements except the first element adjacent to end assembly shall be filled with water. When temperature is predicted to fall below freezing, antifreeze agents according to manufacturer recommendations shall be used.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION ABSORB 350 SYSTEM INSTALLATION–TEMPORARY CONCRETE BARRIER


Nov 2016 | Rev 1

ONTARIO STANDARD MUNICIPAL–PROVINCIAL

OPSD 924.131



PLAN



ELEVATION

NOTES:


1 When placed adjacent to concrete barrier or steel beam guide rail, clearance shall be ≤ 0.3m or ≥ 3.0m, otherwise minimum 6.0m wide traversable object free zone shall extend from end assembly for 22.0m minimum.
2 When downstream TCB is achored according to OPSD 923.002, layout shall be according to OPSD 911.236. When downstream TCB is unanchored, layout shall be according to OPSD 911.232.
3 Taper and strap adapters shall be according to manufacturer's specifications for temporary concrete barrier type used.
4 Anchors shall be according to manufacturer's specifications.
A Delineation shall be according to OPSD 984.203.
B System configuration meets AASHTO MASH Test level 2.
C The system depicted here is a proprietary product.
D All elements except the first element adjacent to end assembly shall be filled with water. When temperature is predicted to fall below freezing, antifreeze agents according to manufacturer recommendations shall be used.
E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


ENERGY ATTENUATOR, CRASH CUSHION ABSORB–M SYSTEM TL–2 INSTALLATION–TEMPORARY CONCRETE BARRIER

Nov 2021 | Rev 0

OPSD 924.132



PLAN



ELEVATION

NOTES:

1 When placed adjacent to concrete barrier or steel beam guide rail, clearance shall be ≤ 0.3m or ≥ 3.0m, otherwise minimum 6.0m wide traversable object free zone shall extend from end assembly for 22.0m minimum.
2 When downstream TCB is achored according to OPSD 923.002, layout shall be according to OPSD 911.236. When downstream TCB is unanchored, layout shall be according to OPSD 911.232.
3 Taper and strap adapters shall be according to manufacturer's specifications for temporary concrete barrier type used.
4 Anchors shall be according to manufacturer's specifications.
A Delineation shall be according to OPSD 984.203.
B System configuration meets AASHTO MASH Test level 3.
C The system depicted here is a proprietary product.
D All elements except the first element adjacent to end assembly shall be filled with water. When temperature is predicted to fall below freezing, antifreeze agents according to manufacturer recommendations shall be used.
E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION ABSORB–M SYSTEM TL–3 INSTALLATION–TEMPORARY CONCRETE BARRIER


Nov 2021 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS

OPSD 924.133



PLAN



ELEVATION

NOTES:

1 When placed adjacent to concrete barrier or steel beam guide rail, clearance shall be ≤ 0.3m or ≥ 3.0m, otherwise minimum 6.0m wide traversable object free zone shall extend from nose for 22.0m minimum.

2 First 16m of TCB shall be placed tangential to ACZ–350 system.

3 Transition assembly and method of connection shall be according to manufacturer's specifications for temporary concrete barrier type used.

A Delineation shall be according to OPSD 984.203.

B System configuration meets NCHRP Report 350 test level.

C The system depicted here is a proprietary product.

D All elements shall be filled with water. When temperature is predicted to fall below freezing, antifreeze agents according to manufacturer recommendations shall be used.

E All dimensions are in millimetres unless otherwise shown.

TABLE A		
System Configuration	TL–2	TL–3
Bays	①②	①②③④
System Length	5620	9620


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION ACZ–350 SYSTEM INSTALLATION–TEMPORARY CONCRETE BARRIER


Nov 2016 | Rev 2

ONTARIO STANDARDS · MUNICIPAL–PROVINCIAL · O P S

OPSD 924.135



PLAN



ELEVATION

NOTES:

1 When placed adjacent to concrete barrier or steel beam guide rail, clearance shall be ≤0.3m or ≥3.0m, otherwise minimum 6.0m wide traversable object free zone shall extend from nose for 22.0m minimum.

2 First 16m of TCB shall be placed tangential to SLED system.

3 Transition assembly and method of connection shall be according to manufacturer's specifications for temporary concrete barrier type used.

A Delineation shall be according to OPSD 984.203.

B The system depicted here is a proprietary product.

C System configuration meets NCHRP Report 350 and AASHTO MASH.

D All modules (except Module 4) shall be filled with water. When temperature is predicted to fall below freezing, antifreeze agents according to manufacturer recommendations shall be used.

E All dimensions are in millimetres unless otherwise shown.

TABLE A		
SYSTEM CONFIGURATION	TL–2	TL–3
MODULES	①②④	①②③④
SYSTEM LENGTH	5770	7930


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION SLED SYSTEM INSTALLATION–TEMPORARY CONCRETE BARRIER


Nov 2017 | Rev 1

ONTARIO STANDARDS MUNICIPAL–PROVINCIAL


OPSD 924.141




ELEVATION



SPLICE BOLT AND NUT



RECTANGULAR WASHER
Note 1




ENLARGED SECTION A–A

NOTES:

1 Base metal thickness of rail shall be 2.67mm nominal and 2.44mm minimum.

A All dimensions are in millimetres.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2013	Rev	0
GUIDE RAIL SYSTEM, THRIE BEAM COMPONENT – RAIL			
	OPSD 925.010		




ELEVATION

NOTES:


A Base metal thickness of terminal connector shall be 3.43mm nominal and 3.18mm minimum.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2013	Rev	0
GUIDE RAIL SYSTEM, THRIE BEAM COMPONENT – TERMINAL CONNECTOR			
	OPSD 925.030		



HIGHWAY FENCE
IN EARTH, SHALE, LOOSE ROCK, OR FRIABLE ROCK



GATE DETAIL

NOTES:


1 Standard post spacing shall be 6.0m for wooden post to wooden post and 5.0m for steel post to steel or wooden post.

2 Ratio of steel posts to wooden posts shall be 3:1.


A This OPSD is to be read in conjunction with OPSD 971.103.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2022	Rev	5
FENCE, HIGHWAY IN EARTH, SHALE, LOOSE ROCK, OR FRIABLE ROCK INSTALLATION			
	OPSD 971.101		




HIGHWAY FENCE IN SOLID ROCK




DETAIL A
STEEL LINE POST IN
OVERBURDEN LESS THAN 600mm


STEEL POST DEPTH IN ROCK	
EARTH OVERBURDEN DEPTH	LINE POST DEPTH Min Y
< 600	380
600–1000	230



DETAIL B
STEEL LINE POST IN
OVERBURDEN BETWEEN 600 – 1000mm



DETAIL C
BRACE PANEL IN
OVERBURDEN LESS THAN 600mm



DETAIL D
BRACE PANEL IN
OVERBURDEN BETWEEN 600 – 1000mm

NOTES:
1 Standard line post spacing shall be 5.0m.
A This OPSD is to be read in conjunction with OPSD 971.103.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

FENCE, HIGHWAY
IN SOLID ROCK
INSTALLATION


Apr 2022 | Rev 3

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S


OPSD 971.102




FENCE FABRIC WIRE SPACING DETAIL




STAPLING DETAIL




LINE WIRE WRAPPING SPLICING DETAIL



CRIMP SLEEVE SPLICING DETAIL



FENCE TERMINATION DETAIL



TENSIONING DETAILS, Note 2

NOTES:


1 Each of the nine line wires shall be spliced with a crimp sleeve. Crimp sleeves shall be installed according to the manufacturer's instructions for the type of fence fabric installed.


2 The tensioned curves shall be one half the size of the untensioned curves.

3 Both fabric end vertical stay wires shall be within a maximum of 305mm centres.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	0
FENCE, HIGHWAY			
INSTALLATION DETAILS			
	OPSD 971.103		






CORNER POST
WITH BARBED WIRE ARM



STRAINING POST
WITH BARBED WIRE ARM



LINE POST WITH
BARBED WIRE ARM


NOTES:

1 Terminal post shall be lengthened when barbed wire is specified, except when barbed wire arms are used.


A Installation as viewed from the roadway.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
FENCE, CHAIN-LINK COMPONENT – BARBED WIRE			
	OPSD 972.101		



DOUBLE SWING GATE OPENING



SINGLE SWING GATE OPENING


NOTES:

1 For footing details and Gate and Gatepost Details Table refer to OPSD 972.132.


A Gates as viewed from the roadway.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
FENCE, CHAIN–LINK COMPONENT – GATE			
	OPSD 972.102		



CHAIN–LINK FENCE WITH TOP RAIL



CHAIN–LINK FENCE WITH TOP WIRE

NOTES:

1 For footing details and line post cap detail refer to OPSD 972.132.

A Fence as viewed from the roadway.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

FENCE, CHAIN–LINK
INSTALLATION – ROADWAY


Nov 2012 | Rev 2

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S


OPSD 972.130




END SECTION DETAIL




LINE POST DETAIL



DETAIL A



PLAN



SECTION A–A

ANCHORAGE DETAIL

NOTES:

1 For line post cap detail refer to OPSD 972.132.


2 Turnbuckles shall be installed on diagonal brace wires and top and bottom wires, at intervals of 150m max and at terminal posts.

3 Chain–link fence posts shall be located on centreline of concrete barrier.


4 Anchors shall be installed according to manufacturer's specifications.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
FENCE, CHAIN–LINK INSTALLATION – CONCRETE BARRIER			
			OPSD 972.131




DETAIL A
FOOTING IN EARTH




DETAIL B
FOOTING IN SHALE, LOOSE OR FRIABLE ROCK, OR SOLID ROCK WITH MORE THAN 450mm OVERBURDEN




DETAIL C
FOOTING IN SOLID ROCK LESS THAN 450mm OVERBURDEN




DETAIL D
FOOTING IN RETAINING WALL




HOG RING TIE DETAIL



MANUALLY FASTENED WIRE TIE DETAIL



POWER FASTENED WIRE TIE DETAIL



62mm ID LINE POST CAP DETAIL

POST DETAILS TABLE (Note 1)						
Post/Frame Member Type		OD	Post Length		Wall Thickness	Nominal Weight kg/m (Note 2)
			Standard m	Retaining Walls m		
Line post		60.3	2.6	2.0	3.91	5.4
Terminal Post		88.9	2.9	2.3	5.49	11.3
Gates (Single 3.0m, Double 6.0m)	Gatepost	88.9	2.6	n/a	5.49	11.3
	Frame Members	42.2	n/a	n/a	3.56	3.4
Gates (Single 4.5m, Double 9.0m)	Gatepost	114.3	2.9	n/a	6.02	16.1
	Frame Members	48.3	n/a	n/a	3.68	4.0
Post Sleeves	Line Post	88.9	n/a	0.455	5.49	11.3
	Terminal Post	114.3	n/a	0.455	6.02	16.1

NOTES:

1 All posts and frame members are Schedule 40, Regular Grade, steel pipe.

2 The actual weight shall not vary by more than 10% of the nominal weight.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

FENCE, CHAIN–LINK
DETAILS AND TABLE

Nov 2012 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 972.132



NOTES:

1 Mounting height to top of steel beam shall be measured vertically at face of rail.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


FENCE, STEEL BEAM BARRICADE INSTALLATION

Nov 2022 | Rev 1


OPSD 973.130




WILDLIFE FENCE – TYPE A WITH APRON OF TYPE B FENCE FABRIC
(POSTS NOT SHOWN FOR CLARITY)




SECTION AT POSTS IN EARTH



SECTION BETWEEN POSTS IN EARTH



SECTION AT POSTS IN ROCK
(FOOTING NOT SHOWN FOR CLARITY)
Note 2



SECTION BETWEEN POSTS IN ROCK

NOTES:

1 Apron shall be connected using hog rings to bottom and top contacting line wires at not more than 300mm spacing.
2 For footing details, see OPSD 973.140.
A Fence as viewed from the roadway.
B This OPSD to be read in conjunction with OPSD 973.135.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

WILDLIFE FENCE, TYPE A WITH APRON OF TYPE B FENCE FABRIC

Nov 2022	Rev	0

ONTARIO STANDARD MUNICIPAL – PROVINCIAL

OPSD 973.131



NOTES:


1 For wildlife fence details, see OPSD 973.135.
2 For footing details, see OPSD 973.140.
A Fence as viewed from the roadway.
B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


WILDLIFE FENCE, TYPE A ACCESS GATE

Nov 2022	Rev	0

OPSD 973.132




WILDLIFE FENCE – TYPE B



SECTION AT POSTS IN EARTH


SECTION BETWEEN POSTS IN EARTH




SECTION AT POSTS IN ROCK CUT

(FOOTING NOT SHOWN FOR CLARITY)


Note 1



SECTION BETWEEN POSTS IN ROCK CUT



CORNER POST WITH BARBED WIRE ARM



STRAINING POST WITH BARBED WIRE ARM

NOTES:

1 For footing details, see OPSD 973.140.

2 For wire tie details, see OPSD 973.142.

A Fence as viewed from the roadway.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

WILDLIFE FENCE, TYPE B ON STEEL POSTS INSTALLATION

Nov 2022 | Rev 0

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · O P S

OPSD 973.133




WILDLIFE FENCE – TYPE B


SECTION AT POSTS IN EARTH

(FOOTING NOT SHOWN FOR CLARITY)

SECTION BETWEEN POSTS IN EARTH




POST TOP DETAIL




SECTION AT POSTS IN ROCK

(FOOTING NOT SHOWN FOR CLARITY)



SECTION BETWEEN POSTS IN ROCK



STRAINING POST

NOTES:

1 For footing details, see OPSD 973.141.
2 For wire tie details, see OPSD 973.142.
A Fence as viewed from the roadway.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

WILDLIFE FENCE, TYPE B ON WOODEN POSTS INSTALLATION


Nov 2022 | Rev | 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 973.134



WILDLIFE FENCE – TYPE A



CORNER POST
WITH BARBED WIRE ARM



STRAINING POST
WITH BARBED WIRE ARM

NOTES:

1 For footing details, see OPSD 973.140.
2 For wire tie details, see OPSD 973.142.
A Fence as viewed from the roadway.
B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

WILDLIFE FENCE, TYPE A INSTALLATION


Nov 2022 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S


OPSD 973.135




DETAIL A
FOOTING IN EARTH



DETAIL B
FOOTING IN SHALE, LOOSE OR FRIABLE ROCK, OR SOLID ROCK WITH MORE THAN 450mm OVERBURDEN



DETAIL C
FOOTING IN SOLID ROCK LESS THAN 450mm OVERBURDEN



DETAIL D
FOOTING IN RETAINING WALL OR HEADWALL

POST DETAILS TABLE (Note 1)						
Post/Frame Member Type		OD	Post Length		Wall Thickness	Nominal Weight kg/m (Note 2)
			Type A m	Type B m		
Line Post		60.3	3.5	1.5	3.91	5.4
Terminal Post		88.9	4.3	2.4	5.49	11.3
Brace Rail		42.2	n/a	n/a	5.49	3.4
Post Sleeves	Line Post	88.9	n/a	n/a	5.49	11.3
	Terminal Post	114.3	n/a	n/a	6.02	16.1

NOTES:

1 All posts and frame members shall be Schedule 40, Regular Grade, steel pipe.
2 The actual weight shall not vary by more than 10% of the nominal weight.
A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2022 | Rev 0

WILDLIFE FENCE


STEEL POST FOOTING DETAILS

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 973.140




DETAIL A
FOOTING IN EARTH



DETAIL B
FOOTING IN SHALE, LOOSE OR FRIABLE ROCK, OR SOLID ROCK WITH MORE THAN 450mm OVERBURDEN



DETAIL C
FOOTING IN SOLID ROCK LESS THAN 450mm OVERBURDEN




STAPLING DETAIL


NOTES:

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	0
WILDLIFE FENCE WOODEN POST INSTALLATION DETAILS			
	OPSD 973.141		




HOG RING TIE DETAIL
TYPE B FENCE




POWER FASTENED
WIRE TIE DETAIL
TYPE A AND B FENCE




FENCE TERMINATION DETAIL
TYPE A FENCE



MUFFLER CLAMP
DETAIL
TYPE A FENCE



CRIMP SLEEVE
SPLICING DETAIL
TYPE A FENCE




TENSIONING DETAILS, Note 2
TYPE A FENCE


NOTES:

1 Each line wire shall be spliced with a crimp sleeve. Crimp sleeves shall be installed according to the manufacturer's instructions for the type of fence fabric installed.
2 The tensioned curves shall be one half the size of the untensioned curves.
3 Both fabric end vertical stay wires shall be within a maximum of 305mm centres.
A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	0
WILDLIFE FENCE MISCELLANEOUS DETAILS			
	OPSD 973.142		




TIE–IN AT RECTANGULAR CULVERTS
PLAN




TIE–IN AT CIRCULAR CULVERTS
PLAN

NOTES:
A Type B fence may be constructed with steel or wooden posts.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	0
WILDLIFE FENCE TIE–IN AT CULVERTS OR WILDLIFE CROSSING STRUCTURES			
	OPSD 973.143		



SECTION A–A
(FENCING NOT SHOWN FOR CLARITY)



PLAN




SECTION B–B
(FENCING NOT SHOWN FOR CLARITY)

NOTES:

1 The landing area shall be graded smoothly away from the base of the ramp with a slope of 3H:1V or flatter.
2 Ramps shall be constructed so as not to encroach on highway drainage.
3 Wildlife fence as specified.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	0
WILDLIFE ESCAPE			
	OPSD 973.144		




TYPE B FENCE
FENCE END TURNAROUND
PLAN VIEW

NOTES:

A Type B fence may be constructed with steel or wooden posts.

B All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	0
WILDLIFE FENCE, TYPE B FENCE END TURNAROUND			
	OPSD 973.145		




ELEVATION


NOTES:

1 When sidewalk is not specified, posts shall be set in centre of 300mm dia x 450mm deep or 300 x 300 x 375mm deep concrete footings.
2 Anchors shall be installed according to manufacturer's specifications.


A Concrete shall have a nominal minimum 28–Day compressive strength of 20MPa.
B Posts and railings shall be hot dip galvanized according to ASTM A123 after fabrication.
C Posts shall be vertical. All exposed corners shall be ground smooth.
D Welding shall be according to CSA W59.
E All joints shall be shop welded.
F Pipe shall be according to ASTM A500, Grade C.
G A difference in elevation between the adjacent ground level and top of footing shall not exceed 600mm.
H All dimensions are in millimetres unless otherwise shown.




PLAN OF BASE PLATE




SECTION A–A



SECTION B–B



JOINT DETAIL




BASE PLATE ELEVATION
INSTALLATION DETAIL ON EXISTING CONCRETE

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2017 | Rev 3

PEDESTRIAN BARRICADE
INSTALLATION


OPSD 980.101



SECTION A–A



PLAN




ELEVATION

NOTES:


1 Anchors shall be installed according to manufacturer's specifications.
2 Frame shall be welded to the steel pipes all around.

A All steel pipe shall be according to ASTM A500, Grade C.
B Welding shall be according to CSA W59.
C All parts shall be hot dipped galvanized according to ASTM A123 after fabrication.
D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	2
SPLASH GUARD, PEDESTRIAN INSTALLATION			
	OPSD 982.101		



POST MOUNTED DELINEATOR
TYPE A




POST MOUNTED DELINEATOR
TYPE B

NOTES:


1 Type A delineators shall be 125 x 125mm.
2 Type B delineators shall be 250 x 250mm.
3 Delineator posts shall be 25 x 25mm steel square tube post, 2134mm in length.
4 Prior to galvanizing, four holes shall be drilled or punched, size No. 30, 3.2mm diameter. Delineators shall be fastened with two #10 (3/16") x 3/4" metal drilling screws.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	1
POST MOUNTED DELINEATOR INSTALLATION			
	OPSD 984.101		



PAVED SURFACE INSTALLATION
TYPE A



GRANULAR SURFACE INSTALLATION
TYPE B


NOTES:

1 Relective sheeting shall be wrapped fully around the post.


2 Base shall be installed according to the manufacturer's specifications and installation instructions.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	0
FLEXIBLE DELINEATOR POST INSTALLATION – TEMPORARY AND PERMANENT			
	OPSD 984.105		




STEEL BEAM TERMINAL




STEEL BEAM ENERGY ATTENUATING TERMINAL – TANGENT



STEEL BEAM ENERGY ATTENUATING TERMINAL – FLARED




APPROACH END – LEFT SHOULDER




APPROACH END – RIGHT SHOULDER

NOTE:
A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	1
ENERGY ATTENUATOR, END TREATMENT DELINEATION INSTALLATION – APPROACH END			
	OPSD 984.201		




STEEL BEAM TERMINAL



STEEL BEAM ENERGY ATTENUATING TERMINAL – TANGENT




STEEL BEAM ENERGY ATTENUATING TERMINAL – FLARED




LEAVING END

NOTE:
A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	1
ENERGY ATTENUATOR, END TREATMENT DELINEATION INSTALLATION – LEAVING END			
	OPSD 984.202		



SHOULDER WIDTH < 2.0m




SHOULDER WIDTH ≥ 2.0m




GORE

TABLE 1		
POSTED SPEED km/h	FLEXIBLE DELINEATORS REQUIRED	DELINEATOR SPACING m
<70	3.0	3.0
≥70	5.0	3.0




GRANULAR SURFACE **PAVED SURFACE**

SHOULDER



FLEXIBLE DELINEATOR POST



GORE

NOTES:

1 Type IV reflective sheeting or higher shall be wrapped around post.

2 Right shoulder installation shown. For left shoulder installation, use Wa–33L.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


ENERGY ATTENUATOR, CRASH CUSHION DELINEATION INSTALLATION – TEMPORARY

Nov 2017 | Rev 1


OPSD 984.203




SHOULDER



SHOULDER



GORE



GORE

NOTES:

1 Right shoulder installation shown. For left shoulder installation, use Wa–33L.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

ENERGY ATTENUATOR, CRASH CUSHION DELINEATION INSTALLATION – PERMANENT


Nov 2017 | Rev 1

ONTARIO STANDARDS – MUNICIPAL – PROVINCIAL


OPSD 984.204



PLAN



UNIDIRECTIONAL CIAS INSTALLATION




BIDIRECTIONAL CIAS INSTALLATION

NOTES:


A High intensity retroreflective sheeting shall be applied directly to the CIAS cylinder. The edges of the applied sheeting shall be vertical and free of bubbles and wrinkles.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2013	Rev	0
ENERGY ATTENUATOR, CRASH CUSHION CONNECTICUT IMPACT ATTENUATION SYSTEM DELINEATION INSTALLATION – PERMANENT			
	OPSD 984.205		



SAFENCE TERMINAL



LEAVING END

NOTES:

1 Wa–33 not required on divided highways or one–way ramps.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

GUIDE RAIL SYSTEM, HIGH TENSION CABLE DELINEATION INSTALLATION – LEAVING END


Apr 2018 | Rev 0

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •


OPSD 984.206



SAFENCE TERMINAL



APPROACH END – LEFT SHOULDER




APPROACH END – RIGHT SHOULDER

NOTES:
A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2018	Rev	0
GUIDE RAIL SYSTEM, HIGH TENSION CABLE DELINEATION INSTALLATION – APPROACH END			
	OPSD 984.207		

SIGN SUPPORT REQUIREMENTS

Embedment Depth	Dressed Post Size and Hole Diameter			Note 2			Galvanized Lag Bolt Size
				Max. Sign Dimensions		Max. Sign Area	
E	w	b	Hole Dia.	B cm	H cm	A m^2	inch
920	89	89	N/A	120	90	0.41	3/8 X 3
1000	89	140	38	120	120	0.90	3/8 X 3
1000	140	140	51	120	180	1.08	3/8 X 4
1200	140	184	76	120	180	1.80	3/8 X 4



FRONT



SIDE

NOTES:

1 Minimum vertical clearance of 2.1m shall be provided between the finished grade and the bottom of the lowest sign or tab.

2 Dressed post size (w and b) shall be selected to accommodate sign sizes specified in the Contract Documents so that maximum dimensions for sign size (B and H) and total sign area (A) including tabs shall not exceed values in the table.

3 When curb is present, minimum 0.3m from face of curb.
When guide rail is present, minimum 1.0m behind face of guide rail.

4 When holes are drilled prior to pressure treatment of post, additional treatment of holes is not required. When holes are drilled after pressure treatment of post, additional field treatment of holes is required.

5 When top of post is not cut after pressure treatment, it does not require to be bevelled as shown.
When top of post is cut after pressure treatment, it shall be bevelled at 15 to 30° angle and treated in the field.

A When Wa–33 is specified below a Rb–125, the bottom of the Wa–33 shall be 1.2m above finished grade.

B System configuration meets NCHRP Report 350 TL–3.

C Wooden dressed post shall be S–P–F species No. 1 or No. 2 grade.

D Wooden dressed post shall be stamped for grade, species, and treatment.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

SMALL SIGN SUPPORT SYSTEM
SINGLE BREAKAWAY WOODEN POST
89x89mm, 89x140mm, 140x140mm, AND 140x184mm
INSTALLATION–SINGLE POST ASSEMBLY


Apr 2019 | Rev 1

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S

OPSD 985.110

SIGN SUPPORT REQUIREMENTS

Embedment Depth	Dressed Post Size and Hole Diameter			Note 2		
				Max. Sign Dimensions		Max. Sign Area
E	w	b	Hole Dia.	B cm	H cm	A m^2
920	89	89	N/A	150 to 240	90	0.90
1000	89	140	38	150 to 240	120	1.89



NOTES:

1 Minimum vertical clearance of 2.1m shall be provided between the finished grade and the bottom of the lowest sign or tab.

2 Dressed post size (w and b) shall be selected to accommodate sign size specified in the Contract Documents so that maximum dimensions for sign size (B and H) and total sign area (A) including tabs shall not exceed values in the table.

3 When curb is present, minimum 0.3m from face of curb. When guide rail is present, minimum 1.0m behind face of guide rail.

4 When holes are drilled prior to pressure treatment of post, additional treatment of holes is not required. When holes are drilled after pressure treatment of post, additional field treatment of holes is required.

5 When top of post is not cut after pressure treatment, it does not require to be bevelled as shown. When top of post is cut after pressure treatment, it shall be bevelled at 15 to 30° angle and treated in the field.

A System configuration meets NCHRP Report 350 TL–3.

B Wooden dressed post shall be S–P–F species No. 1 or No. 2 grade.

C Wooden dressed post shall be stamped for grade, species, and treatment.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


SMALL SIGN SUPPORT SYSTEM DOUBLE BREAKAWAY WOODEN POST 89x89mm AND 89x140mm INSTALLATION–DOUBLE POST ASSEMBLY

Apr 2019 | Rev 1

OPSD 985.210

SIGN SUPPORT REQUIREMENTS

Embedment Depth	Dressed Post Size and Hole Diameter			Note 2		
				Sign Dimensions		Max. Sign Area
E	w	b	Hole Dia.	B cm	Max. H cm	A m²
1000	140	140	51	240	90	2.16
1200	140	184	76	240	150	3.60



NOTES:

1 Minimum vertical clearance of 2.1m shall be provided between the finished grade and the bottom of the lowest sign or tab.

2 Dressed post size (w and b) shall be selected to accommodate sign size specified in the Contract Documents so that maximum dimensions for sign size (B and H) and total sign area (A) including tabs shall not exceed values in the table.

3 When curb is present, minimum 0.3m from face of curb. When guide rail is present, minimum 1.0m behind face of guide rail.

4 When holes are drilled prior to pressure treatment of post, additional treatment of holes is not required. When holes are drilled after pressure treatment of post, additional field treatment of holes is required.

5 When top of post is not cut after pressure treatment, it does not require to be bevelled as shown. When top of post is cut after pressure treatment, it shall be bevelled at 15 to 30° angle and treated in the field.

A System configuration meets NCHRP Report 350 TL–3.

B Wooden dressed post shall be S–P–F species No. 1 grade.

C Wooden dressed post shall be stamped for grade, species, and treatment.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

SMALL SIGN SUPPORT SYSTEM
DOUBLE BREAKAWAY WOODEN POST
140x140mm AND 140x184mm
INSTALLATION–DOUBLE POST ASSEMBLY


Apr 2019 | Rev 1

ONTARIO STANDARD · MUNICIPAL – PROVINCIAL · OPSS


OPSD 985.220




LAP SPLICE SPACER
Gold coloured nickel/steel




4.46 kg/m RIB–BAK POST



2.61 kg/m RIB–BAK POST



Front View Top View
TYPE A, Note 1 and 3



Front View Top View
TYPE B, Note 2 and 3

SPACER FOR SIGN TO POST

NOTES:

1 Type A sign spacer shall be used with 2.61 kg/m upper post.
2 Type B sign spacer shall be used with 4.46 kg/m upper post.
3 Sign spacers shall be molded from Acrylonitrile Butadiene Styrene thermoplastic resin with an ultraviolet inhibitor finish.
A Posts and hardware depicted on this OPSD are proprietary.
B Posts shall be manufactured from hot rolled carbon steel bars according to Marion Steel Company Grade SP–80 having minimum yield strength of 552 MPa according to ASTM A 499.
C Posts shall be perforated with 11mm diameter holes @ 51mm c/c spacing or 9.4mm diameter holes @ 25mm c/c spacing.
D Posts shall be hot dip galvanized after fabrication.
E Lap splice spacer shall be fabricated from hot rolled carbon steel bars according to ASTM A36M.
F All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


SMALL SIGN SUPPORT SYSTEM
LAP SPLICE RIB–BAK BREAKAWAY SYSTEM COMPONENTS

Apr 2019 | Rev 1


ONTARIO STANDARDS MUNICIPAL – PROVINCIAL

OPSD 987.101

SIGN SUPPORT REQUIREMENTS Note 2			
Max. Sign Dimensions		Max. Sign Area	Upper Post
B cm	H cm	A m^2	kg/m
90	135	0.45	2.61
	150	0.81	4.46




FRONT



SIGN ASSEMBLY

SECTION A–A



DETAIL A

NOTES:

1 Minimum vertical clearance of 2.1m shall be provided between the finished grade and the bottom of the lowest sign or tab.

2 The upper post size (kg/m) shall be selected to accommodate the sign size specified in the Contract Documents so that maximum dimensions for sign size (B and H) and total sign area (A) including tabs shall not exceed values in the table.

3 Lower Rib–Bak post shall be 4.46 kg/m x 1.07m long.

4 When curb is present, minimum 0.3m from face of curb. When guide rail is present, minimum 1.0m behind face of guide rail.

A The system depicted on this OPSD is a propriety system and shall be installed according to manufacturer's specifications.

B This OPSD shall be read in conjunction with OPSD 987.101.

C System configuration meets NCHRP Report 350 TL–3.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

SMALL SIGN SUPPORT SYSTEM LAP SPLICE RIB–BAK BREAKAWAY SYSTEM INSTALLATION–SINGLE POST ASSEMBLY


Apr 2019 | Rev 1

OPSD 987.110


SIGN SUPPORT REQUIREMENTS Note 2			
Max. Sign Dimensions		Max. Sign Area	Upper Post
B cm	H cm	A m^2	kg/m
90 to 240	105	1.10	2.61
	150	2.02	4.46



DETAIL A



SIGN ASSEMBLY



FRONT

SECTION A–A

NOTES:

1 Minimum vertical clearance of 2.1m shall be provided between the finished grade and the bottom of the lowest sign or tab.

2 The upper post size (kg/m) shall be selected to accommodate the sign size specified in the Contract Documents so that maximum dimensions for sign size (B and H) and total sign area (A) including tabs shall not exceed values in the table.

3 Lower Rib–Bak post shall be 4.46 kg/m x 1.07m long.

4 When curb is present, minimum 0.3m from face of curb.
When guide rail is present, minimum 1.0m behind face of guide rail.

A The system depicted on this OPSD is a propriety system and shall be installed according to manufacturer's specifications.

B This OPSD shall be read in conjunction with OPSD 987.101.

C System configuration meets NCHRP Report 350 TL–3.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


SMALL SIGN SUPPORT SYSTEM
LAP SPLICE RIB–BAK BREAKAWAY SYSTEM
INSTALLATION–DOUBLE POST ASSEMBLY

Apr 2019 | Rev 1


ONTARIO STANDARDS MUNICIPAL – PROVINCIAL

OPSD 987.210


SIGN SUPPORT REQUIREMENTS Note 2			
Max. Sign Dimensions		Max. Sign Area	Upper Post
B cm	H cm	A m^2	kg/m
180 to 240	75	1.58	2.61
	150	2.92	4.46



DETAIL A



SIGN ASSEMBLY



FRONT

SECTION A–A

NOTES:

1 Minimum vertical clearance of 2.1m shall be provided between the finished grade and the bottom of the lowest sign or tab.

2 The upper post size (kg/m) shall be selected to accommodate the sign size specified in the Contract Documents so that maximum dimensions for sign size (B and H) and total sign area (A) including tabs shall not exceed values in the table.

3 Lower Rib–Bak post shall be 4.46 kg/m x 1.07m long.

4 When curb is present, minimum 0.3m from face of curb.
When guide rail is present, minimum 1.0m behind face of guide rail.

A The system depicted on this OPSD is a propriety system and shall be installed according to manufacturer's specifications.

B This OPSD shall be read in conjunction with OPSD 987.101.

C System configuration meets NCHRP Report 350 TL–3.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

SMALL SIGN SUPPORT SYSTEM
LAP SPLICE RIB–BAK BREAKAWAY SYSTEM
INSTALLATION–TRIPLE POST ASSEMBLY


Apr 2019 | Rev 1

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL


OPSD 987.310



SECTION B–B



SECTION A–A



FRONT

NOTES:

1 Minimum vertical clearance of 2.1m shall be provided between the finished grade and the bottom of the lowest sign or tab.

2 This support system shall accommodate sign board sizes specified in the Contract Documents for up to maximum sign width (B) of 120cm, up to a maximum sign height (H) of 150cm, and the total sign area including tabs shall not exceed the maximum sign area of 1.44 square metres.

3 When curb is present, minimum 0.3m from face of the curb.
When guide rail is present, minimum 1.0m behind face of guide rail.

A When Wa–33 is specified below a Rb–125, the bottom of the Wa–33 shall be 1.2m above finished grade.

B The system depicted on this OPSD is a proprietary system and shall be installed according to manufacturer's specifications.

C Posts and sleeves shall be manufactured from hot rolled carbon sheet steel, structural quality according to ASTM A 653, Grade 50 steel or ASTM A 1011, Grade 50 steel.

D Posts and sleeves manufactured from ASTM A 653, Grade 50 steel shall be stripped prior to being hot dip galvanized.

E Posts and sleeves shall be hot dip galvanized after fabrication. Excess zinc shall be removed to ensure telescoping of posts and sleeves.

F System configuration meets NCHRP Report 350 TL–3.

G All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

SMALL SIGN SUPPORT SYSTEM
SQR–LOC PERFORATED STEEL SQUARE POST SYSTEM
INSTALLATION–SINGLE POST ASSEMBLY


Apr 2019 | Rev 1

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL


OPSD 989.110



SECTION B–B



SECTION A–A



FRONT

NOTES:

1 Minimum vertical clearance of 2.1m shall be provided between the finished grade and the bottom of the lowest sign or tab.

2 This support system shall accommodate sign board sizes specified in the Contract Documents for a sign width (B) from 90cm to 240cm, up to a maximum sign height (H) of 150cm, and the total sign area including tabs shall not exceed the maximum sign area of 3.15 square metres.

3 When curb is present, minimum 0.3m from face of the curb. When guide rail is present, minimum 1.0m behind face of guide rail.

A The system depicted on this OPSD is a proprietary system and shall be installed according to manufacturer's specifications.

B Posts and sleeves shall be manufactured from hot rolled carbon sheet steel, structural quality according to ASTM A 653, Grade 50 steel or ASTM A 1011, Grade 50 steel.

C Posts and sleeves manufactured from ASTM A 653, Grade 50 steel shall be stripped prior to being hot dip galvanized.

D Posts and sleeves shall be hot dip galvanized after fabrication. Excess zinc shall be removed to ensure telescoping of posts and sleeves.

E System configuration meets NCHRP Report 350 TL–3.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

SMALL SIGN SUPPORT SYSTEM SQR–LOC PERFORATED STEEL SQUARE POST SYSTEM INSTALLATION–DOUBLE POST ASSEMBLY


Apr 2019 | Rev 1

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • OPS


OPSD 989.210



SECTION A–A




SECTION B–B




SIGN SPACER


COLD FORMED STEEL POST DETAILS, Note B and C




SECTION A–A



SECTION B–B



SIGN SPACER



OVERLAP SECTION

HOT FORMED STEEL POST DETAILS, Note B and D

NOTES:

1 Sign dimensions shall be selected up to maximum sign width (B) of 90cm, up to maximum sign height (H) of 90cm, and the total sign area including tabs shall not exceed 0.56 square metres.

2 Tolerance shall be ± 1.6mm.

3 Tolerance for thickness shall be ± 0.38mm. All other tolerances shall be ± 0.8mm.

4 Holes below grade in lower post shall be optional.

A This system may be installed on low speed roadways with barrier type curb and posted speeds less than 70 km/h.


B Posts shall be manufactured from either cold formed steel or hot formed steel.

C Cold formed steel shall have a minimum yield strength of 345 MPa and weigh a minimum of 3.36 kg/m.


D Hot formed steel shall have a minimum yield strength of 380 MPa and weigh a minimum of 3.02 kg/m.

E Post and hardware shall be hot dip galvanized after fabrication.

F All dimensions are in millimetres unless otherwise shown.




DETAIL A




FRONT


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	1
SMALL SIGN SUPPORT SYSTEM NON–BREAKAWAY U–FLANGE POST SYSTEM INSTALLATION–SINGLE POST ASSEMBLY			
	OPSD 990.110		




ELEVATION




DETAIL A



DETAIL B



MESH PANEL
OPENINGS ORIENTATION



FASTENER DETAIL

NOTES:

1 Fasteners shall be installed so that the hex nuts are on the highway side of fence.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


Nov 2012 | Rev 2

EXPANDED METAL ANTI–GLARE SCREEN INSTALLATION – CHAIN–LINK FENCE

OPSD 991.132




C BRACKET




Note 1


SPACER FOR SIGN TO POST




5.95 kg/m (4 lb/ft)
RIB–BAK POST




KEEPER PLATE




SIGN ASSEMBLY



DETAIL A



TOP



SIDE

NOTES:

1 Sign spacers shall be molded from Acrylonitrile Butadiene Styrene thermoplastic resin with an ultraviolet inhibitor finish.

A The system depicted on this OPSD is a proprietary system and shall be installed according to manufacturer's specifications.

B Posts shall be manufactured from hot rolled carbon steel bars according to Marion Steel Company Grade SP–80 having minimum yield strength of 552 MPa according to ASTM A499.

C Posts shall be perforated with 9.5mm diameter holes @ 25mm c/c spacing.

D Posts shall be hot dip galvanized after fabrication.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

INTERMEDIATE SIGN SUPPORT SYSTEM
SLIP–SAFE SUPREME RIB–BAK BREAKAWAY SYSTEM COMPONENTS

Apr 2022 | Rev | 1

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 992.101



NOTES:

1 Minimum vertical clearance of 2.1m shall be provided between the finished grade and the bottom of the lowest sign or tab.
2 The maximum dimension for the sign size including any sign tab shall be up to B = 2.4m and H = 3.0m to a maximum sign board area of 7.2m².
3 When curb is present, minimum 0.3m from face of curb.
A The system depicted on this OPSD is a propriety system and shall be installed according to manufacturer's specifications.
B The post shall be 5.95 kg/m back–to–back creating an 11.9 kg/m section.
C This OPSD shall be read in conjunction with OPSD 992.101.
D System configuration meets NCHRP Report 350 TL–3.
E System configuration meets wind speed loading of 137 km/h.
F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2018 | Rev 0

INTERMEDIATE SIGN SUPPORT SYSTEM
SLIP–SAFE SUPREME RIB–BAK BREAKAWAY SYSTEM
INSTALLATION–DOUBLE POST ASSEMBLY


ONTARIO STANDARDS MUNICIPAL – PROVINCIAL

OPSD 992.210



PLAN

SIZE OF DROP PIPE		
SEWER ID	DROP PIPE ID	APPLICATION
200	200	Storm and Sanitary
250	200	Storm and Sanitary
300	250	Storm and Sanitary
375	300	Storm and Sanitary
450	375	Storm
525	450	Storm
600	525	Storm
675	600	Storm



SECTION A–A


NOTES:

1 Concrete shall be placed to undisturbed ground and the outside face of the maintenance hole, but there shall be a minimum of 150mm of 15MPa concrete around the drop pipe.

2 Concrete shall be secured to the maintenance hole with 450mm long, 13mm diameter threaded rods and drilled expansion anchors down either side of the drop pipe at 300mm centres.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	3
CAST–IN–PLACE MAINTENANCE HOLE DROP STRUCTURE TEE			
	OPSD 1003.010		



PLAN

SIZE OF DROP PIPE	
SEWER ID	DROP PIPE ID
200	200
250	200
300	250
375	300



SECTION A–A


NOTES:

1 Concrete shall be placed to undisturbed ground and the outside face of the maintenance hole, but there shall be a minimum of 150mm of 15MPa concrete around the drop pipe.


2 Concrete shall be secured to the maintenance hole with 450mm long, 13mm diameter threaded rods and drilled expansion anchors down either side of the drop pipe at 300mm centres.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2016	Rev	3
CAST–IN–PLACE MAINTENANCE HOLE DROP STRUCTURE WYE			
		OPSD 1003.020	




INTERNAL DROP STRUCTURE DETAIL



SIDE VIEW FRONT VIEW

MAINTENANCE HOLE IN SECTION



FASTENER DETAIL

NOTES:

1 At the elbow, a stainless steel strap is required at bottom of bell.


A Internal drop structure shall be used on existing maintenance holes 1500mm diameter and larger with a minimum height of 600mm from the inlet pipe invert to the top of benching. The existing benching shall be modified as required.

B Drop pipe shall be one size smaller than the incoming sewer with a minimum 150mm diameter and maximum of 375mm diameter. A maximum of 300mm diameter for 1500mm maintenance holes.


C Straps shall not be placed within 150mm of any maintenance hole section joint.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	5
INTERNAL DROP STRUCTURE FOR EXISTING MAINTENANCE HOLES WITH OPTIONAL SIDE CLEANOUT			
	OPSD 1003.030		



INTERNAL DROP STRUCTURE DETAIL



MAINTENANCE HOLE IN SECTION



FASTENER DETAIL

NOTES:

1 At the elbow, a stainless steel strap is required at bottom of bell.


2 Straps shall not be placed within 150mm of any maintenance hole section joint.

A Internal drop structure shall be used in maintenance holes 1500mm diameter and larger and larger with a minimum height of 600mm from the inlet pipe invert to the bottom


B Drop pipe shall be one size smaller than the incoming sewer with a minimum 150mm diameter and maximum of 375mm diameter. A maximum of 300mm diameter for 1500mm maintenance holes.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	4
INTERNAL DROP STRUCTURE FOR NEW MAINTENANCE HOLES WITH OPTIONAL SIDE CLEANOUT			
	OPSD 1003.031		




INTERNAL DROP STRUCTURE DETAIL



SIDE VIEW FRONT VIEW

MAINTENANCE HOLE IN SECTION



FASTENER DETAIL

NOTES:

1 At the elbow, a stainless steel strap is required at bottom of bell.


A Internal drop structure shall be used on existing maintenance holes 1500mm diameter and larger with a minimum height of 600mm from the inlet pipe invert to the top of benching. The existing benching shall be modified as required.

B Drop pipe shall be one size smaller than the incoming sewer with a minimum 150mm diameter and maximum of 375mm diameter. A maximum of 300mm diameter for 1500mm maintenance holes.


C Straps shall not be placed within 150mm of any maintenance hole section joint.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	0
INTERNAL DROP STRUCTURE FOR EXISTING MAINTENANCE HOLES WITH TOP CLEANOUT			
	OPSD 1003.032		



INTERNAL DROP STRUCTURE DETAIL



MAINTENANCE HOLE IN SECTION



FASTENER DETAIL

NOTES:

1 At the elbow, a stainless steel strap is required at bottom of bell.


2 Straps shall not be placed within 150mm of any maintenance hole section joint.

A Internal drop structure shall be used in maintenance holes 1500mm diameter and larger with a minimum height of 600mm from the inlet pipe invert to the bottom of channel.


B Drop pipe shall be one size smaller than the incoming sewer with a minimum 150mm diameter and maximum of 375mm diameter. A maximum of 300mm diameter for 1500mm maintenance holes.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	0
INTERNAL DROP STRUCTURE FOR NEW MAINTENANCE HOLES WITH TOP CLEANOUT			
	OPSD 1003.033		



CONNECTION WITHOUT VERTICAL RISER



CONNECTION WITH VERTICAL RISER


NOTES:

1 Sewer service connections to the main pipe sewer shall be made using factory made tees, strap–on–saddles, or other approved saddles.
2 Vertical risers shall be as specified.
3 Cap or plug at property line shall be adequately braced.


A Maintenance holes shall be used at the main sewer to connect service connections greater than 200mm.
B For new construction, saddles shall be installed on the main pipe before that pipe is laid.
C Approved cut–in tool shall be used for field made connections.
D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	4
SEWER SERVICE CONNECTIONS FOR MAIN PIPE SEWER			
	OPSD 1006.010		


	100 to 250mm WATERMAIN	300 to 350mm WATERMAIN
a	1100	1300



PLAN



SECTION A–A



SECTION B–B

NOTES:

1 Exposed portion of lift rings shall be coated with heavy asphalt paint prior to backfilling operations.

A Reinforcement shall have 50mm minimum cover.


B All steel reinforcement shall be 15M at 300mm unless otherwise shown.

C This OPSD shall be read in conjunction with OPSD 1100.011.


D Joint around removable slab shall be sealed as specified.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	3
CAST–IN–PLACE CHAMBER FOR VALVES UP TO 350mm DIAMETER			
			OPSD 1100.010




PLAN



PLAN



ELEVATION



ELEVATION

	Pipe Diameter	
	100 to 250mm	300 to 350mm
a – Chamber Width	1100	1300
b	300	300
c	550	650
d	450	450
e	550	550

NOTES:

A Bond breaker shall be used between the concrete and the fittings and appurtenances.


B Concrete support shall be minimum 200mm high.

C This OPSD shall be read in conjunction with OPSD 1100.010.


D All joints shall be restrained.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	2
PIPING LAYOUT FOR BUTTERFLY AND GATE VALVES UP TO 350mm DIAMETER IN CAST–IN–PLACE CHAMBERS			
	OPSD 1100.011		




CROSS SECTION




PLAN

CAST–IN–PLACE BASE



WALL OPENING DETAIL



SECTION A–A

Dimension	Pipe diameter	
	100 to 250mm	300 to 350mm
a	ø1200	ø1500
b	400	550
c	600	750

NOTES:

1 Sump shall be placed to avoid associated appurtenances and step landing. Position steel reinforcement to maintain minimum 50mm cover at sump.

A This OPSD shall be read in conjunction with OPSD 701.030, 701.031, 701.032, 701.041, and 703.011.

B Bond breaker shall be used between the concrete and the fittings and appurtenances.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST VALVE CHAMBER

1200mm AND 1500mm DIAMETER

Nov 2015 | Rev 4

ONTARIO STANDARDS · MUNICIPAL–PROVINCIAL · O P S

OPSD 1101.010



NOTES:

A Design according to CAN/CSA S6 and Ministry of Transportation of Ontario Structural Manual, Division 1, for maximum 4.0m of earth cover.

B The valve chamber may be buoyant. Measures required to counteract buoyancy shall be as specified.


C When the combined height of chamber and chimney is 5.0m or greater, provide safety platform according to OPSD 404.010.

D Standing water shall not be allowed to accumulate during construction to within 1.6m of top of chamber when chamber is not backfilled to grade.


E Thrust blocks designed for a water pressure of 0.86 MPa and a maximum watermain size of 600mm diameter. If thrust blocks are required, they shall be placed on the outside of the chamber on the side or sides as specified.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
PRECAST CONCRETE VALVE CHAMBER WITH POURED-IN-PLACE THRUST BLOCKS 1800 x 2400mm COMPONENTS			
	OPSD 1101.012		




PLAN OF RISER




SECTION A–A




VIEW OF SIDES WITH CIRCULAR OPENING




VIEW OF SIDES WITH SLOTTED OPENING



PLAN OF BASE



SECTION B–B



SECTION C–C

NOTES:

1 Threaded inserts for the attachment of thrust blocks shall be 15M equivalent with strength of 125% of yield strength of coupled rebar. For location and number of inserts see OPSD 1101.014.
2 If no opening in a single riser, the height of that riser may be 2000 to 4500mm.
3 A+B shall be a minimum of L/2.

A Reinforcing steel shall be according to CSA G30.18, Grade 400W. Inside diameter of bends shall equal six bar diameters. Additional reinforcing shall be rebar Grade 400W.
B Main reinforcing shall be welded wire fabric, fy=500MPa, according to ASTM A497M. Minimum bend shall be six bar or four wire diameters.
C Precast concrete strength shall be 40MPa.
D Clear cover to reinforcing in precast shall be a minimum of 40mm and a maximum of 50mm.
E This OPSD shall be read in conjunction with OPSD 1101.012, 1101.014, and 1101.015.
F All dimensions are nominal.
G All dimensions are in millimetres unless otherwise shown.

LEGEND:

As means Area of Steel


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE VALVE CHAMBER WITH POURED–IN–PLACE THRUST BLOCKS 1800 x 2400mm RISER AND BASE


Nov 2018 | Rev 3

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL


OPSD 1101.013



SECTION A–A



ELEVATION OF SHORT WALL THRUST BLOCK



ELEVATION OF LONG WALL THRUST BLOCK

NOTES:

1 Threaded inserts for the attachment of thrust block shall be 15M equivalent and Dayton Superior DBR system or equal with strength of 125% of yield strength of coupled rebar.

A Reinforcing steel shall be according to CSA G30.18, Grade 400W. Inside diameter of bends shall equal six bar diameters. Additional reinforcing shall be rebar Grade 400W.

B Thrust blocks shall be poured–in–place concrete as specified.

C Thrust block concrete to be Class C–2.

D Clear cover to reinforcing steel:
- 100mm ±25mm to bottom of thrust block
- 70mm ±20mm to remainder of thrust block.

E This OPSD shall be read in conjunction with OPSD 1101.012, 1101.013, and 1101.015.

F All dimensions are in millimetres unless otherwise shown.

Thrust Block Wall	Nominal Watermain Size	Thrust Block Thickness	Thrust Block Reinforcement
Long Wall	≤ ø600	400	8–20M each face*
Short Wall	≤ ø600	350	6–20M each face*

* Other reinforcement as shown


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE VALVE CHAMBER WITH POURED–IN–PLACE THRUST BLOCKS 1800 x 2400mm THRUST BLOCKS


Nov 2018 | Rev 3

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL


OPSD 1101.014




PLAN




ELEVATION
CHIMNEY




PLAN OF CAP



SECTION A–A



PLAN



SECTION B–B

NOTES:

1 Equipment lifting system shall be installed on underside of precast concrete cap, when required.

A Precast concrete strength shall be 40MPa.

B Reinforcing steel shall be according to CSA G30.18, Grade 400W. Inside diameter of bends shall equal six bar diameters. Additional reinforcing shall be rebar Grade 400W.

C Main reinforcing shall be welded wire fabric, fy=500Mpa, according to ASTM A497M. Minimum bend shall be six bar or four wire diameters.

D Clear cover to reinforcing steel in precast shall be a minimum of 40mm and a maximum of 50mm.


E This OPSD shall be read in conjunction with OPSD 1101.012, 1101.013, and 1101.014.

F All dimensions are nominal.

G All dimensions are in millimetres unless otherwise shown.

LEGEND:

As means Area of Steel



EQUIPMENT LIFTING SYSTEM


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE VALVE CHAMBER WITH POURED–IN–PLACE THRUST BLOCKS 1800 x 2400mm CHIMNEY AND CAP

Nov 2018 | Rev 3

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL

OPSD 1101.015



NOTES:

A Design according to CAN/CSA S6 and Ministry of Transportation of Ontario Structural Manual, Division 1, for maximum 4.0m of earth cover.

B The valve chamber may be buoyant. Measures required to counteract buoyancy shall be as specified.


C When the combined height of chamber and chimney is 5.0m or greater, provide safety platform according to OPSD 404.010.

D Standing water shall not be allowed to accumulate during construction to within 1.7m of top of chamber when chamber is not backfilled to grade.


E Thrust blocks designed for a water pressure of 0.86 MPa and a maximum watermain size of 750mm diameter. If thrust blocks are required, they shall be placed on the outside of the chamber on the side or sides as specified.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
PRECAST CONCRETE VALVE CHAMBER WITH POURED-IN-PLACE THRUST BLOCKS 2400 x 3000mm COMPONENTS			
	OPSD 1101.016		




PLAN OF RISER




VIEW OF SIDES WITH CIRCULAR OPENING




PLAN OF BASE




SECTION A–A



VIEW OF SIDES WITH SLOTTED OPENING



SECTION B–B



SECTION C–C

NOTES:

1 Threaded inserts for the attachment of thrust blocks shall be 15M equivalent and Dayton Superior DBR system or equal with strength of 125% of yield strength of coupled rebar. For location and number of inserts see OPSD 1101.018.
2 If no opening in a single riser, the height of that riser may be 2000 to 4500mm.
3 A+B shall be a minimum of L/2.

A Reinforcing steel shall be according to CSA G30.18, Grade 400W. Inside diameter of bends shall equal six bar diameters. Additional reinforcing shall be rebar Grade 400W.
B Main reinforcing shall be welded wire fabric, fy=500MPa, according to ASTM A497M. Minimum bend shall be six bar or four wire diameters.
C Precast concrete strength shall be 40MPa.
D Clear cover to reinforcing in precast shall be a minimum of 40mm and a maximum of 50mm.
E This OPSD shall be read in conjunction with OPSD 1101.016, 1101.018, and 1101.019.
F All dimensions are nominal.
G All dimensions are in millimetres unless otherwise shown.

LEGEND:

As means Area of Steel


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE VALVE CHAMBER WITH POURED–IN–PLACE THRUST BLOCKS 2400 x 3000mm RISER AND BASE


Nov 2018 | Rev 3

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL


OPSD 1101.017



SECTION A–A



ELEVATION OF SHORT WALL THRUST BLOCK



ELEVATION OF LONG WALL THRUST BLOCK

NOTES:

1 Threaded inserts for the attachment of thrust block shall be 15M equivalent and Dayton Superior DBR system or equal with strength of 125% of yield strength of coupled rebar.

A Reinforcing steel shall be according to CSA G30.18, Grade 400W. Inside diameter of bends shall equal six bar diameters. Additional reinforcing shall be rebar Grade 400W.

B Thrust blocks shall be poured–in–place concrete as specified.

C Thrust block concrete to be Class C–2.

D Clear cover to reinforcing steel:
- 100mm ±25mm to bottom of thrust block
- 70mm ±20mm to remainder of thrust block.

E This OPSD shall be read in conjunction with OPSD 1101.016, 1101.017, and 1101.019.

F All dimensions are in millimetres unless otherwise shown.

Thrust Block Wall	Nominal Watermain Size	Thrust Block Thickness	Thrust Block Reinforcement
Long Wall	≤ø750	450	8–25M each face*
Short Wall	≤ø750	400	6–25M each face*

* Other reinforcement as shown


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE VALVE CHAMBER WITH POURED–IN–PLACE THRUST BLOCKS 2400 x 3000mm THRUST BLOCKS


Nov 2018 | Rev 4

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL


OPSD 1101.018




PLAN




ELEVATION
CHIMNEY




PLAN OF CAP



SECTION A–A



PLAN



SECTION B–B

NOTES:

1 Equipment lifting system shall be installed on underside of precast concrete cap, when required.

A Precast concrete strength shall be 40MPa.

B Reinforcing steel shall be according to CSA G30.18, Grade 400W. Inside diameter of bends shall equal six bar diameters. Additional reinforcing shall be rebar Grade 400W.

C Main reinforcing shall be welded wire fabric, fy=500Mpa, according to ASTM A497M. Minimum bend shall be six bar or four wire diameters.

D Clear cover to reinforcing steel in precast shall be a minimum of 40mm and a maximum of 50mm.


E This OPSD shall be read in conjunction with OPSD 1101.016, 1101.017, and 1101.018.

F All dimensions are nominal.

G All dimensions are in millimetres unless otherwise shown.

LEGEND:

As means Area of Steel



EQUIPMENT LIFTING SYSTEM


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE VALVE CHAMBER WITH POURED–IN–PLACE THRUST BLOCKS 2400 x 3000mm CHIMNEY AND CAP


Nov 2018 | Rev 3

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S

OPSD 1101.019



OPTIONAL TOP NUT DETAIL WITH SQUARE STEM



CROSS SECTION

NOTES:


1 Either the square or round stem shall be used with specified connections.

A Valve stem and valve shall be placed plumb.

B Stem guide is required if the unsupported length exceeds 2.0m.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	4
VALVE OPERATOR			
			OPSD 1101.020



NOTES:

A Design according to CAN/CSA S6 and Ministry of Transportation of Ontario Structural Manual, Division 1, for minimum 0.5m and maximum 4.0m of earth cover. The maximum buried depth to bottom of chamber is 7.5m.

B The valve chamber may be buoyant. Measures required to counteract buoyancy shall be as specified.


C When the combined height of chamber and chimney is 5.0m or greater, provide safety platform according to OPSD 404.010.

D Standing water shall not be allowed to accumulate during construction to within 1.7m of top of chamber when chamber is not backfilled to grade.


E Thrust blocks designed for a maximum water surge pressure of 1.72 MPa and a maximum opening size of 1220mm diameter. If thrust blocks are required, they shall be placed on the outside of the chamber on the side or sides specified.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	1
PRECAST CONCRETE VALVE CHAMBER WITH POURED-IN-PLACE THRUST BLOCKS 3000 x 3000mm COMPONENTS			
	OPSD 1101.030		




PLAN OF RISER




VIEW OF SIDES WITH CIRCULAR OPENING




PLAN OF BASE




SECTION A–A



VIEW OF SIDES WITH SLOTTED OPENING



SECTION B–B



SECTION C–C

NOTES:

1 Threaded inserts for the attachment of thrust blocks shall be 15M equivalent and Dayton Superior DBR system or equal with strength of 125% of yield strength of coupled rebar. For location and number of inserts see OPSD 1101.032.
2 If no opening in a single riser, the height of that riser may be 2000 to 4500mm.
3 A+B shall be a minimum of L/2 or 1200mm.

A Reinforcing steel shall be according to CSA G30.18, Grade 400W. Inside diameter of bends shall equal six bar diameters. Additional reinforcing shall be rebar Grade 400W.
B Main reinforcing shall be welded wire fabric, fy=500MPa, according to ASTM A497M. Minimum bend shall be six bar or four wire diameters.
C Precast concrete strength shall be 40MPa.
D Clear cover to reinforcing in precast shall be a minimum of 40mm and a maximum of 50mm.
E This OPSD shall be read in conjunction with OPSD 1101.030, 1101.032, and 1101.033.
F All dimensions are nominal.
G All dimensions are in millimetres unless otherwise shown.

LEGEND:

As means Area of Steel


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE VALVE CHAMBER WITH POURED–IN–PLACE THRUST BLOCKS 3000 x 3000mm RISER AND BASE


Nov 2018 | Rev 1

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • OPS

OPSD 1101.031



SECTION A–A



ELEVATION OF THRUST BLOCK

NOTES:

1 Threaded inserts for the attachment of thrust block shall be 15M equivalent and Dayton Superior DBR system or equal with strength of 125% of yield strength of coupled rebar.

A Reinforcing steel shall be according to CSA G30.18, Grade 400W. Inside diameter of bends shall equal six bar diameters. Additional reinforcing shall be rebar Grade 400W.

B Thrust blocks shall be poured–in–place concrete as specified.

C Thrust block concrete to be Class C–2.

D Clear cover to reinforcing steel:
- 100mm ±25mm to bottom of thrust block
- 70mm ±20mm to remainder of thrust block.

E This OPSD shall be read in conjunction with OPSD 1101.030, 1101.031, and 1101.033.

F All dimensions are in millimetres unless otherwise shown.


Nominal Watermain Size	Thrust Block Height	Thrust Block Thickness	Thrust Block Reinforcement	Total Inserts
≤ø900	2450	500	8–25M each face	16

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE VALVE CHAMBER WITH POURED–IN–PLACE THRUST BLOCKS 3000 x 3000mm THRUST BLOCKS

Nov 2018 | Rev 1


OPSD 1101.032




PLAN




SECTION A–A




PLAN OF CAP



SECTION B–B



PLAN



SECTION C–C

NOTES:

1 Equipment lifting system shall be installed on underside of precast concrete cap, when required.

A Precast concrete strength shall be 40MPa.

B Reinforcing steel shall be according to CSA G30.18, Grade 400W. Inside diameter of bends shall equal six bar diameters. Additional reinforcing shall be rebar Grade 400W.

C Main reinforcing shall be welded wire fabric, fy=500Mpa, according to ASTM A497M. Minimum bend shall be six bar or four wire diameters.

D Clear cover to reinforcing steel in precast shall be a minimum of 40mm and a maximum of 50mm.


E This OPSD shall be read in conjunction with OPSD 1101.030, 1101.031, and 1101.032.

F All dimensions are nominal.

G All dimensions are in millimetres unless otherwise shown.

LEGEND:

As means Area of Steel




EQUIPMENT LIFTING SYSTEM

ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE VALVE CHAMBER WITH POURED–IN–PLACE THRUST BLOCKS 3000 x 3000mm CHIMNEY AND CAP

Nov 2018 | Rev 1

OPSD 1101.033



NOTES:

A Design according to CAN/CSA S6 and Ministry of Transportation of Ontario Structural Manual, Division 1, for minimum 0.5m and maximum 4.0m of earth cover. The maximum buried depth to bottom of chamber is 7.5m.

B The valve chamber may be buoyant. Measures required to counteract buoyancy shall be as specified.


C When the combined height of chamber and chimney is 5.0m or greater, provide safety platform according to OPSD 404.010.

D Standing water shall not be allowed to accumulate during construction to within 1.7m of top of chamber when chamber is not backfilled to grade.


E Thrust blocks designed for a maximum water surge pressure of 1.72 MPa and a maximum opening size of 1220mm diameter. If thrust blocks are required, they shall be placed on the outside of the chamber on the side or sides specified.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	1
PRECAST CONCRETE VALVE CHAMBER WITH POURED-IN-PLACE THRUST BLOCKS 3600 x 3000mm COMPONENTS			
	OPSD 1101.040		




PLAN OF RISER




VIEW OF SIDES WITH CIRCULAR OPENING




PLAN OF BASE




SECTION A–A



VIEW OF SIDES WITH SLOTTED OPENING



SECTION B–B



SECTION C–C

NOTES:

1 Threaded inserts for the attachment of thrust blocks shall be 15M equivalent and Dayton Superior DBR system or equal with strength of 125% of yield strength of coupled rebar. For location and number of inserts see OPSD 1101.042.
2 If no opening in a single riser, the height of that riser may be 2000 to 4500mm.
3 A+B shall be a minimum of L/2 or 1200mm.

A Reinforcing steel shall be according to CSA G30.18, Grade 400W. Inside diameter of bends shall equal six bar diameters. Additional reinforcing shall be rebar Grade 400W.
B Main reinforcing shall be welded wire fabric, fy=500MPa, according to ASTM A497M. Minimum bend shall be six bar or four wire diameters.
C Precast concrete strength shall be 40MPa.
D Clear cover to reinforcing in precast shall be a minimum of 40mm and a maximum of 50mm.
E This OPSD shall be read in conjunction with OPSD 1101.040, 1101.042, and 1101.043.
F All dimensions are nominal.
G All dimensions are in millimetres unless otherwise shown.

LEGEND:

As means Area of Steel


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE VALVE CHAMBER WITH POURED–IN–PLACE THRUST BLOCKS 3600 x 3000mm RISER AND BASE

Nov 2018 | Rev 1

ONTARIO STANDARDS MUNICIPAL – PROVINCIAL

OPSD 1101.041



NOTES:

1 Threaded inserts for the attachment of thrust block shall be 15M equivalent and Dayton Superior DBR system or equal with strength of 125% of yield strength of coupled rebar.

A Reinforcing steel shall be according to CSA G30.18, Grade 400W. Inside diameter of bends shall equal six bar diameters. Additional reinforcing shall be rebar Grade 400W.

B Thrust blocks shall be poured–in–place concrete as specified.

C Thrust block concrete to be Class C–2.

D Clear cover to reinforcing steel:
- 100mm ±25mm to bottom of thrust block
- 70mm ±20mm to remainder of thrust block.

E This OPSD shall be read in conjunction with OPSD 1101.040, 1101.041, and 1101.043.

F All dimensions are in millimetres unless otherwise shown.


Nominal Watermain Size	Thrust Block Height	Thrust Block Thickness	Thrust Block Reinforcement	Total Inserts
≤ø900	2450	500	8–25M each face	16

ONTARIO PROVINCIAL STANDARD DRAWING


PRECAST CONCRETE VALVE CHAMBER WITH POURED–IN–PLACE THRUST BLOCKS 3600 x 3000mm THRUST BLOCKS

Nov 2018 | Rev 1


OPSD 1101.042




PLAN




SECTION A–A




PLAN OF CAP




SECTION B–B



PLAN



SECTION C–C



EQUIPMENT LIFTING SYSTEM

NOTES:

1 Equipment lifting system shall be installed on underside of precast concrete cap, when required.

A Precast concrete strength shall be 40MPa.

B Reinforcing steel shall be according to CSA G30.18, Grade 400W. Inside diameter of bends shall equal six bar diameters. Additional reinforcing shall be rebar Grade 400W.

C Main reinforcing shall be welded wire fabric, fy=500Mpa, according to ASTM A497M. Minimum bend shall be six bar or four wire diameters.

D Clear cover to reinforcing steel in precast shall be a minimum of 40mm and a maximum of 50mm.

E This OPSD shall be read in conjunction with OPSD 1101.040, 1101.041, and 1101.042.

F All dimensions are nominal.

G All dimensions are in millimetres unless otherwise shown.

LEGEND:

As means Area of Steel


ONTARIO PROVINCIAL STANDARD DRAWING

PRECAST CONCRETE VALVE CHAMBER WITH POURED–IN–PLACE THRUST BLOCKS 3600 x 3000mm CHIMNEY AND CAP


Nov 2018 | Rev 1

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL · OPS


OPSD 1101.043




PLAN
TEE




PLAN
TYPICAL BEND




PLAN
90 BEND°



SECTION X–X



PLAN
DEAD END



ELEVATION
DEAD END

SOILS WITH TYPICAL BEARING STRENGTH OF 100 TO 199 kPa

PIPE DIA	Dimensions			
	a	*b*	*c*	*d*
100	150	250	200	200
150	250	400	250	300
200	400	550	300	450
250	500	650	400	500
300	650	800	450	650
350	700	900	550	700
400	900	1050	600	850

SOILS WITH TYPICAL BEARING STRENGTH OF 200 TO 299 kPa

PIPE DIA	Dimensions			
	a	*b*	*c*	*d*
100	150	200	150	150
150	250	250	200	200
200	400	350	250	300
250	500	450	300	350
300	650	500	350	400
350	700	600	400	500
400	900	750	400	600

SOILS WITH TYPICAL BEARING STRENGTH OF 300 kPa AND OVER

PIPE DIA	Dimensions			
	a	*b*	*c*	*d*
100	150	150	150	150
150	250	200	200	200
200	400	300	200	250
250	500	400	250	300
300	650	450	300	300
350	700	550	350	350
400	900	650	350	450

NOTES:

A Concrete shall be placed to within 50mm of the face of the bell.

B Bond breaker shall be used between concrete and fittings.


C The above thrust block dimensions meet or exceed the MECP Watermain Design Criteria for Future Alterations Authorized Under a Drinking Water Works Permit.

D The assumptions made for the above calculations are:
- Maximum operating pressure of 690 kPa,
- Maximum surge pressure with a flow velocity change of 0.6 m/s of 790 kPa for Class 52 DI pipe and 240 kPa for PVC pipe.


E The tables apply to both ductile iron and PVC pipe. When one length exceeded the other, the longer length was used.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
CONCRETE THRUST BLOCKS FOR TEES, PLUGS, AND HORIZONTAL BENDS	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 1103.010		




UP–THRUST BLOCK
ELEVATION




UP–THRUST BLOCK
SECTION X–X



DOWN–THRUST BLOCK
ELEVATION



DETAIL



DOWN–THRUST BLOCK
SECTION Y–Y

NOTES:

A Concrete shall be placed to within 50mm of the face of the bell.

B Bond breaker shall be used between concrete and fittings.

C This blocking is for bends up to 45° for up–thrust and 90° for down–thrust.

D This OPSD shall be read in conjunction with OPSD 1103.021.

E All stainless steel to be type 316.

F Stainless steel rods and nuts to be designed based on actual watermain diameter and surge pressure.

G All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	4

CONCRETE THRUST BLOCKS FOR VERTICAL BENDS

OPSD 1103.020

SOILS WITH TYPICAL BEARING STRENGTH OF 100 TO 199 kPa

PIPE DIA	Note 1				
	a	*b*	*c*	*d*	*e*
100	450	600	750	13	150
150	600	900	900	13	300
200	600	900	1500	13	450
250	900	900	1500	20	600
300	1200	900	1650	20	800
350	1200	1200	1650	25	1000
400	1300	1300	1750	30	1000

SOILS WITH TYPICAL BEARING STRENGTH OF 200 TO 299 kPa

PIPE DIA	Note 1				
	a	*b*	*c*	*d*	*e*
100	450	600	750	13	150
150	600	900	900	13	300
200	600	900	1500	13	450
250	900	900	1500	20	600
300	1200	900	1650	20	800
350	1200	1200	1650	25	1000
400	1300	1300	1750	30	1000

SOILS WITH TYPICAL BEARING STRENGTH OF 300 kPa AND OVER

PIPE DIA	Note 1				
	a	*b*	*c*	*d*	*e*
100	450	600	750	13	150
150	600	900	900	13	300
200	600	900	1500	13	450
250	900	900	1500	20	600
300	1200	900	1650	20	800
350	1200	1200	1650	25	1000
400	1000	1300	1750	30	1000

NOTES:

1 The dimensions are as specified in OPSD 1103.020.

A The above thrust block dimensions meet or exceed the MECP Watermain Design Criteria for Future Alterations Authorized Under a Drinking Water Works Permit.


B The assumptions made for the above calculations are as follows:
- Maximum operating pressure of 690 kPa,
- Maximum surge pressure with a flow velocity change of 0.6 m/s of 790 kPa for Class 52 DI pipe and 240 kPa for PVC pipe.

C The tables apply to both ductile iron and PVC pipe. When one length exceeded the other, the longer length was used.


D This OPSD shall be read in conjunction with OPSD 1103.020.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	1
DIMENSION TABLES FOR CONCRETE THRUST BLOCKS FOR VERTICAL BENDS			
	OPSD 1103.021		



HORIZONTAL GOOSENECK



VERTICAL GOOSENECK OPTION



VERTICAL SECTION

NOTES:

1 For plastic service pipes, install main stop at 15° above horizontal with a minimum 1.2m long gooseneck.

2 Direct tap ductile iron pipe with approved tool with standard AWWA inlet thread.

3 Service connections to plastic watermains shall be made using service saddles or factory made tees.

A When specified, the vertical gooseneck option shall be used.


B Couplings shall not be permitted unless the service length exceeds 20m between the main stop and curb stop.

C All water services shall be installed 90° to the longitudinal axis of the watermain.

D Backfill material within 500mm of service box shall be native or imported, as specified.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	4
WATER SERVICE CONNECTION 19 and 25mm DIAMETER SIZES			
	OPSD 1104.010		



NOTES:


A Couplings shall not be permitted unless the service length exceeds 20m between the main stop and curb stop.

B All water services shall be installed 90° to the longitudinal axis of the watermain.

C Backfill material within 500mm of service box shall be native or imported, as specified.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
WATER SERVICE CONNECTION 32, 38, and 50mm DIAMETER SIZES			
	OPSD 1104.020		



PIPE CONNECTION

END CAP CONNECTION OPTION

PLAN OF WATERMAIN END

NOTES:

A Backfill material within 500mm of service box shall be native or imported, as specified.

B Refer to applicable regulations for end of pipe treatment.


C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

BLOW OFF INSTALLATION

Nov 2018 | Rev 3

OPSD 1104.030



NOTES:

1 All concrete thrust blocks shall be poured against undisturbed ground.

2 When specified, for watermains 400mm and less, locate valve within 1.0m of centreline of watermain. Retaining and restraining devices shall be utilized. For watermains 600mm and over, bolt valve with flanged end directly to flanged tee.

3 Retaining and restraining devices shall be as specified.

A Bond breaker shall be used between the concrete and the fittings and appurtenances.

B Bolts and nuts for buried flange to flange connections shall be stainless steel.

C When required, flange of standpipe extensions shall not be in frost zone.


D This OPSD shall be read in conjunction with OPSD 1103.010 and 1103.020.

E Backfill material within 500mm of service box shall be native or imported, as specified.


F Tracer wire shall be installed as specified.

G All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2018	Rev	3
HYDRANT INSTALLATION			
	OPSD 1105.010		




PLAN
NO BY–PASS



PLAN
WITH BY–PASS



ELEVATION



ELEVATION

NOTES:


1 Circular chambers may be used, such that 100mm minimum clearances from any pipe to wall shall be maintained.


2 By–pass piping shall be installed with a minimum 300mm unobstructed clearance from the outside wall of the bypass pipe to the nearest wall.

A By–pass line size shall be same size as the meter line.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	3
PIPING LAYOUT FOR WATER METERS 50mm AND SMALLER IN CHAMBERS			
	OPSD 1107.010		





ELEVATION

Pipe and Chamber Size		
Private water service pipe size mm	Minimum A m	Minimum B m
75–100	3.5	3.2
150	4.3	2.3
200	5.0	2.5
250	6.0	2.7
300	6.6	3.0

NOTES:

1 Circular chambers may be used if clearances are maintained.

2 Water meters shall be installed with a minimum 900mm unobstructed clearance in front of water meter to the nearest wall.

3 By–pass piping shall be installed with a minimum 300mm unobstructed clearance from the outside wall of the bypass pipe to the nearest wall.

4 Refer to manufacturer's installation recommendation for up and downstream piping requirement


A A 75mm meter shall have 75mm to 100mm increasers on each side.

B By–pass line size shall be same size as the meter line.


C All joints shall be restrained.

D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	3
PIPING LAYOUT FOR WATER METERS 75 TO 250mm IN CHAMBERS WITH BY–PASS			
		OPSD 1107.020	



SIDE VIEW




TOP VIEW OF METER


NOTES:

A All joints shall be restrained. Pipes and valves shall be supported.
B Flanged fittings are required for all compound meters.
C By–pass line size shall be same size as the meter line.
D Working space at the meter shall be a minimum of 2.0m in height.
E Details of this OPSD shall be verified in conjunction with OBC where it governs.
F All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	3
PIPING LAYOUT FOR WATER METERS IN BUILDING WITH BY–PASS			
	OPSD 1107.030		



PLAN



SECTION A–A

LEGEND:

∠ means length

NOTES:

1 When specified, location of remote reader cable sleeve according to the Contract Documents.

A Reinforcing bars shall have minimum 50mm cover.


B Frame and cover shall be according to OPSD 402.030.

C Flexible sealant shall be used where pipe goes through the wall.

D Reinforcing steel deformed bars shall be CAD/CSA–G30.18, Grade 400R or W.

E When casting against earth, reinforcing bars minimum cover shall be 75mm. In all other cases, the reinforcing bars minimum cover shall be 50mm.

F All dimensions are in millimetres unless otherwise shown.



DETAIL

REMOTE READER CABLE SLEEVE


METER SIZE	∠
75 and 100	3400
150	3700
200	4100
250	4600

ONTARIO PROVINCIAL STANDARD DRAWING

CAST–IN–PLACE WATER METER CHAMBER FOR 75 TO 250mm METERS

Nov 2018 | Rev 3

OPSD 1108.010




WIRING DETAIL IN TEST STATION

NOTES:

1 Anode shall be placed at least 1.0m away from the water system pipe and appurtenances and as deep as the bottom of the pipe and appurtenances or as specified in Contract Documents.
2 Anode connecting wires shall be loosely wrapped around pipes and fittings and knotted.
3 The test station shall be set flush with the final grade as shown or post–mounted.
4 Protective coating shall be applied to all thermite welds.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev	3
CATHODIC PROTECTION FOR METALLIC WATERMAIN SYSTEMS			
	OPSD 1109.010		




NOTES:

1 Anode shall be placed at least 1.0m away from the water system pipe and appurtenances and as deep as the bottom of the pipe and appurtenances or as specified in Contract Documents.
2 Anode connecting wire shall be loosely wrapped around pipes and fittings and knotted.
3 Protective coating shall be applied to all thermite welds.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev	3
CATHODIC PROTECTION FOR PVC WATERMAIN SYSTEMS			
	OPSD 1109.011		



PLAN



ELEVATION

NOTES:


1 Anodes shall be spaced as far apart as anode wires and excavation permit.

2 Where the watermain is exposed, the connection shall be made with a thermite weld on the existing watermain.

A Protective coating shall be applied to all thermite welds.

B All dimensions are in metres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev	2
CATHODIC PROTECTION OF EXISTING METALLIC WATERMAINS EXPOSED SERVICE OR PIPE METHOD			
	OPSD 1109.012		




NOTES:

1 Protective coating shall be applied to all thermite welds.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev	2
ANODE INSTALLATION OVER PIPE METHOD FOR EXISTING METALLIC WATERMAINS			
	OPSD 1109.013		



NOTE:

1 Header wire shall not be cut during splicing.

2 Test station shall be flush–mounted or pole–mounted, as specified.

A Wiring detail in test station shall be according to OPSD.1109.010.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

HORIZONTAL ANODE BANK AT SERVICE

Nov 2020 | Rev 2

OPSD 1109.014



NOTE:

1 Header wire shall not be cut during splicing.

2 Test station shall be flush–mounted or pole–mounted, as specified.

A Wiring detail in test station shall be according to OPSD.1109.010.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING

VERTICAL ANODE BANK AT SERVICE

Nov 2020 | Rev 2

OPSD 1109.015




NOTE:
A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


WATERPROOFING OF SPLICES

Nov 2015 | Rev 1

OPSD 1109.025



PLAN



T = thickness of insulation

SECTION A–A
TYPICAL PIPE INSULATION DETAIL

NOTES:

1 The insulation material shall be extruded polystyrene according to OPSS 1605 with a minimum compressive strength of 275 kPa.

2 Pipe embedment or bedding, cover, and backfill shall be according to:
a) Flexible OPSD 802.010, 802.013, 802.020, and 802.023.
b) Rigid – OPSD 802.030, 802.031, 802.032, 802.033, 802.050, 802.051, 802.052, and 802.053.


A Minimum insulation thickness shall be 50mm.

B Joints shall be staggered for multiple insulation sheets.

C This OPSD is to be read in conjunction with OPSD 3090.100 and 3090.101.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev	1
INSULATION FOR SEWERS AND WATERMAINS IN SHALLOW TRENCHES			
	OPSD 1109.030		



TYPE I

TYPE II

ELEVATION



PILE DRIVING SHOE

SECTION A–A

NOTES:


A Flange plates shall be according to CSA G40.20/G40.21, Grade 300W.


B Welding shall be according to CSA W59.

C Driving shoe Type I shall be used unless Type II is specified.


D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2010	Rev	2
FOUNDATION PILES STEEL H–PILE DRIVING SHOE			
	OPSD 3000.100		







BUTT WELD



SECTION A–A






BUTT WELD WITH SPLICE PLATES

SECTION B–B


NOTES:

A The pile splice shall be perpendicular to the centreline of pile.
B Splice plates shall be according to CSA G40.20/G40.21, Grade 300W.
C Welding shall be according to CSA W59.
D Splice plate alternative is only applicable to H–pile sizes HP310x79, HP310x110, and HP310x132.
E Splice weld shall be complete joint penetration (CJP) butt weld perpendicular to centreline of pile.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	2
FOUNDATION PILES STEEL H–PILE SPLICE			
	OPSD 3000.150		



PILE POINT



SECTION A–A

SECTION B–B

NOTES:

A Material for the 100mm dia pile point shall be according to ASTM A 576 UNS designation G10450.


B Welding shall be according to CSA W59.

C Each pile point tip shall be pre–tested by an approved testing laboratory to establish the Brinell hardness and a certificate stating the hardness shall be affixed to each point.

D C180x18 shall be according to CSA G40.20/G40.21, Grade 300W.

E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2010	Rev	1
FOUNDATION PILES STEEL HP 310 OSLO POINT			
	OPSD 3000.201		




TYPE I **TYPE II**

SHOE DETAILS

(*) or tube wall thickness whichever is smaller.

	Plate Thickness	
Pipe Diameter (mm)	X (mm)	Y (mm)
D < 324	25	12
324 ≤ D ≤ 406	40	15
406 < D ≤ 610	50	25




BOTTOM VIEW

NOTES:

A Driving shoe Type I or II as specified.
B Welding shall be according to CSA W59.
C Steel plates shall be according to CSA G40.20/G40.21, Grade 300W/350W.
D All dimensions are in millimeters unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	2
FOUNDATION PILES STEEL TUBE PILE DRIVING SHOE			
	OPSD 3001.100		




SPLICE DETAILS

NOTES:


A Splice weld shall be complete joint penetration (CJP) butt weld perpendicular to centreline of pile.

B Welding shall be according CSA W59.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev 2	ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL ·
FOUNDATION PILES STEEL TUBE PILE SPLICE			OPSD 3001.150



PLAN



DETAIL A



SECTION A–A


NOTES:

A Welding shall be according to CSA W59.

B Steel for structural angle shall be according to CSA G40.20/G40.21, Grade 300W.

C All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2010	Rev	1
FOUNDATION PILES STEEL SHEET PILE ANCHORAGE			
	OPSD 3002.200		




NOTE:

1 Nails shall be 100mm common nails in accordance with ASTM F1667.

A Steel plate shall be according to CSA G40.20/G40.21, Grade 300W.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	2
FOUNDATION PILES WOODEN PILE DRIVING SHOE			
	OPSD 3003.100		



NOTE:

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2010	Rev	1
FOUNDATION PILES WOODEN PILE HEAD PROTECTION			
	OPSD 3003.150		

NOTES:

A These values are approximate and should only be used where the recommendations of a geotechnical engineer are not available.

B This information is based on the Ministry of Transportation and Communications Research Publication RR225 "Aspects of Prolonged Exposure of Pavements to Sub-Zero Temperatures" dated December 1981.

C Values between contours should be interpolated. If interpolation is not possible, use the adjacent contour with the greater depth.

D Frost penetration depths are in metres.

ONTARIO PROVINCIAL STANDARD DRAWING

FOUNDATION
FROST PENETRATION DEPTHS
FOR NORTHERN ONTARIO

Nov 2010 | Rev 1

OPSD 3090.100


ONTARIO PROVINCIAL STANDARD DRAWING

FOUNDATION
FROST PENETRATION DEPTHS
FOR SOUTHERN ONTARIO

Nov 2010

Rev 1

OPSD 3090.101




NOTES:

A These values are approximate and should only be used where the recommendations of a geotechnical engineer are not available.


B This information is based on the Ministry of Transportation and Communications Research Publication RR225 "Aspects of Prolonged Exposure of Pavements to Sub–Zero Temperatures" dated December 1981.

C Values between contours should be interpolated. If interpolation is not possible, use the adjacent contour with the greater depth.

D Frost penetration depths are in metres.



INTEGRAL ABUTMENT



ABUTMENT

NOTES:

1 d = depth of combined base and subbase courses
f = frost penetration depth as specified

2 Dimensions perpendicular to back face of abutment.

3 Height to be consistent with positive drainage of subdrain as specified.

4 Where specified, wall drains shall be installed according to OPSD 3190.100.

5 150mm dia perforated pipe subdrain wrapped with geotextile.


A Lateral limits of granular backfill to bridge abutment to be inside face to inside face of retaining wall or wingwall. Frost taper shall extend the full width of the backfill unless interrupted by the retaining wall or wingwall.

B Sections shown are parallel to centreline of roadway.


C Subdrain shall be installed with a 2% gradient behind wall.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2010	Rev	1
WALLS **ABUTMENT, BACKFILL** **MINIMUM GRANULAR REQUIREMENT**			
	OPSD 3101.150		




PLAN



DETAIL A



SECTION A–A
ABUTMENT CONSTRUCTED BEFORE ROCK FILL



SECTION A–A
ABUTMENT CONSTRUCTED AFTER ROCK FILL

NOTES:

1 Height to be consistent with positive drainage of subdrain as specified.

A Dimensions perpendicular to back face of abutment.

B Grading and compaction of rock backfill and rock fill shall be as specified.


C Lateral limits of backfill to be inside face to inside face of wingwall.

D Section A–A parallel to centreline of roadway.


E Subdrain shall be installed with a 2% gradient behind wall.

F All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev 2
WALLS ABUTMENT, BACKFILL ROCK		OPSD 3101.200



PLAN



ELEVATION

NOTE:

1 Height to be consistent with positive drainage of subdrain as specified.


2 150mm dia perforated pipe subdrain wrapped with geotextile.

A Subdrain shall be installed with a 2% gradient behind wall.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2010	Rev	1
WALLS **ABUTMENT** **BACKFILL DRAIN**			


OPSD 3102.100




TYPE I



TYPE II



TYPE III




PLAN OF JOINT DETAIL IN CONCRETE TOE WALLS AT 3.0m SPACING

NOTES:


1 Walls shall be founded on undisturbed soil having a minimum bearing capacity at ultimate limit states of 200kPa for Type I and 300kPa for Type II and Type III.
2 Excavation for toe walls shall be backfilled with free draining granular material.
3 10mm preformed joint filler, Type A, non–extruding and resilient bituminous type as specified.
4 Cold applied rubber asphalt joint sealing compound.
5 Where specified, wall drains shall be installed as per OPSD 3190.100.
6 150mm dia perforated pipe subdrain wrapped in geotextile.

A Maximum height of slope above top of wall is 4m.
B Concrete for toe walls shall be 30MPa.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2010	Rev	2
WALLS RETAINING CONCRETE TOE WALL			
	OPSD 3120.100		



CANTILEVER WALL
RESTRICTED ROW



CANTILEVER WALL
CUT TREATMENT



COUNTERFORT AND CANTILEVER WALL
FILL TREATMENT
SHOULDER OVER RETAINING WALL BACKFILL

NOTES:

1 d = depth of combined base and subbase courses.
f = frost penetration depth as specified.

2 Dimensions perpendicular to back face of retaining wall.

3 Height to be consistent with positive drainage of subdrain as specified.

4 150mm dia perforated pipe subdrain wrapped with geotextile. Provision shall be made to carry pipe through counterfort wall.

5 Where specified, wall drains shall be installed as per OPSD 3190.100.


A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


WALLS
RETAINING, BACKFILL
MINIMUM GRANULAR REQUIREMENT

Nov 2010 | Rev 1


OPSD 3121.150



SECTION A–A



ELEVATION



SECTION B–B

NOTES:


1 Bottom half of drain to be contoured to shape of vertical groove after removal of formwork.


2 Geotextile shall be non–woven, Class II, with an FOS of 125–250 µm.

A Minimum cover to reinforcing bars shall be measured from the base of the groove.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2011	Rev	2
WALLS RETAINING AND ABUTMENT WALL DRAIN			
	OPSD 3190.100		





ANCHORAGE DETAIL
SECTION A–A



ALTERNATIVE ANCHORAGE DETAIL
SECTION A–A

NOTES:

1 The length of L150x150x13mm shall be as specified.

A All steel shall be according to CSA G40.21, Grade 300W.

B Cutwater shall be hot dip galvanized after fabrication as specified.


C Welding shall be of a low hydrogen classification and according to CSA W59 with E480xx electrodes.

D Anchor studs shall be attached using fusion weld process.


E All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2022	Rev	2
PIERS CUTWATER ASSEMBLY			

OPSD 3290.100



BOTTOM OF DECK BELOW TOP OF GIRDER




BOTTOM OF DECK ABOVE TOP OF GIRDER

NOTES:


1 Dimension shall not be less than the specified slab thickness.

A This OPSD is also applicable to precast box girders.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev 2	
DECK GIRDERS, CONCRETE METHOD OF OBTAINING SCREED ELEVATIONS			OPSD 3310.100



STEEL BOX GIRDER



STEEL I GIRDER




DETAIL A

FORMWORK IN PLACE


NOTE:

1 Dimension shall not be less than the specified slab thickness.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2019	Rev	2
DECK GIRDERS, STEEL METHOD OF OBTAINING SCREED ELEVATIONS			
	OPSD 3311.100		




OUTSIDE FACE – ELEVATION



SECTION A–A



SECTION B–B



DETAIL A

DIMENSIONS:


a = h/4, Maximum 600mm
b = h/4, Maximum 400mm
c = b–175
h = designed web length

NOTES:


1 Door hinges shall be fabricated from 6mm thick plate minimum and hot–dip galvanized. The door hinge assembly shall be attached using M16 bolts.
2 Install M20 bolts with nuts accessible on exterior of web and weld bolt heads from the inside to the framing plate.
3 Bolts shall be ASTM A325M, Type 3.

A Hinges and grab bars shall be according to CSA G40.20/G40.21, Grade 300W. The remainder of the steel shall be the same as for the box girder.
B Access hatch shall be placed on interior web of box girder only.
C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2022	Rev	3
DECK GIRDERS, STEEL BOX ACCESS HATCH			
	OPSD 3311.900		



SECTION A–A



SECTION B–B



TYPICAL SLAB CROSS SECTION

NOTES:


1 Dimension to suit specified nominal cover.

A Bar supports shall be Class D or Class E for maximum protection as detailed in the RSIC Reinforcing Steel Manual of Standard Practice.


B Metal portions of continuous bar supports shall be plastic encased or approved equivalent.

C Individual bar supports shall be firmly fixed to reinforcing bars. Continuous bar supports shall be tied at every fourth intersection with mat bars and shall meet the cover requirements specified.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	2
DECK, REINFORCEMENT SUPPORTS FOR REINFORCING STEEL FOR SLAB DEPTHS 300mm OR LESS			
	OPSD 3329.100		




SECTION A–A



SECTION B–B



DECK WITH RECTANGULAR VOIDS



SOLID DECK OR WITH ROUND VOIDS

NOTES:

1 Dimension to suit specified nominal cover.


A Individual bar supports shall be placed on a grid of 900mm maximum, except at webs when it is to be continued.

B Bar supports shall be Class D or Class E for maximum protection as detailed in the RSIC Reinforcing Steel Manual of Standard Practice.


C Metal portions of continuous bar supports shall be plastic encased or approved equivalent.

D Individual bar supports shall be firmly fixed to reinforcing bars. Continuous bar supports shall be tied at every fourth intersection with mat bars and shall meet the cover requirements specified.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2017	Rev	2
DECK, REINFORCEMENT SUPPORTS FOR REINFORCING STEEL FOR SLAB DEPTHS GREATER THAN 300mm			
	OPSD 3329.101		



SECTION



SIDE VIEW

CORRUGATED METAL VOIDS OD	STRAPPING SPACING	UPLIFT FORCE TO BE RESISTED, Note 4 kN/m
250 – 450	1500	5.3
475 – 600	1300	8.8
625 – 750	1200	13.2
775 – 900	1000	18.5
925 – 1050	800	24.7
1075 – 1200	600	31.8

NOTES:

1 Bolts shall be removed before post–tensioning operations.

2 Void form support height shall be such that the specified cover to the voids is provided.

3 Strut location shall be such that it does not interfere with reinforcement or ducts.

4 Approved alternative tie–down systems and spacing shall resist the uplift force.

5 Strapping shall be according to CAN/CGSB 43.24M, Type 1, Grade 1.

A Void loop tie–down unit and strapping size and spacing shall suit void size.


B Void form support size to suit spacing indicated and shall be hot dip galvanized as specified.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	2
DECK ROUND VOIDS FORM SUPPORTS AND TIE–DOWNS			

ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL • O P S

OPSD 3332.100



TYPICAL DETAIL WITH FORMWORK IN PLACE



TYPICAL DETAIL WITH FORMWORK REMOVED


NOTES:

1 For corrugated voids, the drainage tubes shall be inserted at the lowest points of the corrugations and shall not protrude above the inside face of the void at those points.


A One of the drainage tubes shall be placed maximum 300mm from the lower end of each void tube.

B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2010	Rev	1
DECK ROUND VOIDS DRAINS			
	OPSD 3333.100		



TYPICAL DETAIL WITH FORMWORK IN PLACE



TYPICAL DETAIL AFTER FORMWORK REMOVED


NOTES:

1 The drainage tubes shall be located at the lower side of each void and shall not protrude above the inside face of the void at those points.


A One of the drainage tubes shall be placed 300mm maximum from the lower end of each void.

B All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2010	Rev 1	
DECK TRAPEZOIDAL VOID DRAINS			OPSD 3333.101




FRAME
PLAN




DETAIL B




SECTION C–C




CLAMP
PLAN




SECTION E–E




SECTION D–D




HATCH
PLAN



SECTION B–B



SECTION A–A



DETAIL A

Drill and tap square bar to suit M12x45mm long stainless steel hex socket head cap screw with stainless steel washer 13 ID x 22 OD x 3mm thick, 4 places

NOTES:

A All steel shall be according to CSA G40.20/G40.21, Grade 300W.

B All steel shall be hot–dip galvanized after fabrication as specified, except for stainless steel.

C All welded construction shall be according to CSA W59 for steel and CSA W59.2 for aluminum. Any company undertaking welded fabrication or erection or both according to CSA W59 or CSA W59.2 shall be certified according to CSA W47.1, Division 2.1, or CSA W47.2, Division 2, respectively. All welding shall be carried out by welders having a CSA W47.1 or CSA W47.2 identification card valid for the type of welding to be done and for the duration of the welding work.

D Anchor studs shall be attached using a stud welding process.

E Access hatch components shall be aluminum according to CSA S157/S157.1 for Alloy 6061–T6 or T651.

F All sharp edges shall be rounded 2mm.

G All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2022 | Rev 3

DECK, VOIDS
ACCESS HATCH FOR CONCRETE BRIDGES
ASSEMBLY


ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •

OPSD 3339.100



PLAN

Aluminum hatch not shown



SECTION A–A


NOTES:

A This OPSD shall be read in conjunction with OPSD 3339.100.


B Reinforcing steel shall be according to CSA G30.18, Grade 400W.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2011	Rev	1
DECK, VOIDS ACCESS HATCH FOR CONCRETE BRIDGES INSTALLATION			
	OPSD 3339.101		



PLAN



SECTION A–A



DRAIN

NOTES:

1 Length and shape of downspout as specified.

A Drains shall be hot dip galvanized after fabrication according to ASTM A 123.


B Anchor studs shall be attached using fusion weld process.

C Pipe shall be according to ASTM A 53M, Grade B.


D All welding shall be of a low hydrogen classification and according to CSA W59.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	2
DECK DRAINS WITH DOWNSPOUT			
	OPSD 3340.100		



PLAN



SECTION A–A



DRAIN

NOTES:

1 Placement and length of downspout as specified.

A Drains shall be hot dip galvanized after fabrication according to ASTM A 123.


B Anchor studs shall be attached using fusion weld process.

C Pipe shall be according to ASTM A 53M, Grade B.


D All welding shall be of a low hydrogen classification and according to CSA W59.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2014	Rev	2
DECK DRAINS WITH SLOPED DOWNSPOUT			
	OPSD 3340.102		




PLAN OF DRAIN




SECTION C–C



SECTION A–A



CATCH BASIN DETAILS



SECTION B–B

NOTES:

1 Shape and length of downspout as specified. When the drain location conflicts with end of barrier form, drain may move a maximum of 1.5m along length of barrier.

2 End bars shall be 12x38mm steel bar and centre bars shall be 12x50mm steel bar.

A After fabrication, drains shall be hot–dip galvanized as specified.


B Pipe shall be according to ASTM A53M, Grade B.

C Steel bar shall be according to ASTM A53M, Grade B.


D All welding shall be of a low hydrogen classification and according to CSA W59.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	3
DECK DRAINS WITH TRANSVERSE BAR OPENINGS			
	OPSD 3340.150		




PLAN OF DRAIN




SECTION C–C



SECTION A–A



SECTION B–B



CATCH BASIN DETAILS

NOTES:

1 Shape and length of downspout as specified.

2 End bars shall be 12x38mm steel bar and centre bars shall be 12x50mm steel bar.

A After fabrication, drains shall be hot–dip galvanized as specified.


B Pipe shall be according to ASTM A53M, Grade B.

C Steel bar shall be according to CSA G40.21, Grade 300W.


D All welding shall be of a low hydrogen classification and according to CSA W59.

E All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2022	Rev	3
DECK DRAINS MEDIAN WITH TRANSVERSE BAR OPENINGS			
	OPSD 3340.153		



PLAN OF DRAIN



DETAIL FOR SETTING



MODIFIED DRAIN
SECTION A–A

NOTES

A Dimensions of steel pipe extension shall match existing pipe dimensions.

B Steel pipe for drain modification shall be according to ASTM A53M, Grade B.

C Steel bar shall be according to CSA G40.21, Grade 300W.


D Welding electrodes shall be of low hydrogen classification and according to CSA W59.

E After fabrication, modification assembly shall be hot–dip galvanized as specified.


F Field welds shall be painted with an approved zinc rich paint.

G All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2022	Rev 3
DECK DRAINS WITH DOWNSPOUT MODIFICATION FOR ADDITION OF ASPHALT TO EXISTING STRUCTURE		OPSD 3340.200



PLAN OF DRAIN



DETAIL FOR SETTING




MODIFIED DRAIN
SECTION A–A


NOTES:

A The steel pipe for drain modification shall be according to ASTM A53M, Grade B.
B Steel shall be according to CSA G40.21, Grade 300W.
C After fabrication, modification assembly shall be hot–dip galvanized as specified.
D Dimensions of steel pipe extension shall match existing pipe dimensions.
E Field welds shall be painted with an approved zinc rich paint.
F All welding shall be of a low hydrogen classification and according to CSA W59.
G All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	3
DECK DRAINS WITH SLOPED DOWNSPOUT MODIFICATION FOR ADDITION OF ASPHALT TO EXISTING STRUCTURE			
	OPSD 3340.201		



PLAN



SECTION A–A




DETAIL A

ISOMETRIC VIEW OF MODIFICATION ASSEMBLY


NOTES:

A Steel shall be according to CSA G40.21, Grade 300W.
B After fabrication, modification assembly shall be hot–dip galvanized as specified.
C Dimensions of steel extension shall match existing dimensions.
D Field welds shall be painted with an approved zinc rich paint.
E All welding shall be of a low hydrogen classification and according to CSA W59.
F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	3
DECK DRAINS WITH TRANSVERSE OR LONGITUDINAL BAR OPENINGS MODIFICATION FOR ADDITION OF ASPHALT TO EXISTING STRUCTURE			
	OPSD 3340.250		



TOP DECK PLAN



SECTION A–A



DRAINAGE TUBE SUPPORT DETAILS

NOTES:

1 Top of drain shall be installed flush with top of concrete deck. Flexible coupler and drain extension shall be installed after removal of deck formwork. All metal parts shall be galvanized as specified.

A PVC drainage tubes shall be rigid type.

B Drainage tubes shall be placed at low points of the bridge deck to prevent ponding of water.


C No waterproofing compound shall be allowed to seal the drainage tubes. Drainage tubes shall be cleaned out prior to placing asphalt.

D Drain extension shall be securely fastened to substructure as shown.


E Drainage tubes shall be straight and shall be positioned to avoid any interference with beams, end diaphragms, stressing cables, voids, and to prevent discharge onto bearing seats of piers or abutments.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	3
DECK, DRAINS DRAINAGE OF NEW DECK BELOW ASPHALT WEARING SURFACE			
	OPSD 3349.100		



TOP DECK PLAN



SECTION A–A



DRAINAGE TUBE SUPPORT DETAILS

NOTES:

1 Top of drain shall be installed flush with top of concrete deck. Flexible coupler and drain extension shall be installed after removal of any deck formwork. All metal parts shall be galvanized as specified.

A PVC drainage tubes shall be rigid type.

B Drainage tubes shall be placed at low points of the bridge deck to prevent ponding of water.


C No waterproofing compound shall be allowed to seal the drainage tubes. Drainage tubes shall be cleaned out prior to placing asphalt.

D Drain extension shall be securely fastened to substructure as shown.

E Drainage tubes shall be straight and shall be positioned to avoid any interference with beams, end diaphragms, stressing cables, voids, and to prevent discharge onto bearing seats of piers or abutments.


F All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2022	Rev	3
DECK, DRAINS DRAINAGE OF EXISTING DECK BELOW ASPHALT WEARING SURFACE			
	OPSD 3349.101		



PLAN

Barrier wall not shown




SECTION A–A

NOTES:

A Reinforcing steel for deck and barrier wall not shown.
B Cover to reinforcing steel 70mm ±20mm, except as noted.
C Stainless steel bars shall be Type 316LN or Duplex 2205 with a minimum yield strength of 500 MPa.
D Read in conjunction with bridge electrical details.
E Anchorage based on 4–32mm dia studs on 406mm bolt circle diameter.
F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2016	Rev	2
DECK LIGHT POLE BASES STRUCTURES WITH BARRIER WALLS			

OPSD 3360.100



PLAN

Parapet wall not shown




SECTION A–A


NOTES:

A Reinforcing steel for deck and barrier wall not shown.
B Cover to reinforcing steel 70mm ±20mm, except as noted.
C Stainless steel bars shall be Type 316LN or Duplex 2205 with a minimum yield strength of 500 MPa.
D Read in conjunction with bridge electrical details.
E Anchorage based on 4–32mm dia studs on 406mm bolt circle diameter.
F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2016	Rev	2
DECK LIGHT POLE BASES STRUCTURES WITH PARAPET WALLS			
	OPSD 3360.200		




SECTION AT JOINTS EXCEPT AT EXPANSION JOINT ASSEMBLIES




SECTIONS WITH CHASE



SECTIONS WITHOUT CHASE



SECTION AT EXPANSION JOINT ASSEMBLY INSTALLED BEFORE PAVING



SECTION AT EXPANSION JOINT ASSEMBLY INSTALLED AFTER PAVING

NOTES:

1 Existing joint filler to be removed as shown. Depth may vary when removing a neoprene joint filler at expansion joint.
2 Saw cut groove in pavement to be centred over joint and filled with hot–poured rubberized asphalt joint sealing compound.
3 5mm ±1mm thickness of asphalt to be tapered to zero in a distance not less than 1.0m from concrete dams.
4 20mm wide full depth saw cut groove in hot mix asphalt to be filled with hot–poured rubberized asphalt joint sealing compound.
5 5mm ±1mm hot applied asphalt membrane.


A Joint filler Type A as specified.
B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


DECK, WATERPROOFING HOT APPLIED ASPHALT MEMBRANE WITH PROTECTION BOARD

Nov 2008 | Rev 2


OPSD 3370.100




JOINT IN CONCRETE OVERLAY
DIRECTLY ABOVE JOINT
IN BRIDGE DECK




JOINT BETWEEN BRIDGE DECK
AND APPROACH SLAB
WITH CONCRETE OVERLAY




JOINT OR ACTIVE WIDE CRACK
IN BRIDGE DECK




NO JOINT IN CONCRETE OVERLAY
JOINT IN BRIDGE DECK



JOINT BETWEEN BRIDGE DECK
AND APPROACH SLAB
WITHOUT CONCRETE OVERLAY



JOINT BETWEEN CONCRETE DECK
AND GRANULAR BACKFILL



JOINT IN CONCRETE OVERLAY
NO JOINT IN BRIDGE DECK

NOTES:


1 Cracks in concrete to be repaired as specified.

A This OPSD is to be read in conjunction with OPSD 3370.100.


B Protection board is not shown for clarity.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2008	Rev 2
DECK, WATERPROOFING HOT APPLIED ASPHALT MEMBRANE AT ACTIVE CRACKS GREATER THAN 2mm WIDE AND CONSTRUCTION JOINTS		
		OPSD 3370.101



SECTION



LOCATION OF DRIP CHANNEL WITH CONSTRUCTION JOINT



DRIP CHANNEL DETAIL

NOTES:


1 This dimension shall be 150mm, unless a vertical construction joint is within 250mm of the edge of structure, as shown.

A Drip channel detail applies to all types of concrete deck slabs.


B Drip channel shall be continuous along soffit.

C All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	2
DECK DRIP CHANNEL			
	OPSD 3390.100		



2 LANE FACILITY
1 LANE IN EACH DIRECTION



4 LANE FACILITY
2 LANES IN EACH DIRECTION



6 LANE FACILITY
3 LANES IN EACH DIRECTION


NOTES:

1 Shoulder width shall be as specified.


2 Lane widths shall be as specified.

A All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2005	Rev	0
FALSEWORK CLEARANCE TO TRAFFIC LANES			
	OPSD – 3390.150		




ELEVATION



SECTION A–A





EMBEDDED PLATE ANCHOR DETAIL

NOTES:

1 If curb or sidewalk in front of the barrier wall is 300mm or greater in width, the mounting height shall be measured vertically to the top of the concrete surface.

A This OPSD to be read in conjunction with OPSD 912.401 and 912.430.

B Steel according to CSA G40.21, Grade 300W.

C Studs to be welded using fusion weld process.


D Welding shall be of a low hydrogen classification according to CSA W59 with E480xx electrodes.

E Anchor to be hot dip galvanized after fabrication according to CSA G164.

F All bolts shall be liberally coated with antiseize compound.

G All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2022	Rev	2
BARRIERS AND RAILINGS STEEL BEAM GUIDE RAIL AND CHANNEL ANCHORAGE			
	OPSD 3419.100		



ELEVATION

NOTES:

A Wire struts shall be SAE 1030 steel. Coils shall be SAE 1018 steel.

B Anchor bolts and hardened steel washers shall be according to ASTM F3125.

C All welding shall be according to CSA W59.


D The complete anchorage assembly including bolts, nuts, and washers shall be hot dip galvanized according to CSA G164.

E Bolts shall be given a liberal coating of white non–staining grease.


F A plywood setting template shall be provided for accurate positioning of anchorage within the concrete form. Thickness of template shall not exceed thickness of base plate being installed.

G All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev	2
BARRIERS AND RAILINGS STEEL SINGLE RAILING ANCHORAGE			
	OPSD 3419.150		



SECTION A–A



ELEVATION

NOTES:

1 A plywood setting template shall be provided for accurate positioning of anchorage within the concrete form. Template shall be sized so as to be supported by the formwork. Thickness of template shall not exceed thickness of base plate being installed.

A Wire struts shall be SAE 1030 steel. Coils shall be SAE 1018 steel.

B Anchor bolts and hardened steel washers shall be according to ASTM A 325.


C All welding shall be according to CSA W59.

D The complete anchorage assembly including bolts, nuts, and washers shall be hot dip galvanized according to CAN/CSA G164M.


E Bolts shall be given a liberal coating of white non–staining grease.

F All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2021	Rev 2	ONTARIO STANDARDS • MUNICIPAL – PROVINCIAL •
BARRIERS AND RAILINGS STEEL DOUBLE RAILING ANCHORAGE			OPSD 3419.155




TWINNED CONCRETE VOIDED
POST–TENSIONED DECKS



TRAPEZOIDAL CONCRETE BOX
POST–TENSIONED DECK



SLAB–ON–CONCRETE OR STEEL I TYPE GIRDERS



SLAB–ON–CONCRETE OR STEEL BOX GIRDERS

NOTE:

A Polypropylene pull rope shall be installed in ducts.

B Expansion and deflection fitting assembly shall be provided to accommodate design movements.

C Ends of ducts shall be sealed using plastic caps.

D Utility shall supply ducts, wobble joints, plastic caps, pull rope, duct seal, and epoxy impregnated tape, unless otherwise specified.


E Location, number, and details of ducts and duct supports shall be as specified.

F Location of ducts and duct supports shall allow access for future inspection of girders and deck.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2012	Rev	1
UTILITIES DUCT LOCATION			

ONTARIO STANDARDS · MUNICIPAL – PROVINCIAL ·

OPSD 3900.100



PLAN

NOTE:
1 Duct layout shall be as specified.


ONTARIO PROVINCIAL STANDARD DRAWING

Nov 2011 | Rev 1

UTILITIES

DUCT TERMINATION AT BRIDGE APPROACHES

OPSD 3900.150




BOX UNIT CROSS–SECTION

NOTES:

1 For box units reinforced with WWF As1 to As5 shall be as specified.
2 As1 to As4 refer to minimum reinforcement areas required at indicated faces.
3 t = thickness of walls and slabs.
4 d = diameter of perimeter steel reinforcement.
A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2015	Rev	0
PRECAST REINFORCED CONCRETE BOX CULVERT WITH HEIGHT OF FILL ≥ 0.6M	_ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _ _		
	OPSD 3920.100		



BOX UNIT CROSS–SECTION

NOTES:

1 For box units reinforced with WWF As1 to As6 shall be as specified.


2 As1 to As4 refer to minimum reinforcement areas required at indicated faces.


3 t = thickness of walls and slabs.


4 d = diameter of perimeter steel reinforcement.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Apr 2016	Rev	1
PRECAST REINFORCED CONCRETE BOX CULVERT WITH HEIGHT OF FILL < 0.6M			
	OPSD 3920.110		







SPACING FOR LETTERING

NOTES:

1 Centre warning message over centreline of pipe. Adjust layout of message to suit. Lettering to be set in concrete.

A This OPSD to be read in conjunction with OPSD 3940.151.


B All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING


FIGURES IN CONCRETE WARNING MESSAGE LAYOUT

Nov 2010 | Rev 2

OPSD 3940.150



TYPICAL CROSS SECTION



NOTES:

1 See first occurrence of letter E for dimensions.


A This OPSD to be read in conjunction with OPSD 3940.150.

B The letters shall be formed from cast acrylic sheet or high impact styrene that shall not stain the concrete and are non–absorbent.


C 2mm dia holes for fastening letters to formwork shall be provided in locations shown.

D All dimensions are in millimetres unless otherwise shown.


ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev	3
FIGURES IN CONCRETE WARNING MESSAGE LETTERS			
			OPSD 3940.151




PLAN
BRIDGE




ELEVATION
BRIDGE



ELEVATION
RETAINING WALL



ELEVATION
CULVERT



DETAIL

NOTES:


A Figure forms shall be cast on the bridge fascia or face of culvert top slab or outside face of retaining wall.

B "DATE" shall be the original year of construction.

C Numbering and format are provided as an example only. Numbering and format shall be as specified by the owner.


D All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2020	Rev 3
FIGURES IN CONCRETE SITE NUMBER AND DATE LAYOUT		OPSD 3941.200




ELEVATION

CONSTRUCTION JOINT IN DECK




PLAN

CONSTRUCTION JOINT IN WALL



ELEVATION

EXPANSION JOINT IN FOOTINGS



PLAN

EXPANSION JOINT IN WALL

NOTES:

1 Cold applied joint sealing compound and external waterstop shall be as specified.

2 Asphalt impregnated fibre boards shall be held in place with galvanized nails.

A All dimensions are in millimetres unless otherwise shown.

ONTARIO PROVINCIAL STANDARD DRAWING	Nov 2011	Rev	1
JOINTS CONCRETE EXPANSION AND CONSTRUCTION ON STRUCTURE			
	OPSD 3950.100		

Ontario Provincial Standards Unit
301 St. Paul St., 2nd Floor North
St. Catharines, ON L2R 7R4

REVISION INFORMATION SHEET

ONTARIO PROVINCIAL STANDARDS FOR ROADS AND PUBLIC WORKS

VOLUME 3
DRAWINGS FOR ROADS, BARRIERS, DRAINAGE, SANITARY SEWERS, WATERMAINS, AND STRUCTURES

MANUAL REVISION No. 81 **NOVMEBER 2022**

UPDATING ONTARIO PROVINCIAL STANDARDS FOR YOUR USE

Each roads and public works owner (Owner) is responsible for determining implementation dates and directions for use of Ontario Provincial Standards; therefore, manual holders are cautioned about immediately discarding superseded and cancelled standards.

ACCESSING AND OBTAINING ONTARIO PROVINCIAL STANDARDS

Individual OPS standards, revision packages, and complete manuals are available for download, free of charge, in PDF format, from the MTO Technical Publications website.

WAITING TO HEAR FROM YOU

Further news and information about the Ontario Provincial Standards organization can be obtained from the OPS website at www.ops.on.ca.

Questions should be directed by email to Ontario.Prov.Standards@ontario.ca

If you have a suggestion to revise a standard or you have a standard that works in your ministry, municipality, or area, send it to the OPS Administration, for review and possible inclusion into the Ontario Provincial Standards.

THIS MANUAL IS REVISED AS FOLLOWS:

Index Pages Volume 3

Please remove the entire index and replace with the attached revised index.

Standard Drawings Volume 3

Superseded/Cancelled (Remove)		Revised/New (Insert)		Remarks
OPSD	Date	OPSD	Date	
203.040	Nov 2017	203.040	Nov 2022	**Embankments Over Swamp at Culverts ≤ 1500mm** • Note B removed, all measurements are included within the drawing, making Note B redundant.
219.200	Nov 2015	219.200	Nov 2022	**Sandbag Flow Check Dam** • Trench requirement shown throughout drawing. • Section B-B: amended to reflect Section A-A of OPSD 219.150 to allow for clearer reading.
219.210	Nov 2015	219.210	Nov 2022	**Temporary Rock Flow Check Dam, V-Ditch** • Section A-A: measurements moved to make interpretation easier, modelled after Section A-A of OPSD 219.211. Actual measurements not changed.
219.231	Nov 2015	219.231	Nov 2022	**Temporary Berm Barrier for Slope Drain** • See Summary of Revisions.
219.260	Nov 2015	219.260	Nov 2022	**Turbidity Curtain** • Note 1 added, regarding additional ballasts potentially being needed depending on local conditions.
219.261	Nov 2015	219.261	Nov 2022	**Turbidity Curtain, Seam Detail** • Note 1 added, regarding additional ballasts potentially being needed depending on local conditions.
222.020	Nov 2013	222.020	Nov 2022	**Large Woody Debris** • See Summary of Revisions.
222.030	Nov 2013	222.030	Nov 2022	**Stone LUNKERS** • See Summary of Revisions.
222.040	Nov 2013	222.040	Nov 2022	**Wood LUNKERS** • See Summary of Revisions.
922.161	Apr 2016			**Energy Attenuator, End Treatment, Steel Beam Energy Attenuating Terminal, MASH SoftStop Terminal System, Installation** • This drawing is cancelled, as it is no longer needed. OPSD 922.165 is an updated MASH SoftStop Terminal system drawing that is available for use.

Superseded/Cancelled (Remove)		Revised/New (Insert)		Remarks
OPSD	Date	OPSD	Date	
922.165	Nov 2018	922.165	Nov 2022	**Energy Attenuator, End Treatment, Steel Beam Energy Attenuating Terminal, MASH SoftStop Terminal System, Installation** • Elevation view: MASH SoftStop Terminal impact head revise to have an upward tilt towards the front to the system.
973.130	Nov 2016	973.130	Nov 2022	**Fence, Steel Beam, Barricade, Installation** • See Summary of Revisions.
		973.131	Nov 2022	**Wildlife Fence, Type A, With Apron of Type B Fence Fabric** • New drawing.
		973.132	Nov 2022	**Wildlife Fence, Type A, Access Gate** • New drawing.
		973.133	Nov 2022	**Wildlife Fence, Type B, on Steel Posts, Installation** • New drawing.
		973.134	Nov 2022	**Wildlife Fence, Type B, on Wooden Posts, Installation** • New drawing.
		973.135	Nov 2022	**Wildlife Fence, Type A, Installation** • New drawing.
		973.140	Nov 2022	**Wildlife Fence, Steel Post Footing Details** • New drawing.
		973.141	Nov 2022	**Wildlife Fence, Wooden Post Installation Details** • New drawing.
		973.142	Nov 2022	**Wildlife Fence, Miscellaneous Details** • New drawing.
		973.143	Nov 2022	**Wildlife Fence, Tie-In at Culverts or Wildlife Crossing Structures** • New drawing.
		973.144	Nov 2022	**Wildlife Escape** • New drawing.
		973.145	Nov 2022	**Wildlife Fence, Type B, Fence End Turnaround** • New drawing.
3310.150	Nov 2011			**Deck, Girders, Concrete, Positive Movement Connection at Piers** • This drawing is cancelled, as it is no longer relevant to construction projects and is no longer used.

Superseded/Cancelled (Remove)		Revised/New (Insert)		Remarks
OPSD	Date	OPSD	Date	
3332.100	Nov 2011	3332.100	Nov 2022	**Deck, Round Voids, Form Supports and Tie-Downs** • Note B: reference to hot-dip galvanizing according to OPSS 911 replaced with 'as specified'.
3339.100	Nov 2017	3339.100	Nov 2022	**Deck, Voids, Access Hatch for Concrete Bridges Assembly** • Note B: amended to require metal be hot-dip galvanized as specified.
3340.150	Nov 2012	3340.150	Nov 2022	**Deck Drains with Transverse Bar Openings** • See Summary of Revisions.
3340.201	Nov 2012	3340.201	Nov 2022	**Deck Drains with Sloped Downspout Modification for Addition of Asphalt to Existing Structure** • See Summary of Revisions.
3340.250	Nov 2012	3340.250	Nov 2022	**Deck Drains with Transverse or Longitudinal Bar Openings, Modification for Addition of Asphalt to Existing Structure** • See Summary of Revisions.
3349.100	Nov 2012	3349.100	Nov 2022	**Deck, Drains, Drainage of New Deck Below Asphalt Wearing Surface** • See Summary of Revisions.
3349.101	Nov 2012	3349.101	Nov 2022	**Deck, Drains, Drainage of Existing Deck Below Asphalt Wearing Surface** • See Summary of Revisions.

SUMMARY OF REVISIONS

OPSD 219.231

Temporary Berm Barrier for Slope Drain

- Anchor trench added to both Plan View and Section A-A.
- Note that trench shall be backfilled and compacted added to Section A-A.
- Note that 450mm of geotextile or plastic sheeting shall be used in the trench added to Section A-A.

OPSD 222.020

Large Woody Debris

- Title amended to match title of associated specification (OPSS.MUNI 811).
- Plan View: arrow for back of excavation adjusted to be more exact.
- Section View: label for back of excavation added. Backfill stone and intertwined large woody debris measurements amended to “as specified” to reflect changes in associated specification.
- Note regarding measurements removed.

OPSD 222.030

Stone LUNKERS

- ‘Waterbody bed’ replaced by ‘streambed’ throughout the drawing.
- ‘Previously excavated bank material’ replaced with ‘excavated bank material’ to be in line with the associated specification.
- ‘Large backfill stone’ replaced with ‘Waterbody aggregates as specified’, as per changes made to the associated specification.
- ‘As specified’ added to ‘erosion control measures’.
- Measurement added to the 250 mm indicator in the Schematic View.
- Note B removed as all dimensions and measurements are noted in the drawing.

OPSD 222.040

Wood LUNKERS

- ‘Waterbody bed’ replaced by ‘streambed’ throughout the drawing.
- ‘Previously excavated bank material’ replaced with ‘excavated bank material’ to be in line with the associated specification.
- ‘Large backfill stone’ replaced with ‘Waterbody aggregates as specified’, as per changes made to the associated specification.
- Measurement added to the 50 mm indicator in the Schematic View.
- Note B removed as all dimensions and measurements are noted in the drawing.

OPSD 973.130

Fence, Steel Beam, Barricade, Installation

- Elevation view: steel beam guide rail revised from OPSD 912.101 to OPSD 912.125, terminal section revised to rounded terminal, slice bolts and nuts labeled, wooden posts revised to steel posts, and

optional checkerboard sign moved to the right of centreline of roadway
- Side view: wooden post revised to steel post and steel beam guide rail mounting height revised.
- Terminal Section view deleted.
- New Note 1 added.
- Existing Notes A, B, and C deleted. Other note reordered.

OPSD 3340.150

Deck Drains with Transverse Bar Openings

- Note A: amended to remove external reference and replaced with ‘as specified’.
- Note B: reference to external standard updated to reflect preferred formatting.
- Note 1: amended to remove reference to Contractor as per OPS preferences.
- Asphalt hatching edited to reflect OPS preferences.
- Breaks and arrows amended to reflect OPS preferences.

OPSD 3340.201

Deck Drains with Sloped Downspout Modification for Addition of Asphalt to Existing Structure

- Note A: reference to external standard updated to reflect preferred formatting.
- Note C: amended to be hot-dip galvanized as specified.
- Asphalt hatching edited to reflect OPS preferences.

OPSD 3340.250

Deck Drains with Transverse or Longitudinal Bar Openings, Modification for Addition of Asphalt to Existing Structure

- Note B: amended to indicate that the modification assemble shall be hot-dip galvanized as specified.
- Asphalt hatching edited to reflect OPS preferences.

OPSD 3349.100

Deck, Drains, Drainage of New Deck Below Asphalt Wearing Surface

- Asphalt hatching edited to reflect OPS preferences.
- References to ‘coupler’ throughout the drawing replaced by ‘flexible coupler’.
- Note 1: amended to remove reference to external standard, replaced with ‘all metal parts shall be galvanized as specified’.

OPSD 3349.101

Deck, Drains, Drainage of Existing Deck Below Asphalt Wearing Surface

- Asphalt hatching edited to reflect OPS preferences.
- Reference to ‘coupler’ throughout the drawing amended to ‘flexible coupler’.
- Note 1: amended to remove reference to external specification, replaced with ‘as specified’.
- Note A: reference to Contractor and statement covered by General Conditions removed.